

AUSTRALIA'S LARGEST-SELLING ELECTRONICS & HI-FI MAGAZINE

# ELECTRONICS

## Australia

AUGUST, 1973

New Zealand 75c

60c\*

Registered for posting as a periodical — Category B

**STEREO HEADPHONE ADAPTER \* CORE BALANCE RELAYS  
TRIGGER FOR TIME-LAPSE MOVIES \* VHF CONVERTER**





# Sony conducts you to excellence

**-with the  
TC-377  
tape deck  
and the  
TA-1150  
amplifier**



Two classic new Sony components for a music system of concert hall fidelity. The gleaming TA-1150 integrated stereo amplifier has a frequency range of 20-20,000 Hz with 30W per channel RMS. Harmonic distortion is less than 0.2% at rated output. Two tape recorder inputs, and latest push button controls on its beautifully engineered cabinet. The slant-front\* Sony TC-377 tape deck has Sony's new Ferrite and Ferrite heads for up to 200 times longer wear. Frequency response from the three heads — crase, record and playback — is extended to 20-30,000 Hz with outstanding signal to noise ratio. Automatic total mechanism shut off device. Microphone/line mixing facility. With so many functional and satisfying features the TC-377 will maintain its superior characteristics for years. And ears. Like yours.

\*Can also be used horizontally by reversing the case.



TA-1150



TC-377

Share the Sony secret — of excellence.

# SONY®

**JACOBY**   
**KEMPTHORNE**  
**SERVICES**

SYDNEY: 26 2651, MELBOURNE: 329 6866, ADELAIDE: 93 2338 9, BRISBANE: 44 4488, PERTH: 81 3422, LAUNCESTON: 2 5322, Agents: CANBERRA: 47 9010, NEWCASTLE: 61 4991, FAIRY MEADOW: 84 8022.

**For further information please fill in the Reader Service coupon in this issue.**





# ELECTRONICS Australia

Australia's largest-  
selling electronics  
& hi-fi magazine

VOLUME 35 No 5



More and more hi-fi enthusiasts are using stereo headphones. Join them, by building our new adapter. See p.34.



A computer directs this newspaper delivery truck, as our story on p.24 explains.

## On the cover

Taken at the recent 8th International Television Exhibition in Montreux, Switzerland, this picture shows two new Philips products being demonstrated. At left is the new LDK-15 portable Plumbicon colour camera, while at right is the new infra-red portable link unit.

(Courtesy Philips Industries Ltd)

## CONTENTS — AUGUST 1973

### world of electronics and hi-fi

- 3 Editorial: Should Parliament be televised?
- 16 Japan entering the era of "Total Communications" — 2
- 20 Lee de Forest: idealistic "Father of Radio"
- 24 Computer delivers the newspapers — with a little help
- 26 Core-balance earth fault protectors for greater safety
- 55 Forum: enlarger timers — what is a half stop?

### projects and technical

- 28 Simple converter for the VHF bands
- 34 New universal headphone adapter unit
- 39 Mains monitor — measure the mains in safety
- 43 Digital clock — suggested modifications
- 46 An introduction to marine acoustics — 2
- 51 Auto-trigger: control unit for time-lapse movies
- 59 Circuit and Design Ideas:
  - Modifications to photographic timer — simple electronic dice — precision tachometer squelches point bounce — DC matching of complementary pairs — another constant impedance attenuator.*
- 62 The serviceman: beware the obvious symptoms
- 69 Home study course: Early television systems — 2
- 77 Elementary electronics: equip your car with a burglar alarm.
- 101 Product reviews and releases:
  - Technics 1200 direct drive turntable — Philips SM130 sound module loudspeakers — Philips RH 521 stereo amplifier — Hewlett-Packard LED indicators — Goodmans Minister loudspeakers — McMurdo IC breadboard.*

### regular features

- 8 News highlights
- 83 Record reviews — classical
- 89 Record reviews — devotional, popular, jazz, rock
- 110 Books and literature
- 112 Amateur band news and notes
- 118 Listening to the world
- 121 Answers to correspondents
- 126 Marketplace — classified advertising
- 127 E-A guide to component stockists
- 128 Index to advertisers
- 123 Notes and errata





# Potcores not pot luck

Remember when choosing a potcore meant selecting from upwards of 2,000 cores? Duplication abounded. There were delays in delivery. Remember?

Now ELCOMA change all that.

By analysing customer preferences, we've been able to rationalise our entire potcore range.

Now we have 308 different types of potcores. We've called them the Philips "P" Series.


They're all listed in a handy ready reference for easy selection.

We've also a preferred range covering the series P18 and P26 supplied with AL factors (all with corresponding  $\mu_e$  values) and made here in Australia at our Hendon plant.

Get the booklet that details the entire ELCOMA range. It's yours free when you write to:

**ELCOMA, P.O. Box 50,  
LANE COVE, N.S.W. 2066**

\* Pack quantities in sets of 10 pairs or 20 halves.



## PREFERRED RANGE

### P18/11 POTCORES—PRE-ADJUSTED PAIRS

Catalogue Number 4322.022	Grade of Ferroxcube	AL Factor	Corresponding $\mu_e$ Value	Tolerance on Inductance %	Adjustor Type 4322.021	Adjustor Colour
25040	3B7	100	47.5	$\pm 1$	30770	Red
25050	3B7	160	76	$\pm 1$	30960	Yellow
25080	3B7	250	119	$\pm 1.5$	30970	White
25070	3B7	315	149	$\pm 2$	30730	Brown
25230	3H1	63	30	$\pm 1$	30760	Green
25250	3H1	180	76	$\pm 1$	30960	Yellow
25260	3H1	250	119	$\pm 1.5$	30970	White
25270	3H1	315	149	$\pm 2$	30730	Brown
25280	3H1	400	190	$\pm 2$	31080	Grey
25300	3H1	630	298	$\pm 3$	31080	Grey
04000	3B7	3673	1750	$\pm 25$	—	—
04200	3H1	3673	1750	$\pm 25$	—	—

### SEPARATE POTCORE HALVES

4322 020 21500	3B7	$\geq 2770$	$\geq 1310$	—	—	—
4322 020 21510	3H1	$\geq 2770$	$\geq 1310$	—	—	—

### P26/16 POTCORES—PRE-ADJUSTED PAIRS

Catalogue Number 4322.022	Grade of Ferroxcube	AL Factor	Corresponding $\mu_e$ Value	Tolerance on Inductance %	Adjustor Type 4322.021	Adjustor Colour
29080	3B7	400	127	$\pm 2$	30810	Brown
29260	3H1	250	79.5	$\pm 1$	30980	White
29270	3H1	315	100.2	$\pm 1.5$	30980	White
29280	3H1	400	127	$\pm 2$	30810	Brown
29300	3H1	630	200	$\pm 3$	30810	Brown
29310	3H1	1000	318	$\pm 3$	31090	Grey
08000	3B7	6009.3	1910	$\pm 25$	—	—
08200	3H1	6009.3	1910	$\pm 25$	—	—

### SEPARATE POTCORE HALVES

$L = N^2 AL (10^{-9} H)$

4322 020 22000	3B7	$\geq 4504.3$	$\geq 1430$	—	—	—
4322 020 22010	3H1	$\geq 4504.3$	$\geq 1430$	—	—	—

# ELCOMA

ELECTRONIC COMPONENTS AND MATERIALS  
Sydney, Melbourne, Brisbane, Adelaide, Perth

# PHILIPS

153.20





## EDITORIAL VIEWPOINT

### *Should Parliament be televised?*

#### EDITOR-IN-CHIEF

Neville Williams  
M.I.R.E.E. (Aust.) (VK2XV)

#### EDITOR

Jamieson Rowe  
B.A. (Sydney) B.Sc. (Technology, NSW)  
M.I.R.E.E. (Aust.) VK2ZLO / T

#### ASSISTANT EDITOR

Philip Watson  
A.M.I.R.E.E. (Aust.) (VK2ZPW)

#### EDITORIAL STAFF

Ian Pogson (VK2AZN / T)  
Leo Simpson  
Robert Flynn  
Fred Stirk, M.I.R.E.E. (Aust.) (VK2ABC)  
Ross Tester

#### ADVERTISING MANAGER

Selwyn Sayers

#### CIRCULATION MANAGER

Alan Parker

In recent weeks the daily press has carried reports of the sittings of the "Joint Parliamentary Committee on the Broadcasting of Parliamentary Proceedings," which has been looking into the question of televising Parliament. The reports have been generally quite small, presumably because the newspapers regard the matter as one of minor consequence. I would like to challenge this judgment, and also some of the submissions which seem to have been made.

One report quoted various members and senators as arguing against protracted TV coverage of parliamentary proceedings. Their reasons generally went along the lines that a member making a speech would look ridiculous if the public could see that the House was almost empty, along with doubts about the ability of the public to "correctly interpret" what they might see.

Another report concerned a submission by the Australian Broadcasting Control Board. This apparently contained the results of a survey showing that a majority of the public wanted TV coverage of Parliament, together with a board recommendation that full coverage would not be desirable. The main reasons for the recommendation were apparently that full coverage would be costly and would be likely to attract only a relatively small number of viewers.

It seems to me that both the parliamentary spokesmen and the ABCB have overlooked an important point: the rights of the viewers as citizens. Surely every citizen has the right to see and hear for himself or herself what goes on in their parliament, and they have the right to see all proceedings, not just carefully selected and arranged "highlights."

Let's face it, a member delivering a speech to a near-empty house is being projected into a rather ridiculous situation. But the remedy is not to prevent people from seeing this; it is to alter parliamentary procedure to do away with this sort of situation. And this is far more likely to occur if people become aware of the situation.

It should be our ultimate aim, I believe, to televise not only Federal Parliament but the proceedings of state and local governments as well. Only when all citizens have full and uncensored access to these forums are we likely to generate much motivation to improve the quality of government.

The only legitimate qualification to this is cost. It may well be some time before Australia can afford the additional broadcasting facilities to implement this aim.

— Jamieson Rowe

ON SALE THE FIRST MONDAY OF EACH MONTH

Printed and published by Sungravure Pty Ltd of Regent Street Sydney, at Morley Avenue, Rosebery, NSW.

\*Recommended and maximum price only.

#### Editorial Office

12th Floor, 235-243 Jones Street, Broadway, Sydney, 2007 Phone 2 0944. Postal Address: PO Box 157, Beaconsfield 2015.

#### Advertising Offices

Sydney — 57-59 Regent St, Sydney 2008. Phone 699 3622.

Sydney representative:

Dale Menser

Melbourne — 374 Little Collins Street, Melbourne, 3000. Phone 67 7021.

Melbourne representative: Jeffrey Byrne.

Adelaide — Charles F. Brown & Associates Ltd, 429 Pulteney Street, Adelaide, 5000. Phone 23 1657.

Adelaide representative: Tom Duffy.

Perth — 454 Murray Street, Perth, 6000. Phone 21 8217.

Perth representative: Jack Hansen.

#### Representation

Melbourne — Sungravure Pty Ltd, 392 Little Collins Street. Phone 67 7021.

Brisbane — Sungravure Pty Ltd, 78 Elizabeth Street. Phone 21 6690.

Adelaide — Sungravure Pty Ltd, 104 Currie Street, Phone 51 6422.

Perth — Sungravure Pty Ltd, 454 Murray Street. Phone 21 8217.

Newcastle, NSW — Associated Newspapers Ltd, 22 Bolton Street. Phone 2 3696.

London — John Fairfax and Sons (Aust) Ltd Reuter Building, 85 Fleet Street.

New York — "The Sydney Morning Herald" Ltd, 1501 Broadway, New York NY 10036.

#### Subscriptions

Subscription Dept, 21 Morley Ave, Rosebery, NSW. Phone 663 3911.

Rates and order form given on page 126.

#### Circulation Office

9th Floor, 235-243 Jones Street, Broadway, Sydney, 2007. Phone 2 0944.

#### Distribution

Distributed in NSW by Sungravure Pty Ltd. 57-59 Regent St, Sydney; in Victoria by Sungravure Pty Ltd, 392 Little Collins Street, Melbourne; in South Australia by Sungravure Pty Ltd, 104 Currie Street, Adelaide; in Western Australia by Sungravure Pty Ltd, 454 Murray Street, Perth; in Queensland by Gordon and Gotch (A'asia) Ltd; in Tasmania by Mercury Newspaper Pty Ltd Macquarie St, Hobart; in New Zealand by Gordon and Gotch (NZ) Ltd, Adelaide Rd, Wellington.

All manuscripts, photographs and other material submitted to Electronics Australia for publication must be accompanied by a stamped, addressed envelope. Contributions are submitted at the sender's risk, and Electronics Australia cannot accept responsibility for loss.

#### Copyright. All rights reserved.

Devices or arrangements shown or described herein may embody patents. Information is furnished without responsibility for its use and without prejudice to patent rights.



# The History Savers at work.



David Hall and Sam Sanders discuss a fine point.

Deep inside a building at New York's Lincoln Center for the Performing Arts, recorded history is being recorded again. At the Rodgers and Hammerstein Archives of Recorded Sound, technician Sam Sanders is busy continually transcribing all sorts of old recordings, transcriptions and acetates. Not only will there then be a more permanent record of this valuable material, but access to it is made easy through a sophisticated catalogue system, by which interested persons can hear material that was otherwise unavailable.

The Rodgers and Hammerstein Archives of Recorded Sound are part of the New York Public Library, Research Library of the Performing Arts, and encompass virtually the entire history of recorded sound. But to get these early (and often irreplaceable) discs onto tape wasn't easy. Because until the recording industry established its own standards, playing speeds, groove widths and depths were widely varied.

Stanton engineers worked closely with Archive Head David Hall and engineer Sam Sanders



when the Archive Preservation Laboratory was being set up. Standard Stanton 681 cartridge bodies were chosen for their superior reproduction characteristics. However, some 30 different stylus types had to be prepared to give the tape transfer operation the variety needed to match the various old groove specifications. Each was hand-made by Stanton engineers to fit a particular disc's requirements. So when Sam Sanders begins the careful disc-to-tape transfer, he must first match the stylus to the record. Both microscope and trial-and-error techniques must be often used together. But one of the special styli will enable every last bit of material to be extracted from these recorded rarities.

It goes without saying that a company willing to take such care in helping to preserve recorded history must also be interested in superior reproduction of today's high fidelity pressings. Which is one reason why Stanton cartridges remain the choice of professionals the world over.

Interstate Distributors


QLD: Brisbane Agencies, 21 9139  
N.S.W.: W.C. Wedderspoon Pty. Ltd. 29 6681  
VIC: B.J.D. Electronics Pty. Ltd. 30 4689  
S.A.: Sound Spectrum Pty. Ltd. 23 2181



Sole Australian Distributors—**LEROYA INDUSTRIES PTY. LTD.**, 266 Hay St., Subiaco, Western Australia 6008

LERO41





## Say it again, Stan— We love the sound of your words!

As a matter of fact, Stanton has so many wonderful quotes on the warranty cards that purchasers send in, that we are letting them write this ad.

"The best sound I have ever heard from my sound system — fantastic!"

Jeff E. Booker, 4425 N. 150th St., Brookfield, Wis. 53005

"Very comfortable. Stylish, Excellent Sound."

Gary A. Wanlin, 3266 Cropley Ave., San Jose, Calif. 95132

"Absolutely Great—especially by comparison."

John E. Robinson, 199 Middle Rd. F, Portland, Me.

"The headphone is the best I've heard."

Eddy Schreyer, 5701 Cahill Ave., Tarzana, Calif. 91356

"Good sound, much better than other comparable brands. Excellent design."

Terry Ames, 2602 Calhoun St., Alameda, Calif.

"Excellent bass response. Comfortable headset."

Phil Lulewicz, 15335 Stetson Rd., Los Gatos, Calif. 95030

"The most amazing, most natural sound I've ever heard."

Stephen Sandoz, 6815 S.W. 12th Ave., Portland, Oregon

"Excellent. Best I've listened to."

J. L. Hubbard, 3625 Pine, Long Beach, Calif.

"The best I have ever used or heard."

Howard J. Millbank, 2260 Adair St., San Marino, Calif. 91108

"Sound quality is vibrant and separation is excellent. Prefer Stanton over [censored]"

Thomas L. Saunders, 2408 Phillips Dr., Alexandria, Va. 22306

"Excellent performance. Fantastic Power handling capability."

Todd Sadow, 20 Black Hawk Road, Scarsdale, N.Y. 10583

"The best I have ever heard."

Ronnie Lustig, 933 Percy Warner Blvd., Nashville, Tenn.

"Excellent, best I have ever heard."

Richard Sirois, 508 S. Michigan, Plymouth, Ind.

"Excellent."

Florence A. Davis, 191 Congress Ave., Providence, R.I.

"Excellent."

Steven D. Melchior, 4540 Hazeltine Ave., No. Hollywood, Calif.

"The headset is the most comfortable and best sounding I have seen."

Craig Biggs, 285 Andsbury Ave., Mt. View, Calif. 94040

"The best of 20+ headsets tested."

Michael Fink, 17162 Erwin Lane, Huntington Beach, Calif. 92647

"FANTASTIC!"

Brian D. McCarty, 364F Vinton Ave., Palms, Calif. 90034

"FANTASTIC!"

James P. Schwider, 5520 W. 190th St. 151, Torrance, Calif. 90503

And, that is only a sampling...  
we have thousands more!

Interstate Distributors:

QLD: Brisbane Agencies, 21 9139

N.S.W.: Leroya Industries Pty. Ltd. 521 6254

VIC: B.J.D. Electronics Pty. Ltd. 30 4689

S.A.: Sound Spectrum Pty. Ltd. 23 2181



**STANTON**

"Manufacturers of the World Famous Stanton Calibration and Professional Broadcast Cartridges."

Sole Australian Distributors—**LEROYA INDUSTRIES PTY. LTD.**, 266 Hay St., Subiaco, Western Australia 6008

LERO44

ELECTRONICS Australia, August, 1973





# 40,000 TECHNICIANS CAN'T BE WRONG!

- More than 40,000 ambitious men have benefited from A.R.T.C. training.
- Join this large number of successful men!
- Attain job security and financial reward.
- These can only be yours from:

AUSTRALIA'S

## ESTABLISHED ELECTRONICS COLLEGE

THE AUSTRALIAN RADIO & TELEVISION COLLEGE PTY. LTD.

- ESTABLISHED OVER 40 YEARS
  - OVER 15 FULL TIME STAFF TO ASSIST YOU
  - FULL NIGHT-CLASS PRACTICAL LESSONS
- OR
- EXTENSIVE CORRESPONDENCE TRAINING WITH SPECIAL PRACTICAL HOME-TRAINING KITS

**Mail Coupon NOW**

• You are invited to mail the coupon below which can be your first step towards securing a job or business of your own with good prospects, security and big money. A.R.T.C. will mail to you by return, at no obligation to you the big free booklet: "Careers in Radio and Television". This booklet will show you definite steps you can take for a better job, how you can succeed in life. Post the coupon, phone or call NOW.

**AUSTRALIAN RADIO  
AND TELEVISION  
COLLEGE**

PTY. LTD.

E.S.&A. BANK BUILDING,

Cnr. Broadway and City Road, Sydney.  
(Opp. Grace Bros). Phone 211-4244 (3 lines)



**AUSTRALIAN RADIO & TELEVISION  
COLLEGE PTY. LTD.**

206 Broadway, Sydney, N.S.W.


Dear Sir,

Please send me, without obligation, your free booklet, "Careers in Radio, TV and Electronics".

NAME .....

ADDRESS .....





## Work of art 1375

Microelectronic art:  
a microscopic memory cell shown 200,000  
times actual size. Part of an AWA computer-  
designed integrated circuit. 1300 components  
storing 64 bits of information, and a power  
requirement of only 200 microwatts.

The advanced technology of AWA Micro-

electronics, established since 1965, gives  
Australia its only complete IC custom design  
and fabrication facility. Now supplying  
integrated circuits for equipment ranging from  
cardiac pacemakers to navigational-aid systems.

The real art in electronics is not just your  
point of view, it's also your capability.



Distributed by  
Amalgamated Wireless Valve Co. Pty. Ltd.

your experts in the art of electronics





# NEWS HIGHLIGHTS

## Success for Australian-made colour monitor

An Australian-made 19-inch (49cm) precision colour TV monitor — type LDN 5006 — was unveiled to the television broadcasting world by Philips at the recent 8th International Television Exhibition at Montreux, Switzerland. Some 18 monitors, specially air-freighted from Australia for the Show, were used as part of the huge Philips display. Visitors to the exhibition were singularly impressed by the quality performance of the new monitor — in particular, its superior colour matching capability. Interest in the monitor has since resulted in potential sales of about 200 units for export to five different countries.

Designed and manufactured by Electronic Engineering Communications, a Melbourne-based (Oakleigh South) division of Philips Industries Holdings, the LDN 5006 has been approved by the parent company in the Netherlands as the standard precision monitor. It will be marketed internationally by the world-wide Philips organisation and in Australia by the Philips Vision and Sound division in Melbourne.

At the exhibition Philips also gave an interesting demonstration of remote wireless control of a new colour camera — type LDK 15 — which features a new image intensifier plumbicon assembly allowing broadcast quality pictures to be produced at extremely low light levels. For the budget-conscious broadcaster, Philips also released two new products — a low-cost colour camera — type LDH 20 — and a cassette audio recorder / reproducer which uses standard format audio cassettes.

Pushing the "innovation" theme, Philips showed a portable, lightweight infra-red beam video link that provides interference-



*The Philips exhibit at Montreux. All professional colour monitors used were the Australian designed and built LDN 5006.*

free and low noise broadcast transmission at low cost. Intended for short-haul (up to 1500 metres) program transmission, the link is also a useful companion to the LDK 5 or LDK 15 cameras where even a triaxial cable connection may on special occasions,

be inconvenient.

Another new release was the N1520 video cassette recorder (VCR) which, using the standard European VCR tape format, features insert and assemble editing, stop motion and dual sound track dubbing.

## Satellite helps fight forest fires

One of the oldest threats to life on Earth, forest fires, is now being attacked by the newest of man's tools, space technology. Instruments developed to sense conditions when fires start easily are being teamed with a satellite relay station and computers to give the California Division of Forestry (CDF) a "Fire Index Measurement" from an experimental unmanned remote station in a fire area near Sunol, California.

Foresters say that knowing where fires are probable and how they might act is almost as important as men and equipment actually fighting fires. An unmanned station to establish the fire index in remote areas is doubly important because it gives timely readings which have in the past been made by forestry personnel as only one of their many duties, and it has been a problem for them to get the information to

their headquarters by telephone. Important, too, is the idea that when fires occur, forestry personnel are often pulled into firefighting duties and can no longer monitor their areas.

The new system is based on sensors developed by the CDF and NASA's Ames Research Centre at Mountain View, to check wind velocity and direction, air temperature, relative humidity, and fuel moisture content, a measure of the flammability of forest floor litter. Under an agreement between Ames and the Division Forestry, Ames aerospace technologists have joined the CDF instruments with a NASA "black box" which converts their measurements into data which is beamed to the Earth Resources Technology Satellite (ERTS) at least twice a day.

The ERTS, orbiting Earth every 100

minutes some 915 kilometres (540 miles) overhead, picks up the signals with special receiving equipment. The satellite automatically relays the information to a NASA tracking station in the Mojave Desert which passes it along electronically to NASA's Goddard Space Flight Centre in Maryland. The coded data is sorted out by computer and sent to Ames back in California where it is processed by computer and sent to Forestry headquarters in Sacramento, in a useable form. In the Sunol experiment, the fire index information is passed to Sacramento on a daily basis, but it could be made available within an hour after an ERTS pass if need be.

The sensing unit in the Sunol area has been operating successfully for several weeks and the experiment has been termed by the CDF "highly successful."

The success of the project is also sparking interest in the possibility of using the system to monitor air pollution.



## Hitachi completes tactile robot

The Hitachi Central Research Laboratory in Tokyo, Japan has completed a tactile industrial robot with a flexible wrist and delicate feeling. The robot can insert pistons in cylinders with a clearance of about 20 microns, faster and more deftly than human hands.

In such inserting operations, it is extremely difficult to set the positions of the two objects to be fitted together, and also the small clearance tends to make the two objects freeze to each other to make insertion impossible. Operations requiring clearances measured in microns have been accordingly considered impossible with conventional industrial robots or automatic assembling machines. Generally only skilled human workers can do such operations, which call for delicate feeling rather than good eyesight.

According to Hitachi, their new "HI-T HAND" Expert 1 has been designed with the delicate feeling necessary for such inserting operations. It comprises a main robot with three degrees of freedom of motion, an auxiliary robot with two degrees of freedom, parts supply equipment and a sequence control device.

In the inserting operation, the hands of the main and auxiliary robots each pick up a cylinder and a piston respectively and



*A demonstration of the capabilities of Hitachi's new tactile robot hand.*

seek out the position of the hole in the cylinder. Next, the position of the piston to the hole is fitted and corrections are made in the direction for insertion to prevent freezing.

The operation is carried out with the aid of tactile sensors that feel out the position of the objects to be fitted. (More than 10 patents pending.)

Computers are not used in the operation; only a simple sequence control device. Hitachi claim this is the first time a robot has been given the delicate feeling of the

human hand, making possible the automation of difficult assembling operations in many fields.

Less than 10 seconds is required for the operation from the supply of parts to insertion. Only 3 seconds is necessary for the insertion itself. The sequence of operation with the control device is set by a pin board.

The "HI-T HAND" Expert 1 is scheduled to be announced at the Conference of the Society of Instrument and Control Engineers to be held at Hokkaido University in Japan this month.

## Prime Minister opens new STC plant in Sydney



A new \$3½ million factory and plant installation for Standard Telephones and Cables Pty Limited at Alexandria, Sydney, was opened recently by the Prime Minister, Mr Whitlam. The new plant, of 150,000 square feet over two floors, was built primarily for the development and manufacture of Metaconta IOC electronic public telephone exchange equipment and electronic Minimat private branch exchange (PABX) equipment.

STC won contracts for the supply and installation of Australia's first three electronic trunk exchanges, valued in excess of \$13 million, in open world competition. The first contract, for the new Pitt Street Exchange in Sydney, was followed in 1971 by two further contracts to provide similar equipment for Melbourne and Adelaide. The computer controlled exchanges are designed to handle high usage subscriber trunk dialling facilities, and are claimed to herald a new age in Australian telecommunications.

The Managing Director of STC, Mr A. T. Deegan, said that it was in about 1967 that the Australian Post Office and STC realised that the growth of the trunk network was such that by the early 1970's trunk exchanges would be required in sizes considerably exceeding the economic capacity of the present system.

"Accordingly, we commenced technical discussions with the APO, and following studies of worldwide developments, they were convinced that the correct solution for Australia would be for an electronic system using computer stored program control.

"World wide tenders were called and we were awarded a contract for what is probably one of the world's largest and most advanced trunk exchanges. This is now being installed in the Pitt Street Exchange in Sydney."



## NEWS HIGHLIGHTS

### 200,000 CP from 150W, only 2 cubic inches

An efficient new high-intensity illumination system, based on an exceptionally reliable short-arc xenon lamp, has been developed by Varian Associates of Palo Alto, California. The new lamp measures only two cubic inches but can deliver a peak beam of 200,000 candlepower while consuming only 150 watts.

Varian will market a system that includes the xenon lamp, a power supply and a cooling unit. The company will also design and engineer complete illumination systems to customer specifications, supplying all electrical, mechanical and optical components.

Called the VIX-150, Varian's new xenon lamp is manufactured by the company's Eimac Division. It provides exceptionally consistent, broad-band illumination that spans the UV, visible and IR regions of the spectrum. Wavelength composition of its light is very similar to that of sunlight.

The lamp's efficiency — measured in lumens of output per watt consumed — is three to four times greater than the efficiency of competing designs. Comparable economy has been available heretofore only in an earlier Eimac xenon lamp, the X6207.

Varian says that illumination systems using the new lamp will be ideally suited to clinical, laboratory, photographic and manufacturing applications that demand a dependable source of intense light. Earlier Eimac xenon lamps have been used in optical character readers, surgical light coagulators, photo-etching machines and other advanced devices.

Features of the VIX-150 include long-lasting tungsten-alloy electrodes; a parabolic reflector that is cast into the ceramic body



of the lamp; and an output window made from a single sapphire crystal that is thermally matched to the mating metal parts of the lamp.

The VIX-150's unique integrated construction — the lamp body, electrodes, reflector and window are formed into a single pressurised unit — gives the lamp great mechanical stability. Optical alignment is fixed during manufacture and requires no subsequent adjustment by the user. The finished lamp can be used in any position, unlike some earlier xenon illuminators.

### TV receiver for direct satellite broadcasts

A solid state television set which can be used for community viewing in unelectrified villages, and which incorporates the front-end converter required for direct reception from satellites has been designed and developed by the electronics system division of the Indian Department of Space. Initial field tests have been satisfactory, and the set is now being taken through a production run so as to complete the industrial engineering aspects. It is to be used for India's forthcoming satellite instructional television experiment (SITE).

SITE, on which considerable progress has been officially claimed, involves the broadcasting of Indian instructional TV programs to about 5,000 villages in different parts of the country. About 2,000 sets will be of the direct reception type, capable of receiving signals directly from the satellite. The remaining sets will be located in villages around Delhi, Srinagar, Ahmedabad, and Bombay. Poona where regular TV transmitters exist or are being set up.

TV signals from the satellite will be received in these cities by earth stations and then relayed by conventional TV transmitters for reception by sets located in the villages around.

The experimental satellite communication earth station ESCES will serve as the prime earth station during the experiment. It will be used for transmitting programme materials to the satellite and for monitoring transmissions and the performance of the spacecraft.

ESCES will also coordinate operations with NASA and with the Indian earth stations to be set up for the experiment. The prime station is being modified for the experiment and the UNDP is providing assistance in the form of components, expertise and fellowship.

—N. Viswanath, New Delhi.

### Electronic watch uses 2.4MHz crystal

The Omega watch firm in Switzerland has announced the commercial release of the "Megaquartz 2400" watch, claimed to be the first commercial watch to employ a high frequency quartz crystal and thus be able to offer the performance provided by such a crystal.

Earlier electronic watches have used crystals resonating at audio and supersonic frequencies, from 8192Hz to 65,768Hz, and such crystals tend to be both bulky and prone to excessive temperature drift. The new Omega watch uses a crystal oscillating


at 2.359296 MHz. The crystal is thus not only much smaller than lower frequency units, but also considerably more stable.

Naturally enough, the use of a much higher oscillator frequency requires more divider stages to produce the pulses required to drive the actual watch movement. To achieve this without increasing the power consumption, Omega have used micropower ICs developed jointly with the US firm Intersil, based in Cupertino, California.

The complete divider system uses a transformer and analog divider system for some of the stages, and delivers pulses at 1Hz to drive the micro-miniature stepping motor actuating the movement. The movement itself is designed to allow adjustment of the hour hand without disturbing the accuracy of the minute and seconds hands, for convenient use by international travellers.

Overall dimensions of the movement are 31 x 25.6 x 6mm. Actual precision under normal conditions of use is claimed to be better than one second per month.

At far left is the new Omega 2400 watch, with its movement shown alongside.



### Colour TV, Fortran courses from U.N.S.W.

The Division of Postgraduate Extension Studies at the University of New South Wales is offering two further courses over Radio University, VL2UV, and television University, VITU, commencing in August.

"Colour Television Equipment" is a course designed to present the principles of colour television broadcasting and receiving equipment, and will cover much of the results obtained by the Australian television industry working parties. A basic knowledge of colour television theory to the level of the previous Radio University course will be assumed. The lectures will be by a panel of prominent authorities. Fees for the course are \$15, and enrolments should be made by August 10.


"Basic Fortran IV Programming Part 2" follows on from the first course offered on the Fortran IV programming language, and deals with more advanced concepts. The lecturer is Professor J. M. Blatt. The fees for the course are \$10, and enrolments should be made before August 8.

Address of the Division is PO Box 1, Kensington, NSW 2033.



# BASF CrO<sub>2</sub> CASSETTE RECORDER CC9101

the small machine with the big sound



There's a big new dimension in cassette sound—all packed into the beautifully compact dimensions of the BASF CC 9101 CrO<sub>2</sub> Cassette Recorder.


A difference in sound quality you will actually hear—with any cassette.

Drop in a BASF CrO<sub>2</sub> Cassette and you will hear the extra dynamic range.

Few other recorders of this go-anywhere size can boast as large a speaker, or an amplifier of this power. No other recorder can boast the technical superiority of BASF!

Here are some of the other great features that will make the CC 9101 a natural choice:—

- Automatic or manual recording control.
- Large easy-to-read meter showing recording and battery charge level.
- Only one knob to adjust for output, switching to automatic output and volume.
- DIN connections for remote control microphone, record player, radio amplifier and tape recorder, and for external loudspeaker or headphones.
- Automatic CrO<sub>2</sub> switch.
- Foldaway handle.



And it comes complete with a CrO<sub>2</sub> pre-recorded cassette to introduce customers to the new dimension in sound. BASF CrO<sub>2</sub> tapes increase dynamic range by 80%! Background noise is all but eliminated. CrO<sub>2</sub> is magnetically stable and its smooth regular surface minimises head wear.

**Its Big Brothers are coming!**

The versatile CC 9201 with automatic eject cut-out and instant repeat system. The professional CC 9301, the recorder/radio that can do anything. You know BASF reel-to-reel and cassette tapes—they're the world's finest. Now you have the opportunity of buying the complete BASF Cassette System. Grab it!

## The new dimension in Cassette Recorders



**Distributors: Sydney (Head Office):** Maurice Chapman & Co. Pty. Ltd., 276 Castlereagh St. 2000. **Newcastle:** W. L. Redman Agencies, 11 Hall St., N.S.W. 2300. **Canberra:** Sonny Cohen & Sons, 20 Isa St., A.C.T. 2600. **Melbourne:** Maurice Chapman & Co. Pty. Ltd., 146-150 Burwood Rd., Hawthorn, Vic. 3122. **Brisbane:** Chandlers Pty. Ltd., 399 Montague Rd., West End, Qld. 4101. **Adelaide:** Neil Muller Pty. Ltd., 8 Arthur St., Unley, S.A. 5061. **Perth:** Anderson-Tedco, 11-13B Belmont Ave., Belmont, W.A. 6104. **Launceston:** P. & M. Distributors, 87A Brisbane St., Tas. 7250. **Darwin:** Pflitzners Music House, Smith St., N.T. 5790.

BA2931



Proven reliability, long term stability, long life and guaranteed quality appearance... characteristics that ensure

## **PLESSEY RESIN DIPPED TANTALUM CAPACITORS**

provide lasting service of the highest professional standard

Plessey Series 54 tantalums are particularly suitable for printed circuit board design application in both professional and domestic electronic equipment. Conventional solid tantalum technology is employed in their manufacture, with tantalum oxide dielectric and sintered anode construction. They are available in four different case sizes.

**Temperature Range** Continuous operation at rated voltage from  $-55^{\circ}\text{C}$  to  $+85^{\circ}\text{C}$

**Rated Voltage** 3, 6, 3, 10, 16, 25 and 35

**Capacitance Range** 0.1  $\mu\text{F}$  to 100  $\mu\text{F}$

**Capacitance Tolerance**  $\pm 20\%$

**Humidity Grade** H5 as specified in DEF5011

**Power Factor** 0.2 maximum at 120 Hz

**Leakage Current** 0.05  $\mu\text{A}/\mu\text{F}$  or 2  $\mu\text{A}$ , whichever is greater

Descriptive literature is available on request to the Professional Components Department.

# **PLESSEY**

Plessey Ducon Pty. Limited

Box 2, P.O. Villawood, N.S.W. 2163

Telephone: 72 0133, Telex: 20384

Melb: Zephyr Products Pty. Ltd. 56 7231

Adel: K.D. Fisher & Co. 42 2920

Bris: Douglas Electronics Pty. Ltd. 62 1899

Perth: H.J. MacQuillan Pty. Ltd. 68 7411

Everett Agency Pty. Ltd. 84137

N.Z.: Hamiltonian (N.Z.) 44 169





## Large orders for colour TV equipment

Though colour television is 22 months away, Amalgamated Wireless Aust anticipates its equipment orders in the immediate future will be worth more than \$5 million. The company currently holds orders valued at about \$2.5 million.

Outside broadcast (OB) vans have been ordered by the Australian Broadcasting Commission, Sydney, Amalgamated Television Services Pty Ltd (ATN-7, Sydney), and Herald-Sun TV Pty Ltd (HSV-7), Melbourne.

The outside broadcasting vehicle for the ABC was designed to meet their requirements and was manufactured in Chelmsford, England, by Marconi Communication Systems Limited. The unit has been delivered to the ABC following extensive acceptance tests at AWA's North Ryde plant. This OB vehicle and those for both ATN7 Sydney, and HSV7 Melbourne, have been designed to meet Australian road regulations; care has also been taken to ensure effective operation in the extremes of Australian temperatures. The custom-built vehicles accommodate up to five Marconi Mark VIII automatic colour cameras, full vision and sound mixing



Inside a Marconi colour OB van, of the type ordered from AWA by ATN-7 Sydney and HSV-7 Melbourne.

facilities, video tape recorder, off-air and link equipment.

In addition, AWA has received substantial orders from United Telecasters Sydney Limited (TEN10) for colour television equipment.

Total orders for Marconi Mark VIII colour cameras are in excess of 20. AWA

manufactured and supplied to both national and commercial stations more than 100 television transmitters for monochrome operation. These transmitters were basically designed for colour and the Company is now fulfilling large orders for the up-dating of these equipments for colour performance.

## New telegraph error correcting system

A new potent error correcting system which, for the first time, raises the reliability of radio teleprinter communication over marine and point-to-point radio circuits to a level suitable for connection to international telegraph networks, has been introduced in the UK by Marconi Communication Systems, a GEC-Marconi Electronics company.

Its introduction is claimed to mark the start of a new era in ship-to-shore communication and to represent one of the most significant operational advances in recent years.

Known as Spector, the new system gives ship, mobile and remote HF radio stations using single frequency working, direct access to fixed telegraph networks, which previously has not been practicable. To accommodate all operational requirements, provision is made for two modes of operation — ARQ (automatic repeat on request) for point-to-point, and FEC (forward error correction) for broadcast traffic. Selective calls can be made in either mode.

First orders have already been placed by the British Post Office for installation in coast radio stations communicating with ships in all parts of the world. Spector is also in production for Marconi Marine, who are supplying the system as part of their wide range of marine electronic equipment.

A major factor which has up to now prevented the replacement of most conventional hand morse circuits by radio teleprinter circuits has been the im-

possibility of guaranteeing reliable error-free communication without a radio operator. An unprotected HF radio circuit is liable to interference, fading and bursts of static that often mutilate whole sections of a message. Before connecting such a circuit into a public telegraph or telex network, an effective means of error control is required.

Spector, developed to meet CCIR Recommendation 476 (Revised 72), is designed to do just this. In the ARQ mode, on receipt of mutilated characters it will automatically request a repetition of these characters until they are received correctly, ensuring virtual error free communication.

When used in the broadcast mode with

forward error correction, the system is capable of detecting, and correcting or indicating most errors.

The ARQ mode is normally preferred for ordinary traffic because the transmitted message will be received at the other end with certainty. Under conditions where the distant radio transmitter cannot be used for ARQ or when the same message must be sent to several stations simultaneously, the broadcast mode provides a means of getting the message across with a minimum of errors.

Apart from making available the obvious advantages of radio teleprinter working in terms of speed and the provision of printed copies, Spector enables a coast station to extend an inland telegraph connection to a similarly equipped station anywhere in the world.

## Australia to get "Radio Shack" stores

In recent months Australian electronics enthusiasts, like those overseas, have been hearing mainly bad news about component availability — due to the growing world-wide supply problem. But it looks as if there is at least some good news for local electronics and hi-fi fans: the big US Tandy Corporation has announced plans to set up a chain of its well-known "Radio Shack" stores in Australia.

With over 2,400 stores spread throughout all 50 states of the USA, Tandy Corporation is the largest chain of electronics and hi-fi stores in that country — possibly in the world. They are currently expanding into both Europe and the UK, in addition to the Pacific area. The ultimate plan is to establish about 100 stores in Australia, according to Senior Vice-President Mr Dean Lawrence, who is responsible for the Pacific operation.

Local stores will probably be established on a franchising basis, Mr Lawrence explained. The aim is to employ the highest possible proportion of local people in the organisation.



# Show us a better way to get your degree!



The facilities are great. The lecturers are equal to the best, and you work with them personally.

And when you graduate, you have an assured and well-paid career waiting for you.

That's Duntroon. A gateway to professional life where you are paid from \$2,730 to \$3,785 a year while you are studying for your degree.

The requirements are simple. You need to be under 20 years and holding—or studying for—your Matriculation. And, of course, you must be able to compete successfully for our high entry standards.

The rewards are terrific. You could graduate as a B.E. in either Civil, Mechanical or Electrical Engineering. Or get a Science or Arts degree with the chance to use it in positions ranging from field command to specialised scientific duties; from logistics to communications and planning.

Why not send for our brochure? It will answer those questions you're wondering about.

But hurry—applications close August 22nd.

TOWNSVILLE 71 6784. BRISBANE 31 1031. NEWCASTLE 2 5476. SYDNEY 29 2122. ORANGE 62 1755. WOLLONGONG 28 6492. CANBERRA 47 6530. MELBOURNE 61 3731. GEELONG 9 6780. BALLARAT 32 1614. BENDIGO 43 8008. WARRNAMBOOL 6378. YALLOURN 62 2346. LAUNCESTON 31 1005. HOBART 20 0141. ADELAIDE 23 2891. DARWIN 89 0911. PERTH 22 4355.

## OFFICER ENTRY DUNTROON



*Think about it!*

To: Army Careers Officer  
Box XYZ G.P.O.  
(Capital City)

Please send me a detailed brochure about the Royal Military College, Duntroon.

NAME ..... BIRTH DATE .....

ADDRESS .....

STATE ..... POSTCODE .....

Authorised by the Director General of Recruiting, Department of Defence.

RMC46.FP.63



# DICK SMITH & STAFF — SUPER VALUES

## SPECIAL WITH KITS THIS MONTH

### FREE copy of NEW 'BASIC ELECTRONICS'

This 100 page book has only just come off Electronics Australia's press. It's an excellent follow-on book to any of the kits described here, gives a basic, easy to understand insight into electronics covering radio, t.v. etc. Crammed with illustrations, diagrams etc and normally sells for \$2. This month we're giving it away FREE with any of these kits. Yes a \$2 book for nothing with every kit.

#### 10 in 1 kit



The beaut thing about this one is that you don't need to know a thing about electronics to build radios, amplifiers and oscillator circuits. Ten of them are described, teaching the principles with actual working circuits: 4 radios, a transmitter type circuit and 5 different oscillators. A variety of applications are also covered. Very simple you don't need a soldering iron, a clever spring-grip terminal is used with pre-cut and stripped wires and each terminal is numbered for easy connection. The 20 page booklet tells you how each circuit works and about the parts which include a solar cell, ferrite bar antenna earphone, transformer etc. Some of the circuits can be run from the solar cell but a 1.5V battery (14c extra) is advisable. The kit measures 15"x10 1/2"x2" and costs \$8.95 (P&P 50c) and you get the ideal follow-up book FREE, 'Basic Electronics'.

#### IC 20 in 1 kit



This kit features a specially designed, enlarged integrated circuit (IC) with the top taken off so you can see, just as if you were looking through a powerful microscope, how the capacitor, two resistors, a transistor and diode are placed. Then there are 20 fascinating experiments using

the IC. The kit uses an ingenious see-thru printed circuit idea. The components are mounted on a clear plastic sheet and you simply put the circuit you want to build underneath. You can then see where to run the wires to make the circuit work. No soldering thanks to the clever spring-grip terminals. There's a solar battery, ferrite antenna, speaker and earphone and various other components. You can build 1 and 2 transistor radios, a photo burglar alarm, a light frequency controlled oscillator, an electronic machine gun generator etc. Really educational and will give many hours enjoyment. Circuits can be built over and over again. A 9V battery is needed with this kit (53c extra) \$13.25 (P&P 75c) including FREE \$2 'Basic Electronics'.

#### 150 in 1 The Ultimate kit



How else could we describe this truly magnificent kit which comes complete in a wooden presentation case? The 88 page manual describes 150, yes one hundred and fifty, experiments. No soldering and the kit operates off safe battery supply. An enlarged IC is included (see IC kit above). Kit includes CdS cell, solar battery, d.c. microammeter, speaker, relay, microphone, radio tuner, transformers, two transistors plus IC, potentiometer, slide switch, 15 resistors, 10 capacitors, Morse key etc. Projects include Sensitive galvanometer with IC amplifier, ultra low frequency pulse generator, logic circuits, transistorised voltmeter, IC signal tracer, flickering lamp rainfall indicator, tachometer, garage door transmitter and receiver, electronic harmonica, bongo, physiotherapy shocker, wireless IC burglar alarm. The list goes on and on. Case measures 16"x8 1/2"x3 1/2" \$35.95 (P&P \$2) You'll need a 9V and 2 3V batteries also (85c extra) Dick also gives you FREE 'Basic Electronics' the next step...

#### 50 in 1 Solar Energy Kit

You need nothing extra to be able to build 50 simple yet interesting circuits. Then see what you yourself can dream up! The 50 described cover a variety of circuit types — communications, test, control, indicator and alarm circuits; all designed to teach you the basic principles of electronics. Many of them feature the solar cell (a more reliable one than the last space mission we hope!) The kit contains a generous assortment of components just like those used in space electronics, so there's plenty of opportunities for experimenters. Includes relay, earphone, speaker, meter, transformer etc. 56 page manual and hardwood case. \$21.95 (P&P \$1.00). Batteries 1 x 9V 53c and 2 x 1.5V 14c each extra. Don't forget your FREE Basic Electronics too!

#### GOT A CATALOGUE?

We've already sold thousands, so how come you're managing without one? Most people reckon it's just another catalogue till they see one. Our's is crammed full of goodies, most are illustrated for easy identification. There are useful charts and the transistor spec page is an innovation, saves time sorting through data to make your selection. We charge 50c for the catalogue but you get FREE discount vouchers inside to recover the investment (orders over \$10 qualify for a free catalogue so tell us with your order if you want one). Just mail the coupon and give yourself a surprise!



DICK SMITH (WHOLESALE) PTY. LTD.,  
162 Pacific Highway, Gore Hill, 2065  
Tel: 439 5311 (near Channel 2)

#### DEAR DICK

Please send me your catalogue. I enclose 50c towards the cost plus 25c to cover p&p knowing that it contains special 50c discount vouchers.

NAME .....

ADDRESS .....

.....POST CODE .....

CATALOGUE AVAILABLE AT NO CHARGE TO ORGANISATIONS, RADIO CLUBS, SCHOOLS ETC. APPLYING ON OFFICIAL LETTER HEAD.

#### BOOKS

##### The Philips Pocket Book 1973 edition



Needs little introduction, a 700 page bible of everything made by Philips. Specs, parameters etc. Enormous sections on Tubes, crts, transmitter, microwave, photosensitive nuclear devices etc; semiconductors and ICs (280 pages in this section alone); Components and materials (257 pages). Every hobbyist, engineer, technician, amateur, yes everyone should have one. At \$2.30 it's under 1/2 cent per page! (P&P 50c extra)

##### G.E. Electronic Experimenter's Manual



This one describes some 40 interesting projects, many of which could have industrial applications, (they're not just fun circuits). But first a useful chapter on fundamentals of all the parts — SCRs, diacs, triacs etc. Then the projects are split up into groups: audio, motor-car, games, home and workshop. Typical circuits include CD ignition, burglar alarm, electronic dice, battery operated fluorescent lamp, speed controller, precision thermostat etc. In all 250 pages for just \$3.40 (P&P 50c)

##### G.E. Transistor Manual



We've managed to get a further supply of this hard to get manual. A text book that's in great demand. The 7th edition has 596 pages and covers theory right through to applications in 20 chapters on every semiconductor. Typical chapters include biasing and dc amplifiers, logic, digital circuits, feedback and servo amps., regulated power supplies, unijunctions, tunnel diodes, silicon controlled switches. Various GE specs are also included. \$3.50 (P&P 50c).



# The Era of Total Communications...

Here is the second and final part of our correspondent Gene Gregory's report on the way Japan appears to be leading the world in the "era of total communications". Following on from the first part published last month, he deals here with new telephone technology and developments in optical communications.



In the final analysis, Japan's "Total Communications" revolution depends on a variety of specific advances that will make both transmission and switching equipment less expensive. Since the cost of transmission goes down the more signals that are sent over a given path, the development of two new systems in Japan have critical importance for the development of an integrated communications network: pulse code modulation (PCM) transmission system and the electronic exchange (DEX). The PCM system, highly flexible in nature, provides hybrid transmission of television, videophone, facsimile and data signals without any one set of signals interfering with the others, while high-capacity, high speed electronic switching systems are needed for low cost handling of integrated telephone, data and video systems.

Along with the recent development of the semiconductor industry, the practical use of a sufficiently economical PCM system as a short haul carrier system became feasible. In 1965, the 24-channel PCM system for short trunks was first introduced in Japan. Since exchange offices on toll trunk circuits have been transformed to subscriber toll dialing at a very high speed, the demand for the number of short haul toll trunk circuits has increased remarkably in recent years. But the congestion of cables in underground conduits makes new telecommunications installations in large cities extremely difficult, so that the economical multiplexing of local exchange trunks without requiring underground conduit extension becomes a most important consideration in the expansion or modernisation of existing circuits.

The PCM-24 system meets the requirements for a multiplex system that is at once more economical than conventional carrier systems and capable of being used for still shorter haul toll circuits as a TDM-PCM system. It can be used for all kinds of toll trunks and local exchange trunks by attaching the appropriate trunk relay set, and is easily adaptable for both 2-wire and 4-wire purposes. And, in addition to its advantages as a general telephone circuit, the system can be used for 24-channel 50-baud carrier telegraph or 1,200-baud high speed data transmission.

Since the 24-channel PCM transmission was introduced in 1965, the rapid increase in demand on the system has led to the development of higher capacity PCM systems. A microwave and a pair cable system was developed with a capacity of 240

*JAPANESE COMMUNICATIONS technology in other countries: a satellite communications earth station in New Zealand, built by NEC.*



# Part 2

channels and a bit rate of 16 Mb/sec. More recently, to meet the needs of an expanded system and the high flexibility of hybrid transmission, a 100 Mb/sec system is being developed together with a new type pair cable with improved crosstalk characteristics which will give high flexibility in network planning.

By using pair construction instead of quad, an appropriate combination of stranding pitches of pairs and shielding tape between layers of pairs, a decrease in crosstalk as well as attenuation has been achieved at higher frequencies. Far-end cross-talk on the new cable is reduced more than 10dB compared to cables now in service. The unit construction and unit shield reduce near-end crosstalk and facilitate two-way transmission on a single cable, using both its units.

The PCM signal is obtained either by multiplexing 12 8Mb/sec (120CH) signals of PCM-16M systems, or by coding a TV signal or an FDM super-master group signal by the highspeed coder of this system. For the trunk circuit, PCM systems with speeds of 400-800 Mb/sec are now being developed. The coaxial system and the millimetric waveguide system have a capacity of 800 Mb/sec at a clock frequency of 400 MHz with 4-phase PSK modulation, while a microwave system in the upper band of SHF has a capacity of 400 Mb/sec at a clock frequency of 200 MHz. In these systems four PCM-100M signals are multiplexed and transmitted.

Transmission tests on these systems have been successful, using prototype equipment, including a 100-400 Mb/sec multiplexer, and regenerative repeaters of cable, millimetric, and microwave systems. By using these high-capacity systems in trunk circuit and the PCM-100M system for transmission in short haul links, a flexible integrated network for video, voice and data signal transmission will be developed.

Millimetric waveguide systems, which transmit wideband signals at a notably low attenuation by using the TE<sub>10</sub> mode, are now being developed to provide the trunk circuit for integrated communications networks. Because of their extremely high capacity for transmitting video and data signals, millimetric waveguide systems decrease the bandwidth unit transmission costs. Since the cost of transmission goes down by increasing the number of signals sent on a given path, accomplished by providing transmission paths of greater bandwidth, the new system provides the solid economic foundations for the information revolution.

The original prototype of this system used pulse code modulation-binary pulse amplitude modulation (PCM-PAM) at a clock



LEADING MANUFACTURER of microwave and satellite communications systems in Japan is Nippon Electric Company (NEC). Shown is their Yokohama plant.

frequency of 225.47MHz, corresponding to a capacity of 3,000 telephone channels or the equivalent. To increase the total channel capacity, a new prototype has been developed using a four-phase modulation with a clock frequency of 403.04 MHz, producing a transmission rate of about 800 Mb/sec, corresponding to a capacity of 12,000 channels in a radio system and 300,000 channels by a waveguide line.

Improvements were made primarily in the modulator-demodulator and clock circuits, as well as in various other circuits at millimetric frequencies. The modulator consists of a  $\pi/4$  radian sinusoidal phase modulator and a pair of Schottky diode switches to select two stripline paths, with a phase difference of  $\pi$  radians. To reduce unfavourable reflections in the modulator circuit, input circuits with the baseband pulse and an IF of 4GHz were carefully designed by constructing a branch filter for these frequencies. The time interval in which the modulator rises and falls is 0.7ns, with a modulation loss of less than 1.6dB and a phase error of less than 3 deg. Each of the two differential demodulators consists of a Schottky barrier diode phase comparator and an Esaki diode pair decision circuit, connected at very short distances to reduce the effect of reflections. Regions of uncertainty are less than  $\pm 5$  deg and 0.3ns for phase and time respectively.

By offsetting the transmitter local frequency of 50MHz and by the sinusoidal phase modulation of  $\pi/4$  radian peak at the clock frequency, a steplike phase modulation of  $\pi/4$  radian is added for each clock period. The operation facilitates clock timing extraction in the receiver by enabling use of a single detector circuit in the IF stage. To reduce the clock phase instability arising from signal strength variations, a wideband limiter with very small phase variation was obtained by giving an appropriate bias to microwave transistors. The phase variation of 400 MHz was less than 4 degrees for an input variation of 30dB. The modulator-demodulator error rate characteristic through the IF was very close to the theoretical figure.

The local power at millimetric frequencies is generated by GaAs

frequency multiplier diodes excited by an X band IMPATT diode oscillator. The oscillator is stabilised by injection locking of a quality crystal oscillator output. For the transmission, a converter employing a germanium avalanche diode gives an output of 1.6mW. The receiving mixer is a GaAs Schottky barrier diode with an overall noise figure of less than 13dB. A repeater overall gain of 50dB is obtained at a transmission error rate of  $5 \times 10^{-9}$ . The repeater system, composed only of solid state devices, uses repeaters at the carrier frequencies of 47 and 50 GHz.

Pending perfection of this system, however, NTT has begun work on a submarine cable system, with a nominal 200 MHz bandwidth, to handle the concentrated demand for communications services along the Pacific coast of central Honshu. The cable will accommodate about 25,000 telephone channels, or the equivalent in television, data, videophone and other services, when it becomes operational between 1975 and 1977. This system, which will supplement the present 4 and 6GHz micro-wave relay systems which now constitute the backbone of Japan's long line network, will be relatively easier to install and maintain than coaxial cables in densely populated urban areas.

Efforts to develop an integrated electronic switching system for the rapidly expanding transmission network, begun in 1964 as a joint effort of Japanese manufacturers and NTT, produced a prototype (DEX-1) of a large-sized electronic switching system in 1966. Based on this experience model DEX-2, designed for commercial use, was built in 1969 and field-tested in a commercial exchange station. This model uses miniaturised crossbar switches as the speech path switches, and is operated by a control program stored in its metal card read-only memory with a capacity of 65 kilowords of 33 bits.

The crossbar switches have two 8 x 8 wire crosspoint contacts each, operated by a self-holding mechanism, resulting in low power dissipation and economical construction. Two of the 4 stages of the crossbar switches are composed of a line-link network and a trunk-link network, each of which has 1024 junctions. On each 1.3m-wide frame rack,



## Total Communications

512 crossbar switches can be mounted, and 4 racks compose a network of 8,192 terminals. The 8,192 subscriber terminals are scanned by a group of 4,096 relays, and the 1,024 trunk terminals by 2,048 relays.

The central control equipment is composed of 5,500 integrated circuits and is similar to an ordinary digital computer, except for features such as efficiency in performing bit-by-bit processing and an extremely high reliability in continuous operation for a long time. Equipped with magnetic drum and tape low-speed storage systems, the central control unit can be connected to ordinary input or output terminal equipment as well as to communications control equipment for common wire signalling.

Since its installation DEX-2 has operated successfully while development work on an improved model, DEX-21, has been progressing. In the new model, miniaturised crossbar switches one-eighth the size of standard crossbar switches are used. The trunk relays have self-holding mechanisms, substantially reducing power dissipation, and the storage systems of DEX-21 further add to its overall economy using high-speed cores with a cycle time of 1.4 us and a common back-up storage not completely duplicated. Instead of the read-only memory of DEX-2, a semi-permanent memory using permalloy plated wires is used, facilitating easy modification of control information, despite the high stability of stored information. Moreover, four storage modules with a total capacity of 1,080 kilobits can be mounted on a rack, at a cost which is less than 60 percent of a core storage system of the same capacity.

A high-capacity magnetic drum storage with floating heads has also been developed for use in this system, as well as in the centralized storage. The drum has a capacity of 37 megabits and a speed of 3,000 rpm. This extremely high bit density resulted, in turn, in reduced size and weight, one-fifth of the conventional drum.

If all goes according to plan, a local exchange system using the DEX-21 will be put into commercial use this year and a toll exchange will follow. Together with medium- to small-sized electronic switching systems being developed as remote-control systems, the DEX-21 will provide the necessary switching facilities for telephone, videophone and data services scheduled for expansion or inauguration in the coming year. The high processing speed combined with the high flexibility of the central control of the DEX-21 system, together with the extremely wide frequency range of the compact crossbar speech path switches are expected to provide efficient and economical exchange facilities for the integrated communications system.

Meanwhile, the next stage in the development of Japan's communications revolution has already been set. Nippon Electric Company has successfully developed and put into commercial application laser communications equipment using the He-Ne gas laser. The new laser transmission has a capacity of 1,000 Mb/sec, obtained with the use of high-speed PCM technology and a newly developed high-performance and high-speed light modulator together with a long-life, stabilised and compact laser oscillator. With a maximum range of 3 kilometres,

longer distance communications is achieved by installing the same type of transmitting and receiving equipment as relays. This equipment can be used for a wide variety and volume of communications needs, being well-adapted to television, videophone, data, facsimile, and telephone. In addition, it is uniquely adapted for use in cities where the use of microwave and installation of cables is unsatisfactory or costly.


Based upon success with He-Ne gas laser data transmission in 1969, MITI's Electro-technical Laboratories have also developed PCM-PAM data transmission over a 1.8 kilometre distance using a carbon dioxide gas laser. With speeds of 1.544 Mb/sec and a 1 in 100,000,000 error rate, the system would be quite satisfactory for use with computers. ETL scientists, now engaged in perfecting the stability of the beam, believe that the carbon dioxide gas laser will be suitable for short-haul computer on-line systems, and for time-sharing systems.

Still another innovation in laser communications has emerged from the NEC laboratories, where, in co-operation with

transmission guide has been extended to 20 metres, which is still only a fraction of what will be necessary if the SELFOC laser is to become functional.

Telecommunications will be to Japan's incipient "information revolution" what highways and the automobile were to the industrial revolution. With the expanded use of CATV, videophone, facsimile and data communications the whole pattern of work, education and entertainment will change — providing vast new opportunities for electronics equipment, service and software industries. New communications technology will serve as the basis for the entire redistribution of Japanese population and industry, improve urban life and reduce transportation problems.

Given these possibilities, broadband telecommunications will develop into a multi-billion dollar business with enormous profit possibilities for manufacturers of transmission and switching equipment, computers and other central processing equipment, and terminal equipment. For the consumer electronics industry, total communications systems needed by the



COMPUTER TAPE UNITS being tested at Hitachi Ltd's Odawara works. Computers are increasingly being used for communications system control.

Nippon Sheet Glass, the SELFOC laser and SELFOC laser guide have been perfected. The SELFOC glass laser provides continuous and stabilised oscillation and amplification and the SELFOC glass fibre, in which the refractive index becomes smaller from the centre to the perimeter, serves as a vastly improved laser beam transmission guide permitting the beam to be bent or turned.

Most important of the SELFOC laser features is the continuous generation of super short light pulses, making possible the transmission of 1,000 TV channels or 10,000 videophone channels. When used for telecommunications, super high speed transmission can be achieved, while as an economical solid state laser oscillator with continuous output of only a few watts, the SELFOC laser can be used for medical treatment and measurement.

But before it can be applied practically in telecommunications, two critical problems must be solved: loss in transmission must be reduced and ways must be found to lengthen the transmission line. During recent tests transmission loss has been reduced to 100-300 dB/km using red colour lights with 0.63 micron wavelength, and when an infrared ray is used with 0.84 micron wavelength, the loss was halved to 50-150 dB/km. At the same time, the

new information society open vast new horizons with a vast range of consumer needs to be met.

The massive effort required to bring together seemingly unrelated technologies and devices will be a major preoccupation of Japanese industry for the remainder of the Twentieth Century. Japan is uniquely equipped for this task. Indeed, it is the only country in the world which seems to have prepared itself organisationally, technologically, industrially and psychologically for entrance into a technetronic age in which information provides the central dynamic force of society as a whole, and its economic and political activities in particular.

As a result, for the first time in modern history, all available evidence indicates that during the remainder of this decade Japan will lead the world in the introduction of high technology — in much the same way it pioneered the production of transistor radios, transistor TV, and solid state calculators during the 1960s. With the combined impetus of advanced technology and a well-organised, dynamic telecommunication service network, the Japanese market for exotic telecommunications products is expected to keep pace with that

(Continued on page 125)



# Sizzling!

the only word  
to describe  
the extraordinary  
performance of  
the new Wharfedale  
"Denton" and  
"Linton" compact  
speaker  
systems.




Building effective compact speaker systems requires technical "know-how" and experience — and that's where Wharfedale really shines. For over forty years Wharfedale has been Britain's leading manufacturer of high quality wide range loudspeakers; Wharfedale advances in technology are very obvious in the all-new "Denton" and "Linton".

Two models of each unit are available . . . a two way system with an entirely new 8" bass reproducer and a 2" tweeter, and a three way system which specifies a 4" mid-range speaker in addition, to add further reinforcement in the "presence" frequencies.

A long throw voice coil is used in the bass speaker to provide restraint-free lower registers and the new 2" tweeter is the result of intensive Wharfedale research — high frequencies are smooth and satisfying. Large magnet structures offer greater sensitivity.

Now examine closely these brief specifications:



## DENTON 2.

Size: 14" x 9 3/4" x 8 3/4"./Frequency response: 60-16,000 Hz.  $\pm 3$  dB./Power rating: 20 watts DIN./Speaker complement: 8" bass speaker, 2" tweeter./Crossover frequency: 1,400 Hz./Finish: Oiled teak or polished walnut.



## LINTON 2.

Size: 19" x 10" x 9 1/2"./Frequency response: 55-17,000 Hz.  $\pm 3$  dB./Power rating: 20 watts DIN./Speaker complement: 8" bass, 2" tweeter./Crossover frequency: 1,200 Hz./Finish: Oiled teak or polished walnut.

## LINTON 3.

Size: 19" x 10" x 9 1/2"./Frequency response: 55-17,000 Hz.  $\pm 3$  dB./Power rating: 25 watts DIN./Speaker complement: 8" bass, 4" mid-range, 2" tweeter./Crossover frequencies: 1,100 and 4,000 Hz./Finish: Oiled teak or polished walnut.

## DENTON 3.

Size: 14" x 9 3/4" x 8 3/4"./Frequency response: 65-17,000 Hz.  $\pm 3$  dB./Power rating: 25 watts DIN./Speaker complement: 8" bass, 4" mid-range, 2" tweeter./Crossover frequencies: 1,100 and 4,000 Hz./Finish: Oiled teak or polished walnut.

# WHARFEDALE



## FINEST BRITISH DESIGN.

Come and hear the difference Wharfedale experience makes. Call at your nearest franchised Bleakley Gray dealer — ask for a no-obligation demonstration. Imagine how well they'll sound at home . . . then find out how little they cost!

Australian National Distributors:

## Bleakley Gray Corporation Pty. Limited.

Head Office: 28 Elizabeth St., Melbourne, Vic. Tel. 63 8101\*. Telex 31904  
Sydney Office: 177 Salisbury Rd., Camperdown, N.S.W. Tel. 519 5555\*  
Canberra Office: 25 Molonglo Mall, Fyshwick, A.C.T. Tel. 95 2144\*

Adelaide Office: 301 South Terrace, Adelaide, S.A. Tel. 23 6219  
Brisbane Office: 3 Prospect St., Bowen Hills, Qld. Tel. 52 7333  
Perth Office: 27 Oxford St., Leederville, W.A. Tel. 81 4988

INTERSTATE REPRESENTATIVES: N.T.: Pitzner's Music House, Smith Street, Darwin, Tel. 3801.

Tas.: K. W. McCulloch Pty. Ltd. 57 George Street, Launceston, Tel. 2 5322.

SG-WNP-4



# Lee de Forest: idealistic "Father of

This month is the centenary of the birth of Dr Lee de Forest, the great American electronics pioneer and entrepreneur often called the "father of radio". As a timely tribute to the man, we are happy to present this summary of his life and its many achievements in the fields of radio, television, talking pictures, radar and diathermy.

by GEOFFREY MASLEN

The "father of radio" was born one hundred years ago this month. He was Lee de Forest, born in Council Bluffs, Iowa, on August 26, 1873. Like Edison and Tesla, he was one of the last of the individualistic inventors, now virtually eliminated by the advent of the large research laboratories.

While credited with more than 300 American and foreign patents, the name de Forest is largely connected with but one magic word — audion, first of the line of multi-electrode valves. In inventing the triode valve in 1906, de Forest took the most important single step in the whole development of radio communication. Indeed, the transition from wireless to broadcasting would not have been practicable without the development of this valve, variously described as the "cinderella of electrical science," "the magic lamp of radio," "the truest 'little giant' in all history," and "the greatest invention since fire, the lever and the wheel."

De Forest lived to see a multi-billion dollar electronics industry employing more than a million people in the US alone, grow from the audion tube. But he also took an active part in the development of radar, television, sound measurements, electric phonographs, and diathermy machines. He recounted in his autobiography, "The Father of Radio," published in 1950, a story of four marriages, and the loss of four fortunes before gaining contentment. He was considered to be a genius in the field of communications; the New York Times described him as "a great dreamer, a poet, and an enthusiastic advocate of radio and television for educating the masses."

De Forest was the son of Henry Swift de Forest, a minister who early in Lee's boyhood became president of Talladega College, Alabama — "founded to educate and uplift negroes." Because of his father's involvement with the blacks, Lee was shunned by other white boys. Left alone, he became interested in experimenting with crude tools. He designed a new farm gate, built a locomotive out of pine boards and barrels, constructed his own electric motor, and at 15 proudly announced he had discovered the secret of perpetual motion.

Despite these interests, Lee's father wanted him to study the classics in preparation for the ministry. Lee put an end

to these hopes after he entered Mt Hermon Preparatory School in 1891. He wrote to his father: "Dear Sir, I intend to be a machinist and inventor because I have a great talent in that direction." That was the end of the controversy, and Lee went on to the Sheffield Scientific School at Yale in 1893, where he enrolled in the first course in electricity to be offered in any American college.

At Yale he spent his time studying, reading works on electricity, and inventing — one invention at the time was the design for an underground trolley! After receiving his PhD in 1896, he stayed on at Yale for graduate work, eventually completing the research on the "Reflection of Short Hertzian Waves from the Ends of Parallel Wires" which won him his PhD in 1899.

That year was shortly after Marconi had taken out his first patent on wireless telegraphy, and young de Forest, penniless but ambitious, decided to devote his life to research on wireless. With a borrowed \$50 he set out for Chicago and there started work as a labourer in the dynamo factory of

the Western Electric Company. A little later he was promoted to the telephone laboratory. Every spare moment he could find he spent developing a device for detecting wireless signals, and early in his research discovered that he could use a telephone receiver as an indicating device in receiving wireless signals.

After his discovery in 1900 he left Chicago and settled in a shack in Milwaukee with a Professor Johnson, who was doing some experiments of his own on wireless sets. De Forest refused to give him his own anti-coherer idea — and found himself fired.

De Forest returned to Chicago where he obtained one position on the staff of an electrical magazine, and another teaching.

He continued working on his detector, which he called a "sponder," until 1901 when he gave it its first long distance test — and discovered that it worked! The sponder, a kind of electrolytic detector, made possible the use of headphones for wireless messages. It was de Forest's first patent and it made him a close competitor of Marconi. Immediately, he and a partner, Edwin Smythe, decided to go ahead with the marketing of the device, only to discover that money and publicity were necessary.

To get publicity, de Forest persuaded the Publishers' Press to let him report the International Yacht Races with his wireless in competition with Marconi operators, who were doing this for Associated Press. De Forest's broadcast was a complete failure, but so was that of his rivals. However the publicity was successful and encouraged by it, de Forest set up a machine shop and erected the first wireless station of its kind in Jersey City.

Eventually, de Forest was able to interest Wall Street sufficiently to form the De Forest Wireless Telegraph Company, and with the money from the capitalisation bought equipment and set up transmitting rooms. In 1903 he went to England to demonstrate his invention and while there communicated by wireless from Wales to Ireland.

Back in the United States, shortly afterwards, he was awarded gold medals at the St Louis World's Fair in 1904 — the first of many — for his work on wireless telegraphy. Then he began to give up the wireless field, partly because his electrolytic detector had been declared to interfere with the patents of another inventor, but mostly because he was particularly interested in transmitting the human voice.

Returning from a third voyage to England in 1906, de Forest found his company in financial difficulties and with the other directors anxious for him to resign. He accepted a few hundred dollars offered him and set out on his own again. "I'll build a



DE FOREST'S AUDION, the first triode valve, which he developed in 1906. Without it, the development of radio and electronics might have been delayed for decades.



# Radio"

better detector for wireless reception," he announced. "I'll try to send the human voice through the air instead of messages by dots and dashes."

Earlier, in 1904 J. A. Fleming, Professor of Electrical Engineering at University College, London, had experimented with the first thermionic two electrode valve or diode. The full significance of Fleming's experiments was not appreciated at the time, and it was Lee de Forest, who by inserting a third electrode into Fleming's valve, thereby making it a triode, took the most important single step in the whole development of radio communication. Yet, the full significance of de Forest's invention was not realised either, and the two inventors quarrelled about British and American patents instead of exploring the revolutionary implications of their discovery.

The multi-electrode valve enabled much more sensitive wireless receivers to be made and permitted radio-telephone messages to be picked up at far greater distances than had previously been thought possible. It was applicable at one and the same time both to transmitting and receiving circuits. It contained within itself all the potential force of broadcasting. But the triode, like a great many of de Forest's inventions was the subject of a long, drawn-out court battle, in litigation with the Marconi Company. The court held that the origin of the audion could be traced directly to the Fleming valve.

De Forest insisted that he had invented the audion independently of Fleming and that therefore, it was an injustice to him to be credited "only with having added a third element to the Fleming valve and calling the completed bulb an audion." "I worked along entirely original lines," de Forest said, "finally arriving at the three element tube as the result of step-by-step progress."

Immediately after the invention of his triode valve, Lee formed the De Forest Radio Telephone Company to promote his idea and by the end of the year, after a public trial of radio-telephone apparatus, the US Navy Department ordered enough radiophone sets to equip the fleet.

Not only was 1906 a watershed in the history of broadcasting, it was also the year in which de Forest married Miss Lucille Sheardown, after the first "radio courtship" in history. He had installed a wireless apparatus in her home, and being a shy young man, he proposed from a safe distance through the instrument. He was accepted in the same way. Unfortunately, the distance which separated the young couple at the proposal seems never to have been overcome, because the following year the marriage was annulled!



*DR DE FOREST HIMSELF, in his 85th year. This picture was taken late in 1958 when he visited a Hollywood film studio as an honoured guest.*

In 1908, de Forest married Nora Stanton Blatch and went with his bride to Paris to install one of his radio telephone transmitters on top of the Eiffel Tower. Back from his honeymoon, he built an aerial on top of the New York Metropolitan Life Insurance building and shortly afterwards installed microphones in the Metropolitan Opera House. It was via these on January 2, 1910, that the voice of Enrico Caruso singing at the opening night of the opera "Cavaleria Rusticana" was transmitted in the first radio broadcast of its kind.

"This transmission of the voice of

Caruso," the inventor said years later, "was the first broadcasting of music other than phonograph selections. Although only a few amateurs and ship operators had heard the great singer's voice, we knew it had been a success."

De Forest became short of funds again — he was never a success as a business man — and went out to San Francisco as a research engineer for the Federal Telegraph Company, while his own company slowly died. In 1914 he refinanced it with \$50,000 he received from the sale of his audion tubes to the American Telephone and Telegraph



Company. This occurred after he had left San Francisco for New York again. Then he set up another laboratory, and later a transmitter at the World Tower Building from which regular radio broadcasts of vaudeville were given for the first time. In 1916 he transmitted the first radio broadcast of presidential election results.

As radio developed de Forest was manufacturing radio tubes for the new industry, but his heart wasn't in this work. He was looking ahead even further — toward the development of talking motion pictures. By 1923 he had shown for the first time a sound-on-film program in the Rivoli Theatre in New York, and had invented his "noiseless recording" positive prints and "glow light" recording of sound on films. The motion picture producers weren't interested, though — until 1927, when Warner Brothers plunged into the field, four years after de Forest had demonstrated the practicalities of talking pictures.

From talking pictures de Forest turned later to television and from television to its application in "television torpedo planes," predating by some 20 years the advent of the military satellite. Meanwhile, in 1934, after years of litigation with Edwin Armstrong, his claim to the invention of the "feed-back" and oscillating vacuum tube circuits had been upheld by the US Supreme Court. Yet despite recognition from learned societies, manufacturers and scientists, de Forest never made money and by 1937 he had filed a bankruptcy petition listing assets of \$390 and liabilities of \$104,000.

By 1934 he founded the Lee De Forest Laboratories, devoted chiefly to research and manufacture in the new field of short wave, or radio, diathermy: the application of high frequency currents to heating human tissues. This was believed to be beneficial in cases where congestion was involved. The US Army and Navy once used large numbers of de Forest Dynatherms in hospitals and on all battleships.

With the widespread development of commercial radio during and after the Second World War, de Forest became more and more concerned by the way his "child" was being used by the advertising industry. He wrote an open letter to the National Association of Broadcasters at a meeting in



*SMILING DE FOREST reads news of patent infringement decision in his favour, in March 1930. De Forest had taken action against the Stanley Company of America for their use of a motion picture sound recording method.*

Chicago in 1946, a letter whose condemnation might equally apply to parts of Australian radio today:

"What have you gentlemen done with my child?" de Forest asked. "You have sent him out in the streets in rags of ragtime, tatters of jive and boogie-woogie, to collect money from all and sundry for hubba hubba and audio jitterbug. You have made of him a laughing stock to intelligence, surely a stench in the nostrils of the gods of the ionosphere; you have cut time into tiny segments called spots — more rightly stains — wherewith the occasional fine program is periodically smeared with impudent insistence to buy and try."

Despite such occasional outbursts, de Forest removed himself pretty thoroughly from the public eye to the cloistered retreat of his laboratory in Los Angeles, where he

spent many hours working on a terrain altimeter, patented in 1946; diathermy machines; and in 1948 a television device for the transmission of colours! (In 1949, however, de Forest told the Federal Communications Commission that no major colour television systems were ready for commercial use.)

He was now renowned and respected. Two radio schools paid him retainers for the glamour of his name; in 1947 he was in Chicago directing veterans' training at American Television Inc; in 1951 he became vice-president of the National Association for Better Radio and Television; former President Herbert Hoover addressed a dinner in his honour at the Waldorf-Astoria Hotel in April, 1952. And despite his advancing years, de Forest continued working at the same intense pace. In 1957, in his 84th year, he received a patent on an automatic dialling device for telephones! A year later he received an award from the National Association of Broadcasters — those whom he had attacked six years earlier — for his contribution as the originator of modern electronics.

Even 45 years after the historic broadcast of Caruso's voice — right up until the time of his death in July, 1961 — de Forest lived life at a feverish pitch. And always he struggled to keep radio and television as instruments of education and culture.

"Throughout my long career," he said, "I have lost no opportunity to cry out in earnest against the crass commercialism, the heretic vandalism of the vulgar hucksters, agencies, advertisers, station owners — all, who lacking awareness of their grand opportunities and moral responsibilities to make of radio an uplifting influence, continue to enslave and sell for quick cash the grandest medium which has yet been given to man to help upwards his struggling spirit . . ."

### AWA TO DEVELOP INTERSCAN SYSTEM

The development contract for an evaluation version of the new CSIRO-developed microwave landing system for aircraft, INTERSCAN, has been placed by the Department of Civil Aviation with Amalgamated Wireless (Australasia) Ltd. The equipment, which will be developed from the concepts and with the guidance of the Department of Civil Aviation and CSIRO, will be installed during 1974 at an Australian airport and evaluated by DCA, which will compile a final report for consideration by (ICAO) International Civil Aviation Organisation. Countries other than Australia are working on alternative approaches to the common operational problems, and will also make submissions.

AWA engineers, with the support of sub-contractors, will construct a total of four microwave ground antennae complete with transmitters and associated control synchronising equipment. Two sets of airborne equipment for both main airline and general aviation (light) aircraft will be supplied together with monitoring and test facilities.

A detailed study will be completed within the next four months during which precise objectives will be established and appropriate procedures will be planned to enable construction to be completed within the time-scale.






## A clear picture on distortion

Suppose you're listening to the Berlin Philharmonic performing Beethoven's Ninth through an ordinary amplifier. Chances are you're hearing sounds that neither Ludwig nor the Philharmonic intended. And what's the point of buying expensive records if your amplifier is giving inferior performance? The aim is to achieve a replica or mirror image of the original. And to do that you've got to eliminate distortion. That's what

AKAI have achieved with their **AA-5500 AMPLIFIER**. Distortion is actually less than 0.1%! AKAI did it with SEPPOTL circuitry: To eliminate the main cause of distortion. Result? Amazingly clear and distortion-free reproduction. We could go on quite a bit about the AA-5500's sensational tonal control, excellent signal to noise ratio, elimination of turntable rumble etc. but your AKAI dealer has all the facts. Have a listen and judge for yourself.



**THE VERY REAL SOUND EXPERIENCE**

Distributed by Akai Australia Pty. Ltd., 276 Castlereagh St., Sydney, N.S.W. Tel.: 61 9881. 146 Burwood Rd., Hawthorn, VIC. Tel.: 81 0574. 399 Montague Rd., West End, Brisbane, QLD. Tel.: 4 0171. 8 Arthur St., Unley, S.A. Tel.: 71 1162. 11-13B Belmont Ave., Belmont, W.A. Tel.: 65 5833. Homecrafts Pty. Ltd., Petrie St., Canberra City, A.C.T. Tel.: 47 9624. Docen Audio, 122 Bunda St., Civic Centre, Canberra, A.C.T. Tel.: 48 8785. P & M Distributors Pty. Ltd., 87A Brisbane St., Launceston, TAS. Tel.: 31 5815. Pfitzners Music House, Smith St., Darwin, N.T. Tel.: 3801

AK58P



# Computer delivers the newspapers

... with a little help from its friends

It probably had to happen sooner or later, with labour costs rising higher and higher while minicomputers are becoming cheaper and cheaper: by mounting a minicomputer in a newspaper delivery truck, a US firm has made even the humble paper-boy redundant!

by **GEORGE E. TOLES**

Using a little editorial license, a newspaper in Fort Worth, Texas, could easily carry a front page story telling its subscribers that "this newspaper is brought to your home via a minicomputer system."

While that may not be literally true, a minicomputer is certainly at the heart of a new Automated Newspaper Delivery System that unerringly directs the delivery of the paper to many of its readers every day of the week, rain or shine.

Developed and produced by Avcon Inc, of Fort Worth, the ANDS guides a delivery

truck along a complex route and tells two men mounted on either side of a specially designed vehicle when to throw their papers. And they never miss, according to the Avcon people.

Incorporating a "Naked Mini 16" minicomputer built by Computer Automation Inc, of Irvine, California, the Avcon system effectively demonstrates the broad spectrum of applications areas opened by the advent of such low-cost, parcel-sized computing devices.

The Avcon system is a completely self-

contained, on-board system which directs the operation of the newspaper truck and controls its deliveries. It does not require special transponders or electronic signalling devices to be installed at strategic locations along the route.

In effect, the system continuously measures the vehicle's location in relation to a pre-planned route, then issues audio and visual instructions which guide the driver and the paper throwers on their appointed rounds.

The system even activates the vehicle's turn signals shortly before it is scheduled to make a turn, to give the driver added advance warning of the impending manoeuvre. For good measure, the system also detects driver errors and immediately prescribes appropriate corrective actions, according to Robert T. Rapp, Avcon vice president for marketing.

Because of the system's unique guidance capabilities, neither the driver nor the throwers need to be armed with maps, subscriber lists, or prior knowledge of the route. It's all done by tape and computer memory.

All of the system hardware apart from the driver's display panel is mounted in a special installation above the truck's windshield. The driver's display panel is mounted atop the dashboard, so that he can easily read his directions.

The system includes the miniature Naked Mini digital processing and logic unit (it has 4k/16-bit words of core memory); a tape cartridge drive, proprietary sensing devices, control/display console with message printer, and a variety of annunciator and actuator devices.

The mini computer mounted on the rack is programmed to analyse the output of speed and direction sensors developed by Avcon. The mini computes the path of the vehicle and compares it with a route "signature" recorded on the tape cartridge. It then issues instructions and commands, as required.

Here's how it works: First, a fixed route is divided into segments and a "signature" for each segment is recorded by driving over the segment with the Avcon system operating in its mapping mode. Locations of delivery points are recorded when the driver or an assistant depresses a switch at each location. These locations are sited in



*SPECIALLY-DESIGNED newspaper truck in Fort Worth, Texas uses an on-board mini computer to direct the driver along the delivery route. It also tells the throwers when to launch their missiles.*





terms of distance from the beginning point of a segment.

For basic route control, verbal instructions are recorded on audio tape. Cues for advancing the tape and for activating the vehicle's turn signal lights are added to the route control tape.

To travel over a previously mapped route, the driver simply starts the route at a specified point and follows the system's real-time audio and visual demands.

"For example, when a driver approaches an intersection where a left turn should be made, the left turn signal goes on and a voice message gives the command: 'turn left', and names the street," Rapp explained. "The driver needs to make no reference to maps or subscriber lists."

If a driver departs from his specified route, or misses a command, the system sounds an error signal, then produces a message describing the error and gives instructions for corrective action.

The paper throwers mounted by open windows on either side of the van wear earphones that receive the signals telling them when to hurl their rolled-up papers. Lead times for the throwers are automatically adjusted to the speed of the truck, which may be travelling anywhere from 15 to 30 miles an hour along its routes.

*CONSOLE in the driver's cab gives him explicit instructions regarding his route. The minicomputer controlling the system also sounds an alarm if the driver makes a mistake, then tells him how to correct matters.*

The system is accurate down to the last front porch, whether the route is one mile or 100 miles long, according to Rapp.

"On one six mile test run, we compared the location indicated by the system with the true location at 40 random points," Rapp said. "The average difference was 3.76 feet, and the maximum disparity was eight feet."

The system has a few other benefits for its users, in addition to improving subscriber service and lowering distribution costs, which can be reduced by one-half, Rapp claimed.

For example, when the route is mapped, non-subscriber addresses can be listed to pinpoint new targets for sales activities. And the need for post delivery report writing is eliminated because data can be entered into a main office computer system by the driver, including such transactions as collections for subscriptions, the number of items delivered, and the like. Such information and other relevant data is fed into a central subscriber data system located at the newspaper headquarters, providing updated subscriber information and

directional instructions, and centralised and accurate customer billing.

With production of the newspaper delivery system well underway, Avcon is now working on the development of other minicomputer-based systems for similar applications that will have an even broader role for the computer.

In a new system being put together for bread delivery trucks, for example, the computer will not only direct the driver along his route but will also handle his inventory computing problems and his daily accounting for accounts receiving, according to Rapp.

In this respect, the full power of the computer will be put to work in the calculating of invoices and delivery tickets, recording pertinent information for marketing studies (such as potential customers and those serviced by competitors), as well as noting cash received and disbursed and items delivered during the day. The system thus provides a full accounting at the end of the day for all transactions — and telling the driver what to order for delivery tomorrow.



You can cut the risk of electrocution with

# Core-Balance Earth-Fault Protectors

by LEO SIMPSON

Ever had a nasty electric shock from an appliance or mains wiring? Even if you have had one, you may not have realised that it could easily have been fatal. In view of the risk of fatal shock, there is a lot to be said for the protection offered by devices known as "core balance relays."

Just about every time a person uses a mains-operated appliance, he or she is exposed to the possibility of electric shock. Fatal electric shock. All it takes is an insulation breakdown to the metal frame of the appliance, together with a broken earth wire in the power cord, and the scene is set for a nasty event.

Maybe the appliance has a frayed power cord with exposed wires, or perhaps it was wired incorrectly. There is always the risk of a power tool or lawnmower cutting its own cord. And people will poke knives into toasters, or even light their cigarettes from electric radiators! When you consider that the average home may contain anywhere between 20 to 40 plus light fittings, power points and so on, the possibilities for electric shock are almost endless.

But the home is just one area where shocks can occur. Other hazardous areas are swimming pools, construction sites and concert halls — even the intensive-care wards of hospitals.

Statistics show that the majority of electrocutions and severe electric shocks occur when the user accidentally becomes the current path between mains active and earth. Because of this, a major advance in electrical safety is provided by devices known as "core balance relays" or "earth

fault protectors." These can cut off the power automatically when a shock or fault situation occurs, so that instead of being killed the user will at worst get an unpleasant "jolt."

The principle of operation of these devices is as follows: In simple terms, the electricity you use comes via an "active" wire and returns to the substation via a "neutral" wire. Normally the currents in both wires are the same and equal. But when a person receives an electric shock, some current flows from active to earth (in the majority of cases) so that slightly more current flows in the active wire than in the neutral wire.

A "core balance relay" or "earth fault protector" senses the imbalance of current (hence the name) and cuts off the power before the shock becomes severe. Fig 1 illustrates operating principle.

Both active and neutral wires pass through a toroidal magnetic core so that the conductors become the windings of a transformer. These windings are so connected that the magnetic fields generated by the currents in each wire cancel out when the currents are equal. A third winding monitors the residual magnetic flux in the core. If the active and neutral currents become unequal, the flux in the core rises to

a point where the third winding generates sufficient voltage for a circuit breaker to be tripped.


A toroidal core is used for the transformer because this has a very low flux leakage and thus can be used to indicate a very small degree of current imbalance. The same principle of operation is used to protect 3-phase distribution systems.

Typical sensitivity of core balance relays is high — of the order of 20 to 30 milliamps. And the typical response time to kill the power circuit is of the order of 30 milliseconds.

Readers may wonder why the core balance relay needs to have such a high sensitivity and quick release times. Apart from getting you "off the hook" quickly to minimise the pain, there are very vital reasons.

First, let us state that it is not the applied voltage but rather the resulting current which determines the severity of an electric shock. A current of as little as 10 milliamps can provide quite a severe and painful shock. Currents from 10 milliamps to 50 milliamps cause physical shock (in the medical sense), muscular paralysis and upset breathing.

But it is currents of the order of 50 to 200 milliamps which are extremely dangerous, because they can cause ventricular fibrillation of the heart. In this condition, the heart is jolted out of its normal pumping rhythm into a quivering jellylike state — in which it cannot maintain circulation. The only way the victim can be saved in this situation is for external cardiac massage to







At left is a Core-balance circuit breaker for the home switchboard while at right is a portable unit with two 3-pin sockets in the base.



be applied immediately, along with mouth-to-mouth resuscitation (because breathing generally stops at the same time). Cardiac massage must be maintained until the victim is admitted to a hospital, where electric shocks can be applied to jolt the heart back into its normal rhythm.

So there it is. A moderate shock of the order of 50 to 200 milliamps can cause ventricular fibrillation in the victim's heart, and if he is not lucky enough to have persons standing by to apply instantaneous cardiac massage and arrange for admission to hospital within about half an hour, he is as good as dead.

Even shocks which last only a comparatively short time, less than a second for example, can cause fibrillation if the shock coincides with a critical 0.15 second phase at the end of the normal heart cycle of around 0.75 second. As Dr James Loughman, who is a member of the NSW Hospitals Commission committee on electrical safety, puts it: "It's just so easy to receive a belt — and so easy to die from one that it's not funny."

Clearly, for shocks exceeding 50 milliamps it is vital that the electricity supply be cut off in as short a time as possible; hence the value of a core balance relay. This does not provide protection by limiting the value of the shock current, it merely acts to cut off the power quickly. So the victim still receives a shock, but a very short one, and one that could have been fatal if the core balance relay had not been in operation.

It is interesting to note that the United States' National Electric Code as of January 1st, 1973 requires all 15 and 20-amp outdoor receptacles to be equipped with earth fault protection. Closer to home, the Queensland Department of Labour and Tourism requires power outlets on construction sites and similar situations to have some form of earth-fault protection.

And just recently the Standards Association of Australia has modified the SAA Wiring Rules CC1, part 1 in amendment No 6, with regard to swimming pools. Lighting circuits to underwater lighting of swimming pools must now be provided with core-balance earth fault protection.

We must point out, at this stage, that core-balance relays provide a far greater degree

of protection than the commonly known voltage-operated "earth-leakage circuit breaker." These devices are generally regarded as unsuitable these days and most houses do not have them installed.

A core-balance relay is far superior to an earth-leakage circuit-breaker since it does not rely on earth connections to provide protection. And it has the further advantage that it is not subject to "nuisance tripping" because of lightning strikes, electric trains or faults in houses "half-way down the street."

One other term which readers may meet should not be confused with "core-balance relays" is "Earth Fault Detector." This does not provide protection against earth faults but is designed to continuously monitor the insulation resistance between the electrical system and earth and give a warning at an adjustable threshold of failure. It is not used domestically but in factory plants with continuous processes and in hospitals to protect patients in intensive care wards and operating theatres.

Having described the advantages and general operating principle of "core balance earth fault protectors," to give them an all-encompassing title, how do you get this protection? Ideally you have one installed by an electrician on the main switchboard of your house. The Scanelec Safeguard is a typical unit. Price is \$42.00 plus installation cost, not much to save a life. It is a 4-pole unit rated at 25 amps per pole at 415VAC for a 3-phase installation. Alternatively, for a single-phase installation (the normal two-wire mains connection) it can be used as a 2 x 2-pole unit for a total rating of 50 amps at 240VAC.

For either 3-phase or single phase systems, this unit will provide complete protection all normal domestic installations, both inside and outside the house. There are some provisos though. For example, hot water heaters, whether instantaneous demand or off-peak types, are not included in the circuit. This is because

they always have some current leakage to earth, because of their open-element construction. But in any case such devices are positively earthed by the water pipes to which they are connected, so there is no real problem.

Electric ranges are also generally not included in the earth-fault protection circuit. This is particularly so with earlier models, which tended to have poor sealing of the elements, and consequently some leakage to frame. But electric ranges are usually also very well connected to earth so this is again not a problem. As far as we can determine, there have been no deaths attributed to faulty electric ranges.

While a core-balance earth-fault protector installed at the user's switchboard protects the user while he is at home, he can still be killed using a power tool on a construction site, in a neighbour's backyard or anywhere else. For this reason, Scanelec market a portable core-balance relay. Also called the Scanelec Safeguard, this has two general-purpose 10-amp power outlets with individual switching. Principle of operation is the same as the switchboard model, and the price is \$60.00.

Enquiries for Scanelec products should be directed to electrical distributors or to Scanelec Pty Ltd, 248 Coward Street, Mascot, NSW 2020.

Other companies market suitable equivalents to those shown in this article.

In conclusion, we must sound a warning. The earth-fault protector system is only able to protect against electric shock caused by current passing through a person's body to earth. While this is by far the most common cause of fatal electric shock, it is still possible to receive a shock by coming into contact with both the active and neutral conductors. This condition will not trip any core-balance protection device.

The use of these devices cannot replace normal safe practices — including adequate earthing of electrical installations in accordance with the SAA Wiring Rules. ☛



# Simple converter for the VHF bands

Here is a third design in our current series of simple receiving converters, this time tuning selected bands in the VHF spectrum. It uses the same printed board as before, and like the earlier designs is easily built up.

by IAN POGSON

This is the third of a series of converters currently being described. The first one was published in April, 1973 and covered the range 6MHz to 19MHz; the second one appeared in June, 1973 and it covered the range 2MHz to 6.5MHz. We are now moving into the VHF spectrum and details are given for tuning a number of selected bands within this range. Readers who wish to tune other bands not specifically provided for may do so within the limits of the circuit, by interpolating from the data given for coils, padders, etc.

The VHF tuning ranges which we consider to be perhaps the most popular, and those for which we give details are: 52-54MHz, 70-85MHz, 118-136MHz and 140-150MHz. The first and last bands are the 6-metre and 2-metre amateur bands; 70-85MHz includes taxis and other commercial services, while 118-136MHz includes aviation channels.

It may well be asked, why cover 140-150MHz when the amateur band only covers from 144 to 148MHz? In a converter of simple design such as this one, it is not easy to cover only a very small percentage at such high frequencies. Certainly it can be done, but it means quite a bit of delicate "fiddling" with the relevant circuit constants, particularly those of the tunable oscillator. Left as it is, the tuning rate is still quite good, while the ability to tune signals

on either side of the amateur band may perhaps be seen as a bonus.

Although we give details for four separate tuning ranges, it should be pointed out that the converter can only be set up to tune one band. No provision is made for coil changing as this would complicate the converter to the point where serious difficulties may be encountered by readers. Generally speaking we are of the opinion that most readers will be interested in only one band.

The circuit is similar to the previous ones, but there are certain differences brought about by differing techniques as the frequency is taken higher. The first difference to be noted is that the tuned aerial coil does not have a separate winding for inductively coupling the aerial to the tuned circuit. Instead, the aerial is fed via a .001uF capacitor to a tap on the tuned coil. Instead of a standard 10-415pF 2-gang tuning capacitor, we are now using a more specialised 10-24pF unit, still a 2-gang and fitted into the same "tub" as previously. To govern the range tuned by each circuit for various bands, a series "padder" is introduced.


Injection into the FET mixer is quite different from that used before. Instead of injecting into the source, the gate is used. The capacitance required under these conditions is very small — 1pF. Injection from the oscillator is derived from the

emitter of the oscillator, rather than from a coupling winding on the tuned oscillator coil. The output transformer, instead of being a ready made broadcast aerial coil used back-to-front, is now a specially wound transformer.

The need for a different output transformer arises from the desirability of using a higher value of first intermediate frequency. At 1.5 or 1.6MHz, image response would be a considerable problem at VHF. We have selected 3.5MHz as one which will give an improved image response, also as one which should be readily available on most receivers for short wave use. Ideally, as we go higher in frequency, so should the first IF be increased. However we have decided on 3.5MHz as a good compromise.


The tuned local oscillator is still basically the same as used on the earlier converters but there are differences brought about by the use at the very high frequencies. The oscillator was a Hartley but it has reverted to a Colpitts, simply by omitting the capacitor from the oscillator coil centre tap to the emitter. The 6.8pF capacitor was previously 12pF. For frequencies in the lower VHF ranges, the emitter resistor is still 3.3k. However, as we go higher in frequency, it is necessary to reduce the emitter resistor in order to maintain oscillation. A value of 470 ohms is satisfactory under these conditions.

As we mentioned in earlier articles, the printed board has been designed to accommodate these changes. In fact it is able to accommodate quite a few more changes, leading to other converters which we hope to describe in the near future.



The printed board is reproduced full size, is viewed from the component side, with the copper shown "ghosted".





Above is a front view of the converter with the old dial and at right is the circuit diagram, which should be studied with the text.

Apart from the circuit changes just outlined, this converter takes on the same format as before. The metalwork is the same and apart from the dial scale, the external appearance is the same. We are still using one of the older Jabel dial assemblies and it should be pointed out again that these are no longer made in this precise form. The mounting holes are the same but the dial scale is now covered with a perspex moulding. This makes the assembly bigger but we have already allowed for this in our metalwork drawings.


While we are on the subject of dials, we should mention that we have not attempted to give any dial calibrations. The difficulty of aligning to a pre-calibrated dial is so great at VHF that we decided to leave it up to the individual to calibrate according to his own requirements. More will be said about this when we deal with adjustments later on.

Perhaps it is an obvious statement but before construction can start, you must decide which band is to be covered. Information for winding all coils is given in the table. Included with this are also the values of padder capacitors and emitter resistor required. If you wish to cover some other range not given in the coil table, then you will have to interpolate to arrive at a starting point for coils for the frequency of your choice. We must point out that we are unable to enter into any discussions relating to this, however, as there are many potential problems.

No trouble should be experienced in winding or otherwise making the tuning coils. No formers are required, as they are made with a heavy gauge of wire and are physically self-supporting. Where an inside diameter is given, the coil may be wound on a drill or piece of rod of the required diameter. This done, the winding is spaced evenly to occupy the length and the ends are then neatly bent so that they will fit the appropriate holes in the printed board. The oscillator coil for the 118-136MHz band is a hairpin shape and details are shown on the circuit diagram. The oscillator "coil" for the 140-150MHz range is simply a link of 16B&S wire, hard against the surface of the board.

The tap on each of the aerial coils is easy to make. At the appropriate point, a little of the enamel is scraped off, the part tinned, and the capacitor is then soldered to it. Only enough lead should be left on the capacitor so that it just reaches comfortably between the tap and the point on the printed board.

Regardless of the selected tuning range, you will need an output transformer. This is wound on a Neosid 7.6mm diameter former and consists of a primary and secondary



**BASIC VHF CONVERTER**

3 / CV / 11

## LIST OF PARTS

- 1 Chassis-panel, 165mm long x 127mm high x 127mm deep.
- 1 Cabinet to suit
- 1 Dial assembly, Jabel 6 / 36N
- 1 Flexible coupling, 1/4in x 1/4in, Jabel
- 1 Miniature toggle switch, 3-pole, 2-position
- 2 Terminals, 1-red, 1-black
- 4 Rubber feet
- 1 Grommet for coax cable
- 6 Spacers, 1/2in long x 1/4in diameter, tapped 1/4in Whitworth
- 1 Printed board, 6in x 3in, 73 / 3C
- 1 Neosid coil former, 7.6mm x 60mm, with can and 2 grade 900 slugs
- 1 Transistor, 2N5485, FE5485, MPF106
- 1 Transistor, BF115, TT1002, or similar

### RESISTORS (1/2W)

- 1 100 ohms
- 1 470 ohms (see coil table)
- 1 3.3k (see coil table)

- 1 3.9k
- 1 4.7k
- 1 15k
- 1 22k

### CAPACITORS

- 1 1pF NPO ceramic
- 1 6.8pF NPO ceramic
- 2 10pF NPO ceramic (see coil table)
- 2 15pF NPO ceramic (see coil table)
- 1 10-24pF Roblan 2-gang variable
- 2 27pF NPO ceramic (see coil table)
- 2 30pF Philips trimmers
- 2 56pF NPO ceramic (see coil table)
- 1 82pF NPO ceramic
- 1 .001μF 400V ceramic
- 3 .01μF 400V ceramic
- 1 0.1μF 25V ceramic

### MISCELLANEOUS

Hookup wire, 2ft coax cable, solder, screws, nuts, piano wire.

Note: Resistor wattage ratings and capacitor voltage ratings are those used for our prototype. Components with higher ratings may generally be used providing they are physically compatible. Components with lower ratings may also be used in some cases, providing the ratings are not exceeded.

winding. The primary is wound first and it consists of 120 turns of 28B&S enamel wire, close wound. The start and finish of this winding may be anchored with a small piece of adhesive tape, slipped under a few turns at each end during winding. The end protruding is then folded over the top of the winding when completed. The secondary winding is 12 turns of 28B&S enamel, over the bottom end of the primary, after having placed a piece of tape over that part of the primary. Again, tape is used to anchor the winding in place.

To ensure that the windings stay firmly intact, they should now be given a coat of cellulose lacquer or other suitable material. When dry, the leads should be terminated

such that when the coil is fitted to the board, the pins correspond with the relevant parts of the circuit, as shown in the diagram. Note that two slugs are needed to make the coil tune to 3.5MHz with 82pF.

Before leaving the output transformer, it may be noted that the screws used for holding the can to the former and for chassis mounting as well, are 6BA. If you have 6BA screws, all is well. However, they are not always easy to get and an alternative is to retap the threads in the former to 1/4in Whitworth.

We have already mentioned that we are using a gang made specially for tuning at VHF. However, we found a problem related to the gang as we went above 100MHz or so.



## VHF Converter


Oscillator tuning became quite erratic and this was traced to irregularities in the earth return of the rotor section of the gang. The manufacturers of the gang took the usual precaution in providing a wiper between the frame and the centre of the rotor, but this was apparently not sufficient. We found it necessary to provide another wiper, at the oscillator end of the gang.

Readers may be able to come up with other methods of doing the same thing, but we used a piece of 28SWG piano wire, about 8cm long, fitted as shown in the picture. One end is looped and fixed under the foot mounting screw immediately below the shaft. The wire is drawn as tightly as possible and another loop terminates it under another screw and two washers, in a tapped hole above the shaft. The two washers are used as convenient spacers to make termination easier. This arrangement results in the wire wiping the rotor spindle, which we found to completely eliminate the trouble.


We are now ready to wire and assemble the components. It is generally convenient to put the resistors, capacitors and other small components on the printed board first. Care should be taken to make a neat job, with resistor and capacitor pigtails kept as short as possible. When soldering, avoid overheating components.

Apart from the output transformer, it may be noted that the coils are fitted through holes in the board normally provided for the pins of coil formers. Unused holes are left vacant. We found it convenient to place the 1pF capacitor and the .01uF capacitor shunting the 4.7k resistor underneath the board. These components should not be forgotten, as their omission will seriously upset the performance of the finished unit.

Before the 2-gang variable capacitor is fitted to the board, leads must be soldered to the bottom lugs of the fixed plates. Use about 8cm of 20 gauge tinned copper wire, wound firmly around each lug before soldering. This will stop the soldered joint from coming adrift when the other end of the lead is soldered to the board. A trimmer must also be soldered to each section of the gang and as may be seen from the picture, we used the new solid dielectric type. If you have the old "beehive" trimmers, then use



Above is the rear view, showing major components. At right: the front of the gang, showing the wiper wire.



them by all means. Care should be taken when soldering the former trimmers in place to make sure that a good soldered joint is made in each case, without damaging the trimmer by burning or overheating.

Having completed the board, leads must be added to go to external points. Leads of sufficient length are soldered to the earth point near the earth terminal on the back skirt of the chassis, the aerial of the coil to the switch, the +9V point to the switch, the IF output to the switch and from an earth point near the 3.3k or 470 ohm resistor, to earth the IF output braid on the coax.

The two terminals, rubber grommet, switch and dial assembly may now be fixed to the chassis-panel. As mentioned earlier, the dial we used is no longer made but if you have one on hand, then it may be used, as the mounting holes remain the same. As an alternative to the new dial which we have suggested, you may see fit to make other arrangements, possibly still making use of

the dual ratio drive by Jackson Bros. This drive is available as a separate unit from Messrs Watkin Wynne, 32 Falcon Street, Crows Nest, NSW 2065.

At this stage, a careful check should be made to ensure that no errors have been made on the board assembly and elsewhere. Satisfied that all is well, the board may now be screwed to the chassis, not forgetting the flexible coupling between the gang and the dial drive. A short spindle is required between the drive and the coupling and this may be obtained from an offcut of a potentiometer spindle.

All interconnecting leads should now be terminated. The switch connections should be carefully studied to ensure correct operation. We used the centre section to switch the +9V supply, with the other two used for the aerial and IF output respectively. We arranged the wiring such that when the switch toggle arm is uppermost, the converter is switched off and the aerial is fed directly into the main receiver. With the switch operated, the converter is switched on, with the aerial fed to it and the output of the converter is then fed to the receiver. The coax cable and a lead for the +9V supply are passed through the rubber grommet. If desired, a separate negative lead for the supply may be provided and connected to the earth copper of the board.

With the mechanical work complete, we are ready to adjust the converter and put it

### COIL DETAILS FOR FOUR BANDS

#### 52-54MHz

Aerial: 8 turns, tapped 2 turns from earth end, 18B&S enamel, 1/2in ID x 14mm long. Padder 10pF.

Oscillator: 8 turns, 18B&S enamel, 1/2in ID x 21mm long. Padder 10pF. Emitter resistor 3.3k.

#### 70-85MHz

Aerial: 5 turns, tapped 1 turn from earth end, 18B&S enamel, 3/4in ID x 11mm long. Padder 56pF.

Oscillator: 4 turns, 18B&S enamel, 3/4in ID x 10mm long. Padder 56pF. Emitter resistor 3.3k.

#### 118-136MHz

Aerial: 3 turns, tapped 3/4 turn from earth end, 18B&S enamel, 5/16in

ID x 8mm long. Padder 27pF.

Oscillator: Hairpin, 1/4in rad, 18B&S TC, 1/2in above board. Padder 27pF. Emitter resistor 470 ohms.

#### 140-150MHz

Aerial: 3 turns, tapped 3/4 turn from earth end, 18B & S enamel, 5/16in ID x 19mm long. Padder 15pF.

Oscillator: 16B&S TC link across appropriate holes on board. Padder 15pF. Emitter resistor 470 ohms.

#### 3.5MHz Output Transformer

Primary, 120 turns, 28B&S enamel, on Neosid former, 7.6mm x 60mm, 2 grade 900 slugs. Secondary, 12 turns, 28B&S enamel, over earthy end of primary.



## BEST PUMP VALUE EVER!



**3 MONTHS' GUARANTEE**  
Exclusive release ...  
**FAMOUS AMERICAN**  
**THOMPSON 1,000 G.P.H.**

## ELECTRIC PUMPS & MOTOR \$25

The world's most famous manufacturer of pumps! This is the third release of their pump and motor produced at a Govt. cost of \$185 each.


Pump and motor only \$25.00 Ball Foot Valve \$3.95 (2lb.) • **TERRIFIC BUY** - U.S. Govt. cost \$185 ea. • **AIRCRAFT QUALITY** - neoprene seal, fully ball bearing non-corrosive housing and impeller • **CONTINUOUS DUTY MOTOR** - sealed, ball bearing brush motor • **PUMPS ALL LIQUIDS** - water, kero, petrol, diesel fuel, etc. (1" outlet pipe for hose) • **LASTING QUALITY** - sealed unit, corrosion and explosion proof. Electric motor is for 24/32 volts AC/DC (perfect on 12 volt) and draws only 5 amps. Will shift 1,000 g.p.h. at 15 p.s.i., 800 g.p.h. at 6' head. On 24 volts pump will lift 40ft., less on 12 volts. If primed or with foot valve, will suck 20ft. then lift 20ft., less on 12 volts. Pumps have threaded inlet for 1" waterpipe. Has two bolt mounting base. Use pump as water pressure system for taps - have on/off switch (\$1) near tap. 7lb.



**HEAVY DUTY BATTERY CHARGERS**  
• Charges 6V and 12V Batteries overnight • High 4-amp. charge rate • 12 mths. written **GUARANTEE**. 9lb.



**Brand new "Pocket Tester" MULTIMETERS \$7.95**  
• 8 oz.  
Brand new circuit tester with high sensitivity and ruggedly built for checking any electric apparatus; and truck ignitions, motors, shorts, broken leads, etc. Measures all voltages to 1000V AC and DC ... DC current (milliamps.) resistance, etc. Complete with full instructions and probes.



**240V EXTRACTOR FANS \$4.75**  
**12 MONTHS GUARANTEE**  
Brand new English 240 volt A.C. mains operated fans. Make ideal extractor fans for kitchens, caravans and other domestic and light industrial purposes. Continuously rated, smooth, silent-running induction motor, 4,000 r.p.m., balanced 3-bladed, 6 1/2" fan. Size 6 1/2" dia. x 4" deep. 3lb.

# DIRECT DISPOSALS

35 SHOPS  
BRISBANE  
MAIL ORDER TO  
36 HELEN ST.  
FORTITUDE  
VALLEY  
BRISBANE, Q.  
PH. 52 4833




Top quality Philips type cassettes by famous maker sells at half price. Individually packed in plastic library box.

**C60 \$1.45 40z**

## HALF-PRICE SPECIAL HI-FI RECORDING TAPE

Fantastic purchase of "MYLAR" professional recording tape (the best money can buy). Famous 3-name brand (one we can't mention due to huge price reduction). Silicone lubrication. Suits all tape recorders, hi-fi and stereo. Selling well under half price. **ABSOLUTELY BRAND NEW.**

3" x 225' 65c — 40z; 5" x 600' \$1.75 — 80z; 5" LP x 900' \$2.45 — 80z; 5 1/2" LP x 1200' \$2.75 — 100z; 7" x 1200' \$2.25 — 100z; 7" LP x 1800' \$3.95 — 100z.  
3" Empty Spools 25c;  
5" Empty Spools 35c;



Famous English "ACOS" complete PICK-UP cartridges with **STYLUS**. Current issue to fit "Garrard" and most other types of players and decks from all countries. Complete with fixing screws and brackets. G.P. 92-1 hi output mono crystal cartridge which will play stereo records. A special purchase. **\$2.50**

G.P. 93-1 \$3.50; G.P. 93-1 diamond \$4.50; G.P. 94-1 ceramic sapphire \$5.00; G.P. 94-1 ceramic diamond \$5.50. The latest from "ACOS" type 104 transcription P.Z.T. ceramic stereo cartridge for use with magnetic input. Buy from us and save. \$7.50. All above packed in individual cartons. 20z.

## 7 TRANSISTOR AUDIO AMPLIFIERS \$4.95

Fresh 1973 current production. Made in England. Mullard transistors. Brand new with diagram. 2 watts output (peak). Specially designed to provide a complete and reliable basic unit for portable gramophones, radios, intercoms, tape recorders, P.A. systems, etc. Latest printed circuit design suitable for 3 to 15 ohm speakers. For use with 9V transistor radio battery. Frequency response 150-10,000 c/s. A pair are ideal for stereo. Size only 3" x 2". 100z. Usually sold at \$12.



## FAMOUS ENGLISH E.M.I. HI-FI SPEAKERS \$11.50

13 1/2" x 8 1/2" complete with tweeter. Handles to 10 watts, 8 ohm impedance. 55-11,000 H.Z.; Brand New in cartons, 1972 production, complete with instructions to build speaker box. 4lb Has ceramic magnet.

## PARCEL POST RATES

Up to	2lb	3lb	7lb	11lb	19lb	22lb
Ord.	45c	50c	55c	65c	75c	85c
Minimum Charge						
NSW&NT	65c + 8c per lb. over 8lb.					
TRNG & ACT VIC	75c + 12c per lb. over 6lb					
SA, WA, TAS.	80c + 20c per lb. over 4lb					
PACKET POST FOR ARTICLES						
1lb. 2.00 - For Aust. N.Z.						
7 P.N.G. 2.40z, 12c, 58 oz, 10c,						
9.16oz, 24c.						



Made by "Meccano" England. Input 15 volts AC, output 0 to 12 volts DC in fine smooth control. Has 8 speed control positions in both normal and reverse. Unit is a step resistance, rectifier controller for up to 2 amps. Also for reverse and has off pos. and pulse power switch for ultra slow running. Ideal for models etc. new in carton with instructions and guarantee. Worth \$9. 1lb



**WALKIE TALKIES**  
P.M.G. approved  
**\$47.50**  
NO REFUNDS ALLOWABLE ON THESE TRANSCEIVERS




Top quality 5" 5 watt, for rear shelf or door. 12ft. of lead each. Super special price! 500 to clear. 3lb.



A slim mike of outstanding performance. Sensitivity—78 db. 200 ohm. imp. 100—12,000 HZ. with stand, long lead and plug. New 1972 production. Ideal tape recorders, amplifiers etc. Mayfair brand made by "PIEZO". Us. sells at \$9. 6 oz.




**\$15.95 HONEYWELL PROGRAMMER**  
This is a drum type timing device. The drum being calibrated in equal divisions for switch setting purposes with trips which are indefinitely adjustable for position. They are also arranged to allow 2 operations per switch per rotation. There are 15 changeover micro switches each of 10 amp. type operated by the trips thus 15 circuits may be changed per revolution. Drive motor is 240V mains operated 5 revs per minute. Some of the many uses of this timer are Machinery control, Boiler firing, Dispensing and Vending machines, Display lighting animated and signs, Signalling, etc. Price from makers over \$65 each. Special snip price \$15.95 Don't miss this terrific bargain. These are brand new in maker's carton, 1972 production. 4lb.



**Geared Turntable Motor 2 1/2 RPM \$4.95**  
Beautifully made for completely silent operation with 7 stage gearing and overload clutch. 240 Volt mains operation cont. duty. 1/2 RPM at final drive through removable nylon toothed gear on final drive. Brand new. Ideal shop turntables etc. \$4.95. 12 oz.




**COMPUTER BOARDS**  
Set of 3 comprising 2 boards 7" x 5" with 1 board 5" x 4" comprising minimum of 25 transistors plus hosts of diodes, resistors, capacitors, inductors, etc. \$2.95 set of 3. 12oz.



**240v. Electric Pumps BRAND NEW \$14.50**  
Direct English purchase from a famous manufacturer. We purchased their entire stock of these **ABSOLUTELY BRAND NEW** in carton 240 volt electric motorised pump unit. Usually sell for \$25.00. Full 3 MONTH GUARANTEE. Special Neoprene impeller pump for pumping fuel, water, etc. Pumps 300-400 g.p.h. To be gravity fed and will lift to 8'. Ideal for fuel or water transfer, fountains, fish ponds, etc. Pump entirely non-corrosive. Rush your order now as stocks will not last at this price. 4lb

**3 months full Guarantee on all goods**  
**Money cheerfully REFUNDED if not completely satisfied.**



**GEM TUMBLER OUTFIT \$32.50**


As illustrated above (except for flat wood base) or purchase separately in components as under.

**TUMBLER ONLY \$10.75**  
2 mounting blocks, 4 pillow block bearings, shafts, pulleys and belts and 1/2 gal. barrel.

**TUMBLER & MOTOR \$27.50**  
19lb.

**TUMBLER, MOTOR & GRINDER 22lb. \$32.50**

The complete unit as illustrated. Incorporates extra pillow blocks, shaft, flax, coupling, flax, drive with chuck and 5 grinding stones. All units sold in kit form and takes minutes to assemble, instructions supplied, 3 months' guarantee.



**Electrically operated WATER VALVES \$2.75**  
**AUSTRALIAN MADE**  
Waterproof solenoid and moulded nylon valve casing construction. Valve mechanism is brass sleeve containing a spring-loaded plunger which loads a neoprene seal against the outlet port in the normally closed position. An encapsulated solenoid coil fits over the brass sleeve and operates from 230/250 volts mains supply to withdraw the plunger and permit the valve to open. 1lb.

Inlet 1in Outlet 1/2in BSP. 3 1/2in. long x 3in. overall.



**"TAS" 1hp. \$29.50**

**Amazing Offer — Famous 1 H.P. PETROL ENGINES**  
Made in Japan and brand new. **3 MONTHS WARRANTY 10lb.**




**GEARBOXES \$17.50**  
Ratio available 10.5 to 1. Made by David Brown, "Radicon" England. Very robust construction, has two driving shafts at right angles and oil filler plug. Unit is drilled for 4-bolt fixing. Size 4 1/2" x 4 1/2" x 3 1/2" 7/16" and 5/8" dia. x 1 1/4" long. Bargain (cost over \$100 to make). Bargain 100 only. Also "Radicon" gearboxes same as above 14.5 to 1 reduction \$19.50. 9lb



# Better system protection against transient voltages ... Better than selenium



## GE-MOV VARISTORS



GE-MOV™ metal oxide varistors make use of a new technology. They provide tight voltage clamping and high energy absorption . . . better than selenium. Present models offer AC voltage ratings from 100 to 1000V. Energy absorption ratings range from 10 to 160 watt-seconds (joules).

### GE-MOV SUPERIOR FEATURES:

- Clamping Ratio • Size • Peak Current • Energy Density

### COMPETING SELENIUM SUPPRESSORS

Mfrs.	Commercial or Trade Names	Device Nomenclature			
		Selenium Suppressors			
		1 inch Square	2 inches Square	4 inches Square	5" x 6"
IR (W)	Klip-Sel Volt-Trap	KSA SO1, 2AA	KSL SO3AA SO4AA	KSP SO6AA	KSF SO9AA
Syntron Sarkes Tarzian	Surge Stop Klip Volt	SD1544 2KV26	SD2650 5KV26	SD2411 7KV26	SD2452 10KV26

## AUSTRALIAN GENERAL ELECTRIC LIMITED

86-90 BAY STREET, ULTIMO, N.S.W. PHONE 212-3711

### DISTRIBUTORS:

Fairchild Australia Pty. Ltd., Sydney 439-4355, Melbourne 723-4131.  
PB Components, Melbourne 53-2766.  
GEC-Elliott Automation Pty. Ltd., Adelaide 71-7971, Melbourne 387-2811, Sydney 439-1922, Brisbane 32-0441.

Watkin Wynne Pty. Ltd., 32 Falcon St., Crows Nest, 43-2107.  
H. Rowe & Co. Pty. Ltd., Perth 28-5444.  
The National Electrical & Engineering Co. Ltd., Wellington 553-709, Auckland 599-089.



### New All Silicon 30 / 60W PA PORTABLE AMPLIFIER

12-16V, two inputs, 5mV and 100mV. Dimensions 6 1/2" W x 3 1/4" H x 8 1/2" D. 15 ohm output, No 763D, \$42. For 125, 250, 500 ohm output, No 763A, \$44. For 240V operation \$33 extra. 10W PA amplifier similar to above, 4 ohm output, 240V operation, No 729D, \$45. Freight extra.

### CD IGNITION COIL

For EA (Fraser) circuit. Mounted on strong fibreglass printed circuit coded for all other components. Polyester film layer insulation. Connected and tested. For standard distributor, No 787, for photo cell distributor, No 786. \$8 each. Postage 20c each.



### R.C.S. COMPLETE DO-IT-YOURSELF KITS

Peak reception. Low price. No expensive test equipment. Everything fits. 1964 RF Trans ports 7.

Complete kit — No 640 \$43.50  
Portable car radio. Identical to 640 above, plus extra switch and car coil, etc. No. 642 \$46.00  
Postage \$1.  
(Write for booklet on 640 and 642.)

### NEW TRANSISTOR PREAMP KIT

SIZE 3 x 2 x 1 1/2 in. 2 req. for stereo. LOW IMP input, 2 trans, 672C \$7.00  
Wired ready for use, 672D \$8.50  
HIGH IMP, 2 trans, 680C \$7.00  
Wired ready for use, 680D \$8.50  
HIGH IMP silicon, 3 trans, 682C \$8.50  
Wired ready for use, 682D \$10.00  
Postage 10c each. Write for data.

### COILS and IFs 455KHz

Aerial, RF, Osc and IFs \$2.20  
Ferrite aerial \$2.50  
No. 265 Universal tape Osc coil \$6.50  
Postage 10c. Write for details and price.

## ALL PRINTED CIRCUITS SINCE 1960 now available

Clearly coded for easy assembly. Accurate to size. With parts list. Im. mediate despatch.

- Accurately machine printed and etched.
- Specials to your drawing.
- Phenolic or fibreglass — gold or tin plated.
- Special manufacturers packs of 10.
- Order direct or write for blueprints list.
- Add 20c postage.


All printed circuits for EA, R & H, ET, Philips and Mullard projects available

### LATEST P.C.'s

831 EA 72/P3	827 ET021	834 ET026	847 72/GC	\$2.50
829 EA 72/T2D	828 ET023	795 ET025	796 71/SA4A	\$2.50
805 EA 72/P6	830 FA 72/R2	\$2.50 ea	858 73/3C	\$2.50
\$2.00 ea	832 EA 71/A8	835 EA 72/T3	860 73/D1	\$1.50
		836 EA 72/MX6	861 ET1416	\$3.00

### HI-FI BROADCAST TUNER UNIT 4 TRANSISTORS—HIGH SENSITIVITY

RF, mixer, IF power detector. Adjustable aerial coupling with 461 Dial, knobs, switch pot and whistle filter. Can be altered to 8, 9, 10 or 11kHz. Complete as illustrated no. 474D, \$35 + Freight \$1.50.



### 10W STEREO

MULLARD  
10 + 10W RMS

With output transistor PROTECTION. Frequency response 40Hz to 30KHz. Distortion 0.5 per cent. Treble, bass boost, 20dB.  
Complete kit of parts, No. 480C \$74.00  
Wired and tested, No. 480D \$79.00  
Cabinet as illustrated extra \$10.00  
Magnetic pickup preamp, No. 762D extra \$11.50  
Inbuilt BC tuner with w/ filter extra \$35.00  
Plus freight. Write for brochure. For special Saturday demo, ring 59 6550.



### NEW STEREO MAGNETIC PRE-AMP

Hum free, 5mV input, 250mV out. Size 3in x 2in x 1in. Wired ready for use. No. 762D. \$12.00. Post 10c.



### NOISE FILTER for radio and TV

No. 27 line filter, 2A \$9.00  
No. 29, 10A, No. 29B, 20A line filter \$35  
No. 30 pulse filter, 2A \$12.00  
No. 11 aerial filter \$14.00  
Order direct. Pack and post \$1.00.

### CRYSTAL, CERAMIC STEREO PRE-AMP

In 80mV., out 250mV. Bass and treble 20dB.  
Part No 722C — \$26.  
Part No 722D — \$28. Wired ready for use. Plus Post 80c.

### NEW BASS BOOST

#### 4-TRANSISTOR STEREO AMP

Unity Gain:  
400Hz, 0dB  
100Hz, 5dB  
50Hz, 9dB  
30Hz, 14dB  
Connect between your preamp and main amp  
No. 791D, \$11.00.  
Postage 20c.

### WHISTLE FILTERS

Part No 128, 8 + 10KC, Top Cut, \$4  
Part No 129, 10KC, Notch, \$5  
Plus Post 20c.

### LATEST PRINTED CIRCUITS

Freight \$1.50.  
843 72 EA SA10 \$2.80  
852 72 EA SA9 \$2.50  
853 72 EA M12 \$2.50  
850 ET034A \$2.60  
858 EA 73 3C \$2.50  
859 ET518 \$2.00  
860 EA 73 01 \$1.50  
861 ET 416 \$3.00  
Plus post 20c.  
DIAL KIT Playmaster 138 \$4.50 post 20c.

R.C.S.

Order by mail. Cheque or Money Order (add postage) direct to:—  
RADIO PTY. LTD., 651 FOREST ROAD, BEXLEY, N.S.W. 2207. 587 3491




## VHF Converter

into operation. We will assume that you have a suitable receiver — one which will tune 3.5MHz. If the receiver has a suitable supply, then the converter may share it. On the other hand, a separate 9V battery will do just as well. We will also assume at this stage that there is a suitable aerial.

Connect the converter to the receiver and its power supply. If you have a signal generator or have access to one which covers the frequencies of interest, then alignment will be that much easier to do. With an accurately calibrated signal generator, you may also calibrate your own dial scale.

Regardless of the frequency band which you have chosen, the method of alignment will be the same. During the process of alignment, the output level of the generator should be adjusted to avoid overloading the converter and receiver. Set the receiver to 3.5MHz and feed a signal from the generator set to 3.5MHz, into the aerial terminal of the converter. Adjust the slug in the output transformer for maximum response.

With the gang fully closed and the dial pointer set to 100 or other full scale reference point, tighten all dial drive grub screws. Set the trimmers on the gang so that they are about one quarter in mesh.



COIL CONNECTIONS VIEWED FROM ABOVE

Now search with the signal generator at around the wanted low frequency of the converter, until a signal is heard. Tune up 7MHz higher in frequency with the generator and the image should be heard. If no signal is found, then you were already tuned 7MHz too high. Having established the lower frequency, if it is too high, then the oscillator coil must be squeezed up until the right frequency is reached. If the frequency is too low, then the coil should be lengthened until the correct frequency is reached.


With the oscillator coil tentatively adjusted, the aerial coil must be brought into line with it. This can best be done by first testing to determine whether the coil is tuned either too high or too low in frequency. Take an ordinary iron dust or ferrite slug, 7-8mm diameter and approach the coil with it. If the signal strength drops, then the coil should be lengthened, to the point where maximum signal response is achieved. Should the slug result in an increase in signal strength, then the coil must be squeezed up until maximum signal response is reached.

Now tune the converter to the high frequency end of the dial but instead of setting the pointer to the extremity of the scale, it should be brought back by about

5pc. This will be the highest frequency point of the scale. Again search with the generator around the wanted high frequency point of the converter and establish the actual frequency to which the converter is tuned. Also, check that there is an image response when the generator is tuned 7MHz higher in frequency. Having established the actual frequency, set the generator to the wanted frequency and adjust the trimmer on the oscillator section of the gang until the signal is heard again. Now adjust the trimmer on the aerial section of the gang for maximum response.

In common with all superheterodyne receiving systems, the alignment procedure must be repeated at each end of the scale, until correct adjustment of oscillator and aerial tuning systems is achieved.

Readers may be wondering just how a "hairpin" coil, or a simple wire link can be adjusted to satisfy the foregoing alignment procedure. Well, the hairpin can be adjusted by unsoldering and slightly lengthening or shortening the arms as required. The parallel arms of the hairpin may also be brought closer or taken further apart, as an alternative means of adjustment. \*With regard to the link, we agree that there is little that can be done to alter its inductance. Either you must settle for what it provides or you may change the value



At left, the coil connections are shown as viewed from above. Details of a folded dipole aerial are shown above.

slightly of the paddor capacitor in series with it.

If you do not have access to a signal generator, then the task of alignment is not so easy. The output transformer may be adjusted on a subsequent signal, or even noise, with the receiver set to 3.5MHz. Alignment on the VHF range of your choice will depend upon the reception of signals of known frequencies and with calibration points set on the dial accordingly. Perhaps one of the best aids to alignment would be the sound channels of the various TV transmissions. The following is a list of the sound frequency for each of the channels.

0 — 51.75MHz; 1 — 62.75MHz; 2 — 69.75MHz; 3 — 91.75MHz; 4 — 100.75MHz; 5 — 107.75MHz; 5A — 143.75MHz; 6 — 180.75MHz; 7 — 187.75MHz; 8 — 194.75MHz; 9 — 201.75MHz; 10 — 214.75MHz; 11 — 221.75MHz.

An efficient aerial system is most desirable for use with this converter. A multi-element Yagi or other VHF aerial system would be ideal. If the wanted signals all come from one direction, then the aerial may be orientated to suit. On the other hand, if the signals come from different directions, it is desirable to make provision for rotating the aerial.

(Continued on page 125)

# Know Where You are Going

Choose a career in the field of Electronics — the Nation's most progressive and fastest expanding industry.

Advancement in this modern science demands technical ability, a sound knowledge of basic principles and applications. You can master the subject by training at the Marconi School, and be ready to grasp the opportunities that occur in the various branches of Radio Technology.

## BROADCASTING

A thorough grounding is available to students in the broadcasting field, leading up to the P.M.G. Broadcast Station Examination.

## COMMUNICATIONS (Marine)

An extension to the Broadcast Operators course and extending into the fields of Navigation Aids and Electronic Devices used in mobile communications as required by the P.M.G. Certificates of Proficiency.

## APPLIED SERVICING

Comprehensive training in the maintenance and repair of radio and television receivers offers substantial rewards to competent technicians. Marconi School training covers all aspects of radio and television receiver circuit applications, practical exercises in fault finding and alignment procedures.

The Marconi School Radio Servicing correspondence course is approved by the N.S.W. Apprenticeship Commission

Classes are conducted at:

67 Lords Road, Leichhardt.

Day: 9 a.m. to 4 p.m.

Evenings: 6 p.m. to 8.30 p.m. or by Home-Study Courses (except practical instruction on equipment).

SEND FOR PROSPECTUS

There is no obligation

NAME .....

ADDRESS .....

MARCONI SCHOOL OF WIRELESS

Box 218, P.O., Leichhardt 2040

A service of  
Amalgamated Wireless (Australia) Ltd.





# New, Universal Headphone Unit

Does your amplifier have facilities for headphone listening? For two people? With main speakers on or off? If your answer is no to any of these questions then our new headphone adaptor may be just the device you're looking for.

by N. J. MARKS & W. N. WILLIAMS

As will be apparent from the accompanying photograph, the new headphone adaptor is compact, with a pleasing appearance, and can be placed if necessary on an open shelf alongside other items of hi-fi equipment. It does not need to be tucked out of sight.

It is "universal" in the sense that it can be used with virtually any amplifier and it will accommodate two pairs of headphones, which can be of dissimilar type and appearance.

The internal circuitry is so arranged that the level of one pair can be preset, relative to the loudspeaker volume. This semi-fixed channel could also be used with phones having their own in-built level controls.

Volume from the other outlet can be controlled conveniently by front panel

knobs to meet varying needs. It can be adjusted, if necessary, to cope with the needs of a listener who is hard of hearing and or afflicted with an imbalance of hearing acuity.

Because of these special facilities, the adaptor may, in fact, find a use with many amplifiers having an in-built but more limited headphone facility.

When considering headphones, it is appropriate to stress that modern, high fidelity headphones exhibit lower distortion and a response that is much wider and smoother than any of the older, general purpose types. Reproduction, overall, compares very favourably with that from high fidelity loudspeakers, with the best headphones comparing favourably with the best loudspeakers. This, in terms of available listening level, clarity of reproduction,

frequency response, etc. Subjectively, however, there is a difference in the apparent distribution of the sound, when using headphones.

On fully dispersed stereo program material, the listener has the sensation of sitting within the orchestra, with most of the instruments dispersed on either side.

With the more gimmicky "two-channel" type of stereo recording, the listener has the impression of sitting between two distinct groups of musicians. With a "three-channel" type of recording, there is an additional group inside his head!


These impressions are not present when listening to a normal stereo loudspeaker set-up. The sound sources are usually in front of the listener, not adjacent to his ears. Each ear hears each sound source, both by direct and reflection paths, and the listening situation more closely approaches that which it would obtain if the performers were actually located at the far end of the listening room.

Because of the different illusions created, it is possible to argue that headphones are not a legitimate method of listening to ordinary stereo program material. Be that as it may, however, the reproduction can be very satisfying and an alternative far to be preferred to no listening at all! In fact, headphones have advantages of their own.

They do not suffer from apparent attenuation of the high frequencies due to "beaming" effects as do loudspeakers, since the headphone aims right into the ear, as it were. At low frequencies, provided the phones are adequately sealed to the head by flexible surrounds, headphones can produce plenty of undistorted bass; they do not have to set up a large wavefront in a room and cannot excite boomy room resonances. Finally, because the diaphragms need to make only small excursions to move a limited amount of air, they may well contribute less distortion than would many loudspeakers.

These arguments aside, the real reason for the increasing popularity of headphones is that they enable one to listen to music at any time of the day or night, without restriction to the listening level, and without disturbing neighbours, babies or parents.

In designing a universal headphone adaptor, a number of matters have to be considered relating to the drive require-



*As will be apparent from the picture at the top of the page, our new universal headphone adaptor can be used as a free-standing unit, alongside other equipment. Internally, the use of a tagboard and laced wiring can give it a professional appearance.*



ments of headphones and the load conditions presented to the amplifier.

Depending on impedance relationships, headphones clamped to the ears are effectively much more sensitive than any kind of loudspeaker system standing several feet away. This leads to complications which are likely to inhibit the connection of headphones directly to the output stage in lieu of loudspeakers.

The first arises from the fact that practical amplifiers have some inherent noise and hum output, even with the volume control turned right down. Through a loudspeaker system this is normally not troublesome but, heard through earphones, it is often quite objectionable and sufficient to compromise enjoyment of the program.

Another aspect is that since so little audio power is necessary to produce adequate output from the headphones, the volume control may have to be set at a critical position, not far advanced from fully off. If, by chance, it happens to be turned up too far, the headphones could easily be damaged.

A possible secondary effect is that, at such low volume control settings, the balance between the respective sections of the volume control may be anything but good, requiring manipulation of the balance control to equalise matters.

The answer to these problems is the provision in the adaptor of an attenuation circuit (or "pad") such that only portion of the voltage at the output of the amplifier can reach the headphones. It will reduce the hum and noise fed to the phones and allow the amplifier to be operated with the volume control somewhere near setting normally employed for loud-speaker listening.

Such a pad should be so designed that it will work with any type of headphone, irrespective of the impedance. In practice, impedance ratings may range from a few ohms to a few hundred ohms.

One very suitable arrangement, which we have used on a previous occasion is to connect a 47-ohm fixed resistor and a 100-ohm slider or potentiometer in series across each amplifier output circuit. The phones are connected between one end of the slider (or potentiometer) and the adjustable tapping; this ensures a full range of level control in the phones, relative to the amplifier setting, without danger of adversely loading the amplifier's output circuit.


If, as here, it is desired to provide for two pairs of headphones the network in each channel is simply duplicated.

Our adaptor unit provides the appropriate networks, together with switching to connect the headphones to the amplifier, or the loudspeakers, or headphones and loudspeakers simultaneously.

On its own, a headphone network of this type provides only light loading. While most high quality amplifiers are tolerant of this condition, there may be the odd one which will not be so. In any case, complementary symmetry transistor output stages need a suitable DC load circuit, because the load forms part of the bias network.

For the above reasons we have included a 22-ohm, 5-watt resistor as a dummy load for each channel, which is brought into circuit when the adaptor is switched to headphone only. This value is low enough to ensure correct operation of all amplifiers likely to be encountered and is high enough for the 5-watt rating to be adequate for likely levels of operation.


In normal stereo systems, the loud-



**UNIVERSAL HEADPHONE ADAPTOR**

1/MS/10

Wired as shown in the circuit, the unit retains complete independence of the two loud-speaker output circuits in the straight-through "loudspeaker only" function. By using a blocking capacitor in the headphone feed line and taking the return back to chassis by a fifth lead, a DC path is avoided between the output circuits. In the "Headphones Only" position, a 22-ohm resistor provides loading and a DC path in lieu of the loudspeaker voice coil.



For those who want to make a close copy of the prototype adaptor, this wiring diagram should provide all the necessary information. In fact, the layout is not critical and the unit could be constructed inside any convenient housing, metal or non-metal, more fancy or less fancy than our original. See text regarding the coupling capacitors.



# Rabco


## STRAIGHT LINE TRACKING SYSTEM

THE UNIQUE CONCEPT THAT ELIMINATES BOTH SKATING FORCE AND TRACKING ERROR


### Comparison between pivoted arm and RABCO arm

The four unretouched photographs below are of an oscilloscope presentation of a 400Hz tone recorded on a disc at 25 cm/sec. groove velocity. A high quality, high compliance cartridge was used with 1½ grams stylus force. Anti-skating required by the pivoted arm was set at the manufacturer's recommended force.


Pivoted arm  
400Hz tracing  
on outer  
groove.





RABCO tone  
arm 400Hz  
tracing on  
outer groove.



Pivoted arm  
400Hz tracing  
on inner  
groove.



RABCO tone  
arm 400Hz  
tracing on  
inner groove.



The SL8 E Tone Arm



The Rabco ST4 Professional Turntable with Rabco Tone Arm System

Imported and Distributed by

Jervis Australia Pty Ltd  
PO Box, 08 Brookvale, NSW 2100  
Telephone 939-2922

**AVAILABLE ONLY THROUGH HIGH FIDELITY SPECIALISTS**



speakers are independent units, each fed by a separate twin lead. Internally, the output circuits of the two amplifiers may be independent of each other in respect to both the active and neutral wiring. It is wise to preserve this isolation, at least in respect to the loudspeakers, to minimise the risk of introducing unforeseen complications.

The need to preserve isolation can be a problem with many types of headphones because they use a common return (or neutral) lead. For this reason we have suggested a 5-wire circuit between the amplifier and headphone adaptor. Four wires maintain the separate active and neutral leads for loudspeaker operation; the fifth wire allows the headphones to derive their drive from between the respective actives and chassis.

One further complication which needs to be provided for has to do with amplifiers which operate with the loudspeaker circuitry above chassis potential: ie neither side of the loudspeaker is returned to chassis earth.

While it may be possible to check on each amplifier with a voltmeter, or by inspecting the circuit, we have provided for the eventuality by including 250uF / 25VW electrolytic capacitors in series with each active headphone feed line. This will prevent the headphones and their related volume controls from providing a DC path between the amplifier active outputs and chassis.

Note that if the DC potential of the voice coil proves to be negative with respect to the chassis, as was the case with one or two circuits we have seen in overseas magazines, the polarity of the electrolytic capacitors in the adaptor unit would have to be the reverse of that shown in the circuit and wiring diagrams.

To make the adaptor truly universal, the isolating capacitors could be replaced by a bipolar configuration derived by connecting two 500 ufd 25VW electrolytics in series opposition ie with the positive leads connected together and the negative leads taken to the rest of the circuit. On the other hand, if you are absolutely sure that the capacitors are not needed with your amplifier, they can be omitted.

In our previous design for a headphone adaptor, we used a diecast metal box to house the components. For this later version we have adopted a more stylish approach by using a small instrument case, comprising mainly aluminium extrusions and pressings.

The case we used is a "Horwood" H43 / 6, approximately 100mm deep, 75mm high and 150mm wide. This case has the advantage of being composed of separate panels, screwed together, which makes for easier work on drilling holes, painting and final assembly. Other styles of case could well suggest themselves to the home constructor. The circuitry could even be built into an existing amplifier, providing panel space is available for the knobs and headphone jacks.

Smaller components were mounted on a 19-lug segment of tag-strip which was spaced off the rear panel by two brass spacers approximately 2cm long, tapped  $\frac{1}{16}$  Whitworth. Two of the screws holding the loudspeaker sockets are used to mount the spacers which were covered with a length of insulating sleeving to prevent any accidental shorting to the speaker socket connections.

We used McMurdo 2-pin plugs and sockets

on the prototype but if your amplifier uses a different type of plug or means of connection, it might be logical to duplicate them on the adaptor.

The two preset sliders are mounted at one end of the tagstrip followed by the 47-ohm dropping resistors, the 250uF isolating capacitors and the 22-ohm dummy load resistors.

The cable used to connect the adaptor to the amplifier should most obviously be a five-core type. Alternately various types of four-core cables with some cores shielded might be more readily available; the braids could be used as the common return to chassis for the headphones.

Terminations are protected by clamping the cable where it enters the case through a grommetted hole. The two neutral leads for the speakers are taken direct to the sockets on the back of the case; the active leads go to the switch.

Once you have completed the adaptor, you can connect it to your amplifier and check for correct polarity of the active and neutral leads.

On those amplifiers with screw terminals for the loudspeaker connections, the active side may be coloured red or coded with a "plus" sign. If this is not the case, the active side of the speaker output may be determined by trial and error when the adaptor is completed; if the headphones are effectively connected between neutral side of the amplifier output and the amplifier chassis, no sound will be heard.

When everything is properly connected, turn the front panel potentiometers and the sliders to their minimum position.

Put a record on the player and with the switch in the "speakers only" position, adjust the volume to the average listening level.

Switch to the phones only position and adjust the sliders to give you a satisfactory level with the phones in the appropriate socket and repeat this performance with the front panel controls and their socket. In this way you won't need to leap for the volume control when you plug in the 'phones for some personal listening.

You won't hear any noticeable difference in speaker output when the selector switch is in the "Speakers plus phones" position, due to the minimal loading of the attenuator network.

Incidentally, if you make up an extension cord using a stereo phone plug and socket, and a length of three-core cable, sound can be conveyed to somebody confined to bed, so that they can enjoy the music along with other members of the family, or alone.

## PARTS LIST FOR THE HEADPHONE ADAPTOR

- 1 Horwood H / 43 / 6 case
- 1 4-pole 3-position switch. Oak 52259 or similar
- 2 Stereo jack sockets
- 1 19-lug piece of component strip
- 2 Speaker plugs and sockets
- 2 250uF / 25VW Electrolytic capacitors (see text)
- 4 47-ohm  $\frac{1}{2}$ -watt resistors
- 2 22-ohm 5-watt resistors
- 2 100-ohm slider resistors
- 2 100-ohm wire-wound potentiometers
- 3 knobs, 5-conductor cable or 4-conductor with shield, cord clamp, hook-up wire
- 2 brass spacers tapped  $\frac{1}{16}$  Whit 2cms long screws, nuts etc.

# PIHER



## TRIMMER - POTS SERIES PT



PT 10 v



PT 15 h (2'5)

Two basic sizes available - PT 10 Series - 10 mm diameter and PT 15 Series - 15 mm. diameter.

New patented design which offers fully enclosed construction protecting the carbon track and wiper against dust, dirt, solder flux etc. Also prevents track damage due to maladjustment, which is a common problem with open track type presets.

Ability to trim or adjust from either side with screw driver slot.

- Alternatively knurled knobs available.

- Spindle shafts can be specified if required.

## CHARACTERISTICS

	PT 10	PT 15
Mechanical	240°	270°
Torque	50 - 200 pcm	50-250 pcm
Rated dissipation	0.20 W	0.25 W
Working voltage	150 V	200 V
Curves	lin	
Temperature range	-10° C a 70° C	

AVAILABLE FROM LEADING WHOLESALEERS

or send direct to:

**GENERAL ELECTRONIC SERVICES  
PTY. LTD.**

114 Alexander St. Crows Nest  
N.S.W. 2065 Australia  
Phone 439-2488



## NEW ALL-TRANSISTOR STEREO AMPLIFIERS WITH IN-BUILT A.M. TUNER ULTIMATE IN DESIGN— LONG DEPENDABILITY

using all silicon transistors 50 WATTS - RMS

### SPECIFICATIONS

**POWER OUTPUT:**  
25 watts per channel R.M.S. Total output  
50 watts R.M.S. 8 Ohms  
**FREQUENCY RESPONSE:**  
20 cycles to 40,000  $\pm$  1db.  
**HUM & NOISE:**  
Aux. 70db. Mag. 60db.  
**INPUT SENSITIVITY:**  
Mag. 2mv. Aux. 250mv.  
**EQUALISED:**  
Mag. RIAA.  
**TONE CONTROLS:**  
Bass 50 c/s  $\pm$  13db. Treble 10kc/s  
15db.  
**HARMONIC DISTORTION.**  
Less than 0.5 per cent.  
**LOUDNESS CONTROL:**  
50 c/s 10db.  
**SCRATCH FILTER:**  
(high filter) at 10kc/s 5db.  
**RUMBLE FILTER:**  
(low filter) at 50 c/s 5db.  
**PROVISION FOR TAPE RECORDER.**  
Record or play-back with din plug  
connector. Tape monitor switch.  
**SPEAKER SWITCHING:**  
Two sets of speakers can be connected  
and selected by switch on front panel,  
they can also be driven together.  
**HEADPHONES:**  
Headphone jack is situated on front  
panel.  
**DIMENSIONS:**  
16 1/2" X 11in. deep X 5" high Weight  
16lbs  
**TUNER:**  
This unit incorporates a transistor  
tuner with a coverage of 530 to 1,600 K. C.  
Calibrated dial available for all states.  
**POWER SUPPLY.**  
Regulated power supply with switching  
protection for output transistors.  
**SEMICONDUCTORS.**  
30 silicon transistors plus 7 diodes.




**\$169.00** Plus Freight  
(cabinet extra)

Model C700-T (with Tuner)

**Amplifier Only**  
**Model C.700**  
**\$139.00 Plus Freight**  
**Cabinet Extra**

**Provision For 4  
Channel**



All units wired with sockets & control for simulated 4 channel only requires the addition of two extra speakers, also output socket for decoder.  
Cabinets for above amplifiers in Teak or Walnut Oiled Finish with matching metal trim \$10.00 extra

### NEW MODEL C600-T 36 WATTS RMS

36 WATT (18 watts per channel) VERSION OF THE C700-T AMPLIFIER WITH TUNER, SPECIFICATIONS AS FOR THE C700-T BUT LESS THE FOLLOWING: PROVISION FOR SIMULATED 4 CHANNEL, SPEAKER SWITCHING (outlet for one set of speakers only) & tape monitor switch. SUPPLIED IN TIMBER CABINET TEAK OR WALNUT FINISH.

**\$158**

FREIGHT  
EXTRA

### — NEW MAGNAVOX-ROLA 3 WAY SPEAKER SYSTEM —

FREQUENCY RESPONSE 35Hz to 25KHz

POWER HANDLING CAPACITY 30 Watts R.M.S.

#### DRIVE UNITS:

Magnavox 8-30 High Performance 8in Bass Unit •  
Magnavox 6J — 6in Mid Range Speaker • Rola X30  
High Fidelity Dome Tweeter

COMPLETE SYSTEM in 1.6 cubic ft. cabinet. In  
Walnut or Teak Veneer (Size 24" x 15 1/2" x 11").

**\$69.50** ea. *Regret no Mail Orders for Complete System.*

**SPEAKER KIT:** (less cabinet) comprising 1 8-30 speaker,  
1 6J speaker, 1 Rola X30 dome tweeter, 1 1mh. in-  
ductance, 1 8 mfd. & 1 4mfd. polyester condenser, 1 3" &  
1 6" tube, innabond & speaker silk, plans for cabinet.  
(Philips Dome Tweeter can be supplied at \$3.50 each kit  
extra.)

**\$36.00** *Reg Post & Packing \$2.00 Extra.*

## NEW 26 WATT R.M.S. AMPLIFIER-TUNER

BASED ON ELECTRONICS AUST. MOST POPULAR UNIT

### THE PLAYMASTER 136

**\$129.00**

WITH THESE ADDED FEATURES

- TRANSISTOR TUNER WITH A COVERAGE OF 530 TO 1,600 K.C.
- CALIBRATED DIAL AVAILABLE FOR ALL STATES.
- LOUDNESS CONTROL.
- RUMBLE FILTER (low filter).
- SCRATCH FILTER (high filter).
- HEADPHONE SOCKET.
- CABINET IN OILED TEAK OR WALNUT FINISH.

DIMENSIONS — 16 1/2" x 4 1/4" x 11" DEEP.



MODEL C136

FREIGHT  
EXTRA

## CLASSIC RADIO

245 PARRAMATTA RD, HABERFIELD 2045  
PHONES 798 7145, 798 6507



# Mains Monitor

## Measure the Mains without getting "zapped"

Ever wanted to check the AC mains voltage while working on a new project, or look at the power consumption of an appliance while trouble-shooting? Here is a simple little unit, using only a handful of low-costs parts, which allows you to measure both mains voltage and current — and without the risk of shock.

LEO SIMPSON

There are often occasions when it is necessary to monitor the AC mains voltage. For example, when checking the line regulation of power supply it is necessary to vary and monitor the mains input voltage. Another case is the power output test of an audio amplifier, where the test may not be valid if the mains input voltage is not correct. Many other situations can arise in the design and testing of circuits and appliances where it is necessary to know the value of the mains voltage.

Measuring the mains voltage with a multimeter is not very convenient and it can be unsafe. For the person inexperienced in such situations it can be a nerve-wracking experience. One must generally push the meter prods into a power point, or measure across the active and neutral pins of a 3-pin plug pushed part way into a power point. Or maybe you can measure the voltage at some accessible point in the circuit or appliance, which is slightly better.

The possibility of a shock arises if the user's hands are perspiring and sweat has accumulated on the meter prods. The electrical leakage path so formed to the user's hands can be sufficient to deliver quite a nasty "bite." Worse, if your hands slip down the prods, you are in direct contact with the mains supply — in the worst possible condition for a fatal shock.

Often it is desirable to monitor the mains voltage continuously and this means that meter has to be disconnected each time some other measurement is required.

Clearly what is needed is a unit which plugs into a standard power point to measure the voltage — so that the user is in no danger of coming into contact with lethal mains voltage.

If voltage measurement poses a problem, that of current measurement is even greater. For a start, most multimeters lack facilities for measuring AC current. If they

do have AC current ranges, one of the AC leads to the appliance or circuit must be "broken" so that the meter can be connected in series for current measurement. Sometimes this is easily accomplished by removing the appliance fuse and clipping the meter prods to the fuseholder terminals. Mostly, it is not a simple procedure — especially when the device has a hard-to-disassemble case and a moulded cord plug.

One ought to be able to plug the appliance into a unit and read the current directly from a meter without fiddling with any connections. The less chance the user has of being exposed to mains voltages, the longer he is likely to remain a reader of "Electronics Australia" and able to pursue all his other activities!

With these thoughts in mind, we developed our AC "Mains Monitor." One can plug an appliance into it and at the flip of a switch, read the AC mains voltage applied to it or its current consumption up to a maximum of 5 amps. Multiplying the two readings together will give the volt-amps consumption of the device, or if the device is a resistive load such as a radiator or incandescent lamp, the power consumption in watts.

With the maximum current rating of 5 amps, our Mains Monitor is limited to measuring the current consumption of appliances with nominal ratings of less than 1200 volt-amps (VA) or 1200 watts. For most appliances this will not be a problem.

Heart of the Monitor is the Ferguson PF 3596, a low voltage transformer meeting the Australian Standard C126, where applicable with respect to insulation and winding construction. It is used here "backwards," as a current transformer. It has two low voltage windings, each with a nominal rating of 6V at 10VA; these are connected in parallel and the current to be monitored is passed through the composite winding. The 240V "primary" winding is used to develop a voltage proportional to the current in the low voltage windings, across a 100 ohm 5 watt resistor.

A maximum rating of 5A has been decided upon as it results in a power dissipation inside the transformer of a similar order to that in its normal mode of operation when it delivers 20VA to a full wave rectifier with capacitor filter. We strongly advise against modifying the circuit in any way to measure current in excess of 5A. In addition, if the unit is intended to be used measure current near the maximum rating for extended periods, adequate case ventilation must be provided. The transformer will be hot.


In this circuit it is possible that 240 volts AC will be applied between the low voltage windings of the transformer and its core, even though the transformer is shown connected in the Neutral "side" of the circuit. However even if this occurs the transformer is safe since its insulation rating is the same for the low voltage windings as for the 240V winding — we have the assurance of Ferguson Transformers Pty Ltd in this regard. Note that this may not apply to other transformers, so that substitution should only be made after carefully assessing the safety aspects.

The AC voltage developed across the 100 ohm resistor is applied to a bridge rectifier consisting of four germanium small-signal diodes. The rectified AC is then fed to 1mA FSD moving coil meter via a 12k resistor. This results in a FSD sensitivity of 5 amps.

A general-purpose silicon diode shunts the



A novel use for an economy transformer.



7 / M / 44



# MICRO

the  
magnificent!



In June, 1972, Australian Hi-Fi Magazine said:

*"There is no doubt that the Micro MR 611 is a fine turntable, and after a long period of usage, we are unable to fault it" . . . "This is a transcription turntable made to professional standards" . . . "It appeals to people who demand only the best that money can buy."*

In the Micro range, you'll find a turntable that gives good performance at a reasonable price, or like the MR 611, ultimate performance regardless of price. The Micro range includes: MR 611, MR 111, MR 211, MR 311 turntable/base/cover. MB 300, MB 600, MB 800S turntables only.

Micro cartridges M2100/6, M2100/E, VF 3100/7, VF 3100/E, broadcast-station-standard VF 3200/E, and MC 4100/E moving coil. Also MA 101 Mk11 4-channel arm, and Micro Electrostatic Headphones.

**Available from:**

**N.S.W.** M & G Hoskins Pty. Ltd., 37 Castle St., Blakehurst 2221  
Telephone: 54 1464  
**Q'LD** Stereo Supplies, 95 Turbot St., Brisbane 4000  
Telephone: 21 3623  
**S.A.** Challenge Hi-Fi Stereo, 6 Gays Arcade, Adelaide 5000  
Telephone: 23 2203  
**TAS** Audio Services, 72 Wilson St., Burnie 7320  
Telephone: 31 2300  
**VIC** Ence Electronics Pty. Ltd., 431 Bridge Rd., Richmond 3121  
Telephone: 42 3762  
**W.A.** Albert TV & Hi-Fi, 282 Hay St., Perth 6000  
Telephone: 21 5004

**Sole Australian distributors:**

**INTERNATIONAL DYNAMICS**  
(AGENCIES) PTY. LTD.,  
P.O. BOX 205, CHELTENHAM, VIC. 3192

**INTERDYN**



meter movement for applied voltages in excess of 600mV, so that the meter is effectively protected against mechanical damage in the likely event of overload on the current range. Incandescent lamps, motors and transformers all have considerable surge current at switch-on, so this form of protection is very necessary.

Note that the current-monitoring winding of the transformer is in series with the load at all times. The voltage drop across this winding at the maximum current of 5 amps is 2 volts (RMS). This is less than the likely measurement error of the Monitor, so it can be regarded as negligible.

To measure the mains voltage the meter circuitry is switched in series with a multiplier resistor across the active and neutral leads. The multiplier consists of a

parallel combination of 820k and 1M resistors.

Switching from the voltage to current ranges is performed by a double-pole, double-throw switch. The switch must be rated for 240VAC operation.

When calibrated, the Mains Monitor will accurately indicate the RMS value of sinusoidal voltage and current waveforms — ie, those most often encountered. It will not give an accurate indication of the value of chopped waveforms from phase-controlled thyristors or Triacs or half-wave rectified AC. To measure these waveforms accurately, an RMS indicating meter is required and a different mode of current sensing.

**CONSTRUCTION:** Assembly of the Mains Monitor is a straightforward process

and apart from satisfying safety requirements, layout is not critical. No doubt many readers will have their own ideas on the format. Our Monitor was assembled in a sloping front panel case, with a three-pin mains socket mounted on one side.

It is important that mains cord termination is done properly. The cord should be passed through a grommeted hole in the rear of the case and securely anchored by a clamp. The earth lead is terminated to a solder lug at the rear of case which also terminates the earth wire from the three-pin socket. The active and neutral wires are terminated on a four-way insulated terminal block, as shown in the wiring diagram.

The transformer is mounted with the normal "240V" winding at the front of the case. The current monitor windings are connected to the four-way terminal block. Also accommodated on the terminal block are the two multiplier resistors for the 240V range.

Connection of the two low voltage windings is critical. If it is not done correctly, the magnetic fields from the two windings will not add and the Monitor will not work. See the wiring diagram and inside photograph for the details.

## PARTS LIST


1. sloping front case, 13 x 13 x 13cm.
- 1 Ferguson PF 3596 power transformer.
- 1 DPDT 240VAC toggle switch.
- 1 moving coil meter movement, 1mA sensitivity.
- 1 three-pin mains socket.
- 4 rubber feet.
- 1 four-way terminal block.
- 1 seven-lug length of miniature tagboard.
- 1 EM4005, BY126 / 50 silicon diode.
- 4 1N34 germanium diodes.

### RESISTORS


- ( $\frac{1}{2}$  watt, 5 pc tolerance unless specified)  
 1 x 100 ohm 5 watt, 1 x 12k, 1 x 220k,  
 1 x 820k, 1 x 1M

### MISCELLANEOUS

Mains cord and plug, mains cord clamp, solder lug, hookup wire, screws, nuts, lockwashers, solder.



Simple to wire up, the Mains Monitor frees your multimeter for routine measurements.



We used a standard 1mA meter movement. The 0 to 1 calibrations were removed with a typing eraser and 0 to 5 substituted with Letraset rub-on lettering. Only one scale is used for both ranges. The reading is multiplied by 100 for voltage so that 250 volts is indicated in the centre of the scale.

Remaining components in the circuit are mounted on a seven-lug length of miniature tagboard mounted on the rear of the meter movement. Do not cut the pigtailed of the diodes too short when mounting, otherwise they may be damaged when soldering.

Calibration of the Mains Monitor can only be done by comparison with a meter of known accuracy. Calibrate the current range first, by adjusting the high value resistor in shunt with the 12k resistor. Calibration of the voltage range can now be done by adjusting the 1M resistor shunting the 820k resistor.

If you do not have another meter handy we suggest you install the components we have shown. This will result in an accuracy of about the same as likely component variations, about plus or minus 5 pc. 2



# Its every word is crystal clear.



You won't miss a word with this fully solid state Acitron SSB025 transceiver. The crystal stability combined with the special 'noise blanker' ensures maximum clarity at all times.

It operates in the frequency range of 2-12 MHz and is ideal for long range communications. Operation is simplicity itself.

The transceiver is particularly compact and light but it's tough too. Takes any amount of handling whether in mobile, portable or fixed station use.

The Acitron SSB025 is designed and made by ACI Electronics in Australia to RB209 and fully backed by service. Like to know more? Then mail this coupon for a technical brochure.

ACI Electronics  
310-324 Ferntree Gully Road,  
Clayton North, Victoria, 3168.

Please send me technical details of your  
Acitron SSB025 transceiver.

Name: .....

Company position: .....

Company name: .....

Address: .....

.....Postcode.....

**ACI**

**A.C.I. Electronics**

ACE2780FP/R.



# Digital Clock - Addendum

Fairly obviously, the Low Cost Digital Clock described in the June issue has been very popular. Already we have received a lot of "positive feedback" regarding the project, including some worthwhile modifications which we are happy to present here. They include three simple schemes to allow conventional readout of the twelfth or twenty-fourth hour.

by LEO SIMPSON

The "Low Cost Digital Clock" published in the June issue of Electronics Australia was attractive in that it was simple to build and contained relatively few parts. However, it did have one major drawback: For 12-hour operation, it counted to 11.59 and then reset to 00.00 and so on. Similarly, for the 24-hour mode, it counted to 23.59 and then reset to 00.00. This scheme was adopted because of the apparent difficulty of resetting to 01.00.

At the time, we felt that the limitation was not serious enough to prevent publication of the article. Now, three readers have come to light with simple modifications to allow conventional operation, by permitting automatic resetting to 01.00.

Mr P. Hardy of Woomera, South Australia has evolved an elegantly simple modification which involves no extra components and uses one of the un-utilised NAND gates in the second 7400 quad NAND gate. Fig. 1 shows the circuit.

When pins 2 and 3 are both high, a 7490 will reset to a condition where outputs A, B, C and D (pins 12, 9, 8 and 11 respectively) are all low. This is decoded by the 7441 decoder/driver IC to provide an output at pin 16, which normally drives the zero digit of the appropriate numerical indicator tube. However, if pin 16 of the HOURS 7441 is connected instead to the numerical indicator tube cathode which indicates 1, then the clock will be effectively reset to 01.00, not 00.00.

Similarly, all other cathodes are moved to read one higher. This means that pin 15 of the 7441 connects to the "2" cathode instead of "1" and so on. Finally pin 2 of the 7441 connects to the "0" cathode instead of "9".

Since the HOURS output is now shifted by one step it is no longer possible to connect the output from pin 11 of the HOURS 7490 to pin 14 of the following "HOURS x 10" 7490, since the change of state indicating the zero condition for the HOURS 7490 occurs at a different time, i.e. at the normal count of "nine" which has now become "zero".

To overcome this problem, a two-input NAND gate is used to detect the incidence of the new "zero" condition (pins 12 and 11 high). The output of the NAND gate is used to drive the "Hours x 10" 7490. The additional gate is one of the previously unused sections of the two 7400 quad two-input NAND gates used in the time-setting circuitry.

As with the original clock, the two 7490s driving the HOURS readouts may be wired to provide 12 or 24 hour operation merely by wiring in the links shown dotted on the diagram. For 12-hour operation, wire the

dotted links marked 12 and for 24-hour operation, wire in the links marked 24. With the simple modification the circuit now counts to 12.59 or 24.59 before resetting to 01.00.

Another interesting solution to the resetting (from 12.59 to 01.00) problem was presented by Mr R. Kempton, of Herne Hill, Victoria. His circuit modifications are shown in Fig 2.

As with the previous circuit in Fig 1, the output of the HOURS 7441 to the numerical indicator tube has been shifted up by one for all digits, so that the "nine" output now corresponds to "zero". However the "Hours x 10" 7490 has now been deleted and is

connected to the B, C and D outputs of a 7490 decade counter. Pin 3 of the 7441 is connected to pin 8 (output of the RS flip-flop) of the 7400. If pin 8 is low, "0" will be indicated, if pin 8 is high, "1" will be indicated.

Suppose that initially pin 8 is low and zero is being indicated by the Hours x 10 readout. The HOURS 7490 counts through from 1 up to 0. When this happens, pins 11 and 12 of the 7490 go high and the NAND gate monitoring this condition drives pin 9 of the 7400 (one of the RS flip-flop inputs) low. This triggers the flip-flop so that pin 3 of the associated 7441 is driven high and "1" is indicated by the Hours x 10 readout. At the same time, the HOURS 7490 is reset to zero and recommences its count.

When the 7490 reaches 3 (according to our new code) the NAND gate monitoring the B output (pin 9 of the 7490) drives the other input of the flip flop low and flips the Hours x 10 readout back to "0". At the same time, the 7490 is reset to 1 and the process recommences. Note that in the second half of the cycle, 13.00 is not shown by the readouts — this condition is instantaneously reset to 01.00 as soon as it occurs.




Fig 1. This modification allows conventional readout for 12 or 24-hour operation.

replaced by a 7400 quad two-input gate. This has been ingeniously interconnected to provide an RS flip flop (similar to that used in the time-setting circuitry) and the two remaining gates provide trigger pulses to the appropriate RS flip-flop inputs. It works as follows:

Since the "Hours x 10" 7441 only has to give a "0" or "1" indication (for 12-hour operation), pins 4, 7 and 6 are connected to the negative rail. These pins are normally

In its own way, this modification is also elegant and it has the advantage that it uses the cheaper 7400 device instead of a 7490. Against this, it can only function as a 12-hour clock. If 24 hour operation is desired, the circuit in Fig 1 must be used. Note that in Fig. 2 the "Hours x 10" 7441 is being used not as a decoder at all, but merely as a driver for the two readout tube cathodes.

A further suggestion has been made by Mr Kempton, as shown in Fig. 3. If the





## IT'S ONE THING TO BUILD A RADIO. IT'S ANOTHER THING TO BUILD A 3 INCH OSCILLOSCOPE. APPRENTICES IN THE SERVICES DO.

Whatever field of engineering or communications turns you on—we've got it. Some so secret we can't even tell you about it. But it's there. In the Navy, the Army and the Air Force. And to function properly it needs skilled operators and technicians to maintain and service it. And there are no dead end jobs here. If you've got the ability, you could go on to university and commissioned rank.

Either way, you'll enjoy the finest training that money and dedicated instructors can provide. And you're set for life with a skilled technical trade that's acknowledged everywhere. In the meantime, you'll enjoy the extras such as meals and accommodation; free medical, optical and dental care; free initial clothing; free text books and tools of trade and free travel home on leave twice a year. And the time for fun and relaxation with a great bunch of mates. If you think you're the

### DEFENCE FORCES APPRENTICESHIPS

TO: Service Careers Officer,  
G.P.O. BOX XYZ in your State Capital City.  
Please send me information about life as an apprentice in today's NAVY/ARMY/AIR FORCE (Indicate your preference).

Name

Address

Postcode  Date of birth

sort of guy we need and you're 15 or under 17 (Navy 17½ yrs.) before entry, we'll send you some literature. Just send in the coupon or drop in to your nearest recruiting office. There's no obligation. Applications close soon.

Townsville: Navy, 71 5253; Army, 71 6784; Air Force, 71 3191. Brisbane: 31 1031. Newcastle: 2 5476. Sydney: 29 2122. Wollongong: Army, 28 6492. Canberra: Navy, 65 3318; Army, 47 6530; Air Force, 65 2225. Orange: Army, 62 1755. Melbourne: 61 3731. Geelong: Army, 9 6780. Warrnambool: Army, 8378. Ballarat: Army, 32 1614. Bendigo: Army, 43 8008. Yallourn: Army, 62 2346. Launceston: Army, 31 1005. Hobart: Navy, 23 7054; Army, 20 0141; Air Force, 34 4116. Adelaide: 23 2891. Darwin: Navy, 81 6451; Army, 89 0911; Air Force, 89 9911. Perth: 22 4355.

Authorised by the Director General of Recruiting, Department of Defence.



time-keeping of the clock appears erratic it could be because of noise pulses "riding" the 50Hz mains-derived trigger waveform fed to the 7490 divider stages. The circuit in Fig. 3 acts as a pulse squarer to improve noise immunity. It uses two 7400 NAND gates, which may be already available if the Fig. 1 modification is used.




Fig 3: A Schmitt Trigger for the 50Hz input.

Last to present a circuit modification was Mr P. Tsui of Balaclava, Victoria. He has substituted a 7410 triple 3-input gate for one of the 7400s, and has eliminated one of the 7490 counters. The modifications are included in an abbreviated version of the June circuit shown in Fig 4.

Readers may recall that the "divide by 5" 7490 (first) in the divider chain has an unused flip-flop. This has been teamed with the "divide by 5" section of another 7490 to drive the HOURS 7441 decoder, using the original decoding system. The remaining flip-flop in this latter 7490 is then used to drive the HOURS x 10 7441 decoder. Only two output electrodes of this decoder, pins 15 and 16, are connected to the HOURS x 10 indicator tube. The rest can be left floating.

Operation is as follows: Consider the HOURS circuitry counting from 01.00 to 12.59. On arrival of another input pulse to the HOURS section, the clock attempts to indicate 13.00. However, the 3-input NAND gate monitoring pin 3 and 8 of the HOURS 7441 and pin 3 of the HOURS x 10 7441 immediately senses the HIGH condition of these pins. Its output goes LOW and the following NAND gate functioning as an inverter drives the reset pins, 3 and 2, of the 7490 HIGH and thus resets the flip-flops to zero.

The flip-flop connected to pin 3 of the HOURS decoder is not reset to zero. Consequently, the HOURS indicator reads 1 and the time indication is 01.00 instead of 13.00.

Perhaps this represents the neatest and




Figure 2: A decoding change and a flip-flop connected 7400 allow 12-hour readout.

most efficient of the three solutions to the original decoding problem, as it uses all available circuitry — there are no unused gates or flip-flops. But it has the drawback that it does not provide 24-hour operation. It also requires two long interconnections from the 1st 7490 in the divider chain to the HOURS circuitry.

Several other modifications can be made to the clock circuit to improve its operation. First, the zener diode in the regulator circuit can be increased to a 5.6V device, BZY88/C5V6 and the associated resistor reduced to 220 ohms. As it is, the nominal 5V supply is a little on the low side. In addition, the HT rail can be filtered with a 4uF/300VW electrolytic capacitor to provide greater brightness from the readout tubes. The PIV rating of the diode should be increased to 600V at the same time.


Kitsets Australia Pty Ltd advise that they can supply the compact readout tubes used

in the prototype. These are of Japanese origin and are brighter than some of the locally available tubes.

Doubtless there are more of our readers who have worked out equally ingenious modifications to the basic circuit featured in June and we are glad to have provided the initial stimulus. We appreciate the interest of readers who have written in on the subject. However, we regret we can devote no further space to this design.

In conclusion, we make note of several corrections to the circuit diagram published in the original article in June, 1973. First, pins 1 and 2 of the HOURS 7490 should be connected together. Secondly, the 1 PPM output from the "divide by six" 7490 should be taken from pin 8 rather than pin 11. Finally, two 0.1uF suppression capacitors were omitted. These are included in Fig 4 and are connected between the positive supply in the divider stages and the negative rail.

Fig 4: Conventional 12-hour readout with no change in decoding and elimination of one 7490 decade counter.





# An Introduction to Marine Acoustics



## PART TWO

In this second article of the series, the Author explains the factors which set a frequency limitation on underwater communications and shows the conflict between the useful transmission band and the concentration of marine noise. He discusses the various types of underwater transducer and indicates how a practical device can be contrived from a conventional magnetic earphone.

by J. D. PENROSE Ph. D.

(Physics Dept, West Australian Institute of Technology)

In the first article of this series a number of applications of marine acoustics were described and the importance of the refraction and reflection processes illustrated.

For many applications the way in which the sea absorbs sound and the background noise spectrum of the marine world must also be considered. For example, the recording and analysis of noises made by fish and crustaceans, a field now being explored by hobbyists and amateur scientists around the world, calls for an understanding of these topics, as does any attempt to use sound waves in a communications role.

The dominant feature of sound absorption in water, including sea water, is the strong frequency dependence observed. This is shown in Fig 1, where the absorption coefficient for sound is plotted against sound frequency. Both distilled water and sea water strongly absorb high frequency sound so that frequencies above about one megacycle are impractical for communication links of more than a few metres.

Low frequency, eg audio range sounds, however, are only slightly attenuated and so may be used to transmit information over long distances. An example of this was treated in the discussion on SOFAR trans-

mission in the first article in this series.

Another example can be heard by swimmers in the vicinity of an outboard motor boat. The sound heard through the water can be quite loud, since water attenuates low frequencies less than an air path, and human hearing under water is reasonably effective. The sound is also much duller and flatter than that heard through the air link above the water. This effect can be striking if the boat to swimmer distance is about a quarter of a mile, illustrating vividly the way in which the sea acts as a low pass filter for sound waves, with preferential absorption of the higher frequencies.

Two major mechanisms have been proposed to account for the strong frequency dependence of absorption coefficient. The most important of these is the shear viscosity process, and the dotted line in Fig 1 indicates the absorption behaviour to be expected if this mechanism operates alone.

Fig 2a,b shows what is meant by a shear displacement. If the rectangular block being deformed is made of rubber, or indeed any solid material, it will behave elastically in this mode of deformation. This factor permits the formation of sound waves with transverse vibrations, ie in

which particle movement is perpendicular to the direction of sound propagation.

For fluids such as air and water, the deformation of Fig 2b is not associated with any elastic reaction. Transverse oscillations are suppressed, leaving only the longitudinal mode in which particle movement is parallel to the direction of sound propagation. However, although there is no elastic reaction to the shear process of Fig 2 during sound propagation, viscous or frictional losses certainly occur.

Fig 2c shows how the deformation may be viewed rather as the similar movement of a pack of cards and shows how one card (or layer) needs to slide on another. This relative movement of adjacent layers of water uses up energy at a rate which is roughly proportional to the speed of the relative layer movement. Thus shear deformations, which are unavoidable, even in longitudinal mode sound propagation, use up energy in "rubbing" adjacent water layers together and these viscous energy losses increase sharply as the faster "rubbing" associated with high frequencies takes place.

The second major mechanism proposed to account for frequency dependent absorption has been the process of thermal conduction between adjacent areas of compression and rarefaction in the sound wave. That part of the medium which suffers a compression at some instant in time is heated, just as is the air in a tyre pump; conversely, adjacent areas of rarefaction are cooled. Inevitably, some conduction of heat takes place momentarily between the temperature difference areas and some energy is lost from the wave motion.

In practice, this second process is of lesser unimportance in a water medium and it remains true that the viscous drag



mechanism explains most of the features of the data in Fig 1. Curiously, the striking difference observed at 100kHz and below between sea and distilled water has been shown to be associated with the concentration of about 0.17 per cent of magnesium sulphate in the sea; it appears to involve a complex interaction between this compound and water molecules.

Overall, the absorption characteristics of the sea have restricted all but a few applications to make use of frequencies below 500kHz and most, including virtually all echo sounding gear, to 200kHz and below. Lower frequencies transmit well in the marine world and would be ideal for many purposes were it not for a direct result of their good transmission properties — that is, the prevalence of low frequency components in the background noise spectrum.

In other words, since low frequency noise propagates farthest, most noise recordings in the sea, other things being equal, will show a predominance of low frequency components. The kinds, locations, power output and spectra of marine noise sources will control ambient noise conditions.

Noise sources in the sea are of three main kinds — wave action, surface agitation and man-made noise. Fig 3 shows the main features of a typical noise spectrum measurement in the ocean. The main features shown are firstly the predominance of low frequency sound, mainly generated by oceanic turbulence. Waves control most of the spectrum between .01Hz and 1Hz and contribute some noise up to 10Hz. Water droplets, either from spray or rain, provide sound energy, while turbulent flow within the body of the sea and at the ocean floor adds further noise. Distant storms and seismic events may also be involved as low frequency sources.

Man-made noise, mainly ship noise, occurs in the middle of the spectrum and the hump shown in Fig 3 has been shown to depend strongly, particularly in North Atlantic waters, on the overall density of ship traffic in the region. The various lines in the high frequency end of Fig 3 are meant to indicate a dependence on wind and sea conditions near the measurement point and are largely due to surface agitation mechanisms, such as the droplet process already described.

Bubbles also play an interesting role in the noise spectrum. They are produced by wave action, fish, decaying matter and sea floor seepage. Also, atmospheric gas supersaturation can occur near the surface, with consequent bubble formation around nuclei. Overall, sea water will contain, particularly near the surface, a population of air bubbles, most of which are very small. These bubbles act as tiny resonators when any pressure disturbance strikes them and oscillate at their resonant frequencies, thus adding to the high frequency region of the noise spectrum.

Noise from marine animals and organisms, while not a large part of the noise level in the sea, has been given close attention, particularly to investigate possible communication behaviour and as a guide in developing fishing technology. Sound appears to play an important part in whale and dolphin behaviour and many non-mammals have characteristic noise patterns. Typical is the loud clicking of the snapping shrimp and the stridulation noise of the western rock lobster — a familiar

sound to skin divers in search of a crayfish dinner!

Assessing the role of sound in the behaviour patterns of animals in the sea continues to be an intriguing research area and is one in which the conventional divisions between scientific disciplines are readily broken down.

Sound absorption behaviour and noise level results together provide two of the limiting factors associated with choice of operating frequency for many applications of marine acoustics. For example, the designer of a communications device of the type to be described in the third article in this series seemingly needs to choose a low operating frequency to give a long range link, yet a high operating frequency to avoid the noisiest part of the background spectrum!

Operating frequency choice also depends on the type and size of transducer available and this topic will now be considered.

The term transducer, properly used, applies to any device that converts energy from one form to another. In practice, it is often restricted to cases where the energy is associated with information transfer; it is certainly applied to the class of objects in marine acoustics which transform sound pressure to electrical voltage and vice versa. Three main mechanisms are in use in marine transducers; these employing magnetostrictive, electrostrictive and electromagnetic principles of operation.

Magnetostrictive transducers employ the effect familiar to many people in electronics, ie the tendency for a ferromagnetic




Fig 1: Illustrating the relationship between frequency and the absorption coefficient of distilled water and sea water. The difference apparently has to do with the chemical content of the latter. The dotted line indicates the likely level of absorption due to shear viscosity alone.




Fig 2: The phenomenon of shear displacement. A cube of "elastic" material (a) is deformed by shear stress as indicated in (b). With a non-elastic medium, such as water, the deformation or displacement resulting from shear stress is best represented by an array of sliding layers as in (c).

material to change its dimensions as its state of magnetic induction is varied. A hard working TV line output transformer can often be heard whistling away, and suburban pole transformers can make their presence audibly noticeable. Many transformers and chokes working in the audio range can also be heard due to the action of magnetostriction.

Ferromagnetic materials such as iron and nickel have atoms which have unusually large magnetic moments, ie each atom is a minute magnet of considerable strength. The magnetic moments of adjacent atoms tend to interact so that the atoms group themselves together in minute assemblies called domains. In an unmagnetised sample, the directions of magnetisation of the domains are randomly oriented, though within each domain all of the atomic moments are parallel. When such a sample is placed in an external magnetic field, either the atomic moments within the domains line up with the field, or




Fig 3: A typical plot of ocean noise level against frequency. The main sources of noise in the various frequency zones are indicated above the graph.




Fig 4: The strain versus flux density for nickel. Note that the change in length ( $\Delta l$ ) does not bear a linear relationship with flux density.




Fig 5: Illustrating diagrammatically the principle of a magnetostrictive transducer. The nickel core contracts by an amount  $\Delta l$ , because of the magnetic field produced by the signal current  $\Delta i$ .





Fig 6: Three common shapes for electrostrictive transducers, which change certain of their dimensions with the application of a signal voltage. They are analogous to capacitors.




Fig 7: The transducers pictured in Fig 6 have metallised surfaces, as indicated above. They need to be polarised by one means or another to ensure a linear relationship between dimensional change and signal.

the domain walls grow so that those domains lined up with the field grow at the expense of the others. The movement of domain walls and atomic moments causes length changes which are independent of the direction of the applied field. The changes are positive in some materials and negative in others. An example of the latter is nickel which shrinks on application of a field.

Fig 4 shows the fractional decrease in length,  $\Delta l/l$ , plotted against applied magnetic flux density  $B$  in Webers per square metre. From the point of view of acoustics use, the important parameter is  $\Delta l$ , ie the total change in length for a given piece of nickel. This will control the amount of movement a nickel transducer is able to apply to the sea water in contact with its radiating face.

Fig 5 illustrates the contraction brought about by the influence of a magnetic field  $B$  produced by current in the energising coil.

As Fig 4 shows, the relationship between  $\Delta l$  and  $B$  is of square law form, ie

$$\Delta l = C_1 B^2 \quad \dots \dots \dots 1$$

where  $C_1$  is a constant.

Since  $B$  is proportional to  $i$ , a transducer as shown in Fig 5 would not be linear; it would not give an output sound wave which was linearly related to some signal current  $i$  but rather to current squared. For this reason, magnetostrictive transducers are subjected to an additional fixed value polarising field  $B_0$  which is either provided by permanent magnets or by a direct current component in the energising coil. In any case, the displacement,  $\Delta l$ , is now given by:

$$\Delta l = C_2 B_0 B \quad \dots \dots \dots 2$$

where  $C_2$  is another constant.

The device, now said to be polarised, is now linear, since  $\Delta l$  is proportional to  $B$  and hence to the signal current  $i$ .

In practice, magnetostrictive transducers are laminated to reduce eddy current losses but even so are essentially restricted to the range 10kHz to 60kHz although applications to 100kHz have been made. They have been widely used in echo sounders and are often actuated, in the transmitting mode, by a simple spike pulse and allowed to ring at their resonant frequency.

Electrostrictive devices have the widest range of application of the three classes. All

dielectrics exhibit electrostriction, but the effect is only sizable in a class of materials called ferro-electrics which are directly analogous to the ferromagnetics. Within ferroelectric materials, electric dipoles are formed spontaneously and aggregate into domains which, under the influence of an electric field, adjust their size and position and cause small changes in the physical dimensions of a sample.

Ferroelectrics, like ferromagnetics need polarisation in order to function as linear transducers but in the ferroelectric case, this is readily done during manufacture so that no external polarising field need be applied.

If ferroelectrics are heated above their Curie temperature, all the electric dipoles are disordered but may be aligned in any




Fig 10: The equivalent circuit of an electrostrictive transducer. Best examples of the device are the ferroelectric materials.




Fig 8 (above): The impedance of a transducer can typically be assessed by operating it in the laboratory in a container of water.

Fig 9 (right): The impedance curve of an electrostrictive transducer in water. The transducer area was 5 square centimetres and thickness 5 millimetres.

direction within a heated sample by applying a strong electric field in that direction. When cooled the field still applied, the sample retains this "frozen in" polarisation and is then linear. Samples can be made in almost any form and are of a ceramic nature.


Fig 6 shows a collection of common electrostrictive transducers and Fig 7 indicates where metallised surfaces have been applied to make the contacts. Since the ferroelectric material, often barium titanate or, more recently lead zirconate titanate (PZT) is a dielectric, the addition of these metallised contact surfaces effectively turns these devices into capacitors as well as transducers. This factor needs to be kept in mind when connecting an electrostrictive device to circuitry.

Since the electrostrictive device is both a capacitor and a mechanical oscillator, it is difficult to visualise how to connect it to, for example, a continuous wave oscillator so as to obtain maximum power transfer from oscillator to transducer and into the sea water. One wants to know what output impedance to choose for the oscillator unit.

This question can be answered quickly on the bench by making a direct measurement of the transducer impedance. Consider an example, involving a disk transducer of the kind shown in Fig 6 and 7 immersed in water. This was arranged as in Fig 8 and its impedance determined at various frequencies by comparing the voltage across the transducer with the voltage across the known resistor.

Fig 9 shows the way in which transducer impedance varied with frequency around a dominant dip in the curve associated with "half wave resonance" of the sample. This is the simplest mode of oscillation of the flat disk and is illustrated also in Fig 9. The transducer should be operated at this frequency in order to transmit maximum power into the water. Provided this was done, the transducer concerned presented an impedance of 44 ohms to the driving circuitry. The mounting and encapsulation necessary to protect it in the marine world would be expected approximately to double this figure.

These results are more easily understood if the equivalent circuit of the device is considered. This is shown in Fig 10 where the mechanical oscillator function has been converted into an analogous electrical circuit. This is made up of an inductor  $L$ , analogous to the oscillating mass elements of the transducer, a capacitor  $C$ , analogous to the elastic properties of the transducer








Fig 11: A practical transducer for underwater use can be made up from a magnetic earphone, as indicated here and described in the text.

and two resistive elements  $R_m$  and  $R_w$  which represent vibrational losses into the mounting and the water.

The analog circuit of the mechanical oscillator has the resonance seen in Fig 9 at:

$$f_r = \frac{1}{2\pi\sqrt{LC}} \dots \dots \dots 3$$

At this frequency maximum energy is dissipated into the resistive elements and thus into the load  $R_w$ .

However, the transducer is still a capacitor ( $C_o$ ) as well and  $C_o$ , as shown in Fig 10 shunts the mechanical oscillator. For continuous operation at  $f_r$ ,  $C_o$  often has an inductor  $L_o$  connected across it chosen such that:

$$f_r = \frac{1}{2\pi\sqrt{L_o C_o}} \dots \dots \dots 4$$

The combination of  $L_o$  and  $C_o$  then forms a rejector circuit which offsets signal losses through  $C_o$ .

Electrostrictive transducers are used in a wide range of marine applications including sonar, some echo sounding and passive listening uses. Generally, single element transducers are not very efficient at low frequencies although many have been used, together with suitable amplifiers, in experiments to monitor fish noises.

In any marine use, lead connection and transducer mounting and encapsulation need to be carefully done. Leads must be connected to the metallised surfaces of the type shown in Fig 7 and this may be done in one of three main ways: Carefully arranged mechanical clamping can be used if good contact is assured but this adds to mounting losses. Leads may be glued using, e.g. conducting Araldite or may be soldered using a silver bearing solder. In the latter case, care should be taken not to overheat the

transducer and exceed the Curie point which, in barium titanate is about 120 C.

Generally, glued or soldered leads cannot be expected to have a load bearing role and separate mounting arrangements must be made. These often take the form of casting or encapsulating the device in an epoxy resin which should ideally have similar acoustic properties to sea water. In practice, most casting resins will be satisfactory provided the transducer is not coated too thickly.



Fig 12: A typical underwater electromagnetic transducer, constructed on a handyman basis, around magnetic earphone components.

Space does not permit a detailed discussion of electromagnetic transducers, which have the particular advantage of high output in the audio range but Fig 11 illustrates how a workable underwater electromagnetic earphone may be constructed from an old headphone. The headphone is mounted in a waterproof PVC housing filled with alcohol or brake fluid. Thus the unit contains no airspaces and will not collapse under water pressure. The fluid in the housing loads the diaphragm considerably and it is usually necessary to rewind the coils of the electromagnets if low voltage signals are employed. Some variation in frequency response of the unit can be achieved by this process and also by drilling vent holes in the diaphragm. Fig 12 shows the completed unit.

In the third and last article of this series, some of the techniques described here will be applied to several interesting underwater projects.

## "OXFORD"

RADIO CHASSIS  
INSTRUMENT CASES  
ENGRAVED & PRINTED PANELS  
"MINI BOXES" (Aluminium)  
Speaker Cases  
Rack & Panels (To Order)  
Stainless Steel Work (To Order)

Wardrobe and Carroll  
Fabrications Pty. Ltd.

Box 330 Caringbah 2229  
Phone 525 5222

## COLOUR TV TEST EQUIPMENT

What equipment is needed?  
Can your present equipment be updated at low cost?

Check with A.T.C. first

**AUSTRALIAN  
TRANSISTOR CO**

P.O. BOX 74  
MOUNT WAVERLEY 3149

# YOUR OWN ELECTRONICS LIBRARY



A collection of "Electronics Australia" makes an ideal reference library, and now with these new, elegant binders you can turn your copies of "Electronics Australia" into a permanent library that will be a handsome addition to your bookshelf. Holds six current issues, size 11" x 8".

**\$2.50 for one, or  
\$4.50 for two**

MAIL THIS COUPON TODAY

ELECTRONICS AUSTRALIA BINDER OFFER

P.O. BOX 93, BEACONSFIELD

Please rush to me by return mail

☐ 1 BINDER ☐ 2 BINDERS

I enclose a ☐ cheque ☐ postal note ☐ money order  
for ☐ \$2.50 for 1 binder \*  
for ☐ \$4.50 for 2 binders \*\*  
(TICK APPROPRIATE SQUARES)

NAME.....

ADDRESS.....

POST CODE.....

\* For 1 binder, please add 50c for packing and postage

\*\* For 2 binders, please add 60c for packing and postage



# Total Quality from Germany

The



Perfection

**ALL NEW 1973 Models  
with Latest *DIAMATIC***

*exclusive to PE. = BY ATRAM*

Lowest Priced quality German turntables.  
Ask for our Special Price Concession.  
Personal Shoppers only Buy direct



## *Hi-Fi class Multimat Turntable*

Single control lever centre — Speed control — Autiscating —  
Four pole shielded synchronous motor — 4-4lbs. balanced  
platter, non-magnetic diecast — All metal tonearm, low  
resonance precision ball bearing supported—Adaptor for  
VTA control.

*German Hi-Fi International*

By

**ATRAM PTY LTD**

We sell





Perfection

5 McLAREN STREET, NORTH SYDNEY, NSW 2060. 92 4177.  
44 LOTHIAN STREET, NORTH MELBOURNE, VIC. 329 8211

GLEN-DOR CAMERA CENTRE,  
43 The Corso, MANLY.

*Also exclusively available from*

PHOTO HI-FI,  
367 Pitt Street, SYDNEY.





# Auto-trigger

## a control circuit for time-lapse movies

Ever thought you'd like to make those intriguing time-lapse movies where normal events are "speeded up," so that clouds swirl across the sky, flowers bloom in an instant, and a car or train seems to be travelling at incredibly high speeds? Hook this little unit up to your movie camera, and all these effects will be easy to achieve.

by LEO SIMPSON

Every day, many scenes are unfolding before our eyes. Our whole world is changing: buildings are erected and demolished, landscapes change, plants grow and die; large numbers of people move from place to place; the weather changes continually and the sun rises and sets.

Trouble is, we seldom really see these things happening. Many of them happen too slowly for us to appreciate them — or to put it another way, our lack of concentration means that we don't bother to watch them. We rarely have the time just to watch a complete sunrise from the first glimmerings of dawn until the sun is fully risen, nor do we have the time to watch and appreciate all the other changing aspects of the world around us.

Seen in this light, time-lapse photography represents a very worthwhile challenge to the movie hobbyist. As well as presenting a lot of technical problems, it provides interesting, educational and often funny film sequences. For example, if we were to take a film of people entering and leaving one of Sydney's railway stations during a peak period and compress it to last just a few minutes, we would have a very funny and convincing demonstration of the ant-like behaviour of people.

Whereas normal motion pictures are produced at the same frame speeds used for projection, from 16 to 25 per second, time-lapse movies are produced at lower frame speeds to suit the subject. For a flower opening when it is exposed to daylight, we might use one frame per second exposure; for a plant growing, we might use one frame every hour. After the film sequence is processed, it is run through the projector at the normal frame speed, producing a resultant speed-up in motion.

Some of the more expensive movie cameras for home use have variable frame speed from one frame per second upwards. Other cameras have a socket for a standard shutter release cable to enable single frames to be exposed at whatever rate the user requires. So unless one has the former type, the simplest way of doing time-lapse movies is to set the camera up on a tripod and periodically press the shutter release cable every second, minute, hour or whatever. But as well as being the simplest method, it is also the most tedious.

Our approach to this problem has been to develop a timer circuit which periodically closes a relay, whose contacts may be used to operate the camera at the required intervals. The timer intervals are adjustable in eleven steps from one second to twenty

minutes (longer time intervals can be arranged). That takes care of the time intervals, but two problems remain.

Lighting is the first problem. If you are exposing film over a period of time it is unlikely that the lighting will remain constant. In many cases artificial lighting will have to be provided, and this poses the question of whether floodlights or electronic flash will be used. If floodlights are used, provision must be made to ensure that they are fully on before each exposure and switched off or down afterwards; if electronic flash is used, provision must be made for correct synchronism of flash and shutter.

The second problem arises because few movie cameras have provision for remote electrical triggering of the single-frame function. Those few cameras which do have this provision will mate with the trigger unit very simply, but with the majority of cameras it will be necessary to provide some sort of mechanical actuator between the two, to operate the single-frame shutter release. The most likely choices would be either a solenoid or a small motor, energised in each case via the relay contacts provided on the trigger unit.


We must stress that you should solve this problem before you start to construct the trigger unit itself, for the fairly obvious reason that without a suitable actuator, the trigger will be virtually useless.

When developing this project we could not obtain a suitable low-voltage solenoid to operate a shutter release cable. Some readers may be in a position to have one made or make it themselves. But this is not an easy task, as the solenoid must have considerable thrust yet be reasonably economical in terms of current drain.

An easier approach is to obtain a 12V automotive windshield wiper motor and linkage system from a car wrecker's yard. You will need one which automatically "parks" the wipers when they are turned off. This type has a cam-operated pair of contacts on the motor which can "hold" and "break" the circuit every revolution of the gearbox output shaft. The gearbox is enclosed in the motor housing.

Current drain of the motor will be of the order of a few amps, depending on the type. It should be possible, considering the proposed intermittent operation of the motor, to run it from a pair of 6V lantern batteries connected in series to provide 12 volts. The wiper linkage system will have to be adapted to operate the shutter release cable, but this should not be too difficult for those with a reasonable degree of mechanical skill.

In operation, the timer relay will energise the motor for about a half-second, following which the motor contacts should take over to maintain the circuit for one revolution of the output shaft.



2/PT/7



# COPAL Model 801

## DIGITAL WALL CLOCK

Complements any decor in home or office.

- "Flip card" system gives instantaneous time change.
- Whisper quiet synchronous motor.
- Big bold numerals 3" high. White on black for maximum visibility.
- Twelve-hour time indication clearly marked AM and PM. Also available in 24-hour readout.
- Resetting from bottom knob.
- Colours in light grey, red or yellow.
- Size 11 $\frac{1}{8}$ " w x 7 $\frac{3}{8}$ " h x 5 $\frac{1}{2}$ " d.
- Fully guaranteed.




## DIGITAL TABLE CLOCKS

A range of eight electric mains, or battery operated, digital table clocks is available in both calendar and alarm models—12 and 24-hour types. Illustrated below are the 702 and 229 models.



**Model 702**  
Electric luxury alarm. Extruded aluminium case in bronze or gold. Neon illuminated. Seconds indicator graduated each five seconds. Snooze alarm.



**Model 229**  
Electric desk or table. Mini-sized calendar and alarm. Neon illuminated. Available in red, black, white and woodgrain. 177 mm x 66 mm x 82 mm.


For further information and availability, contact the sole Australian agents:

**J. A. DAVEY PTY. LTD.**

133 Abbotsford Street, North Melbourne Vlc. 3051

Telephone: 329 8922

JD-16



® "Sonalert" is a registered trademark and is manufactured by P. R. Mallory & Co. Inc., U.S.A.

## Sonalert® electronic audible signal

- Automotive, Marine & Aircraft warning systems
- Intrusion & burglar alarms • Swimming pool splash alarms • Code practice oscillators • Pressure & temperature sensing • Operation with photocells • Liquid level indicators • Voltage variation warnings • Industrial applications

### SIGNAL PRINCIPLES

The Sonalert electronic audible signal is a solid-state device which emits a compelling sound on a minimum current. The standard model is the SC628. This model operates on as little as 6 volts DC but accepts 28 volts DC. Current requirements range from 3 to 14 ma. depending on input voltage. Sound output is proportional to input voltage and ranges from 68

db @ 6 VDC to 80 db @ 28 VDC. Frequency of the SC628 unit is 2800 Hz ± 300 Hz which corresponds to the resonant frequency in the piezoelectric transducer used in the Sonalert. This frequency is generated by a transistorised circuit which is an integral part of the unit and cannot be altered by external means.

**PLESSEY**

### Plessey Ducon Pty Limited

Box 2 PO Villawood NSW Australia 2163  
Telephone 72 0133 Telex 20384  
Cables DUCONCO Sydney

Melb: Zephyr Products Pty. Ltd. 56 7231  
Adel: K. D. Fisher & Co. 42 2920  
Bris: Douglas Electronics Pty. Ltd. 62 1899  
Perth: H. J. McQuillan Pty. Ltd. 68 7111  
Everett Agency Pty. Ltd. 8 4137  
N.Z.: Henderson (N.Z.): 64 189



We must stress that we have not tried this approach. It is only a suggestion, but one which we think can be made to work with the application of a little ingenuity.


Having worked out a solution to the drive problem, the timer circuit can be built. It is a simple module, containing one integrated circuit and one silicon PNP transistor, together with a relay and a handful of minor components.

Heart of the timer is the Philips OM 802, which is a new monolithic integrated circuit primarily intended as a low frequency relaxation oscillator. Its main advantage is a very low triggering current, which enables the provision of very large time constants with modest capacitance values. Putting it another way, it is possible to obtain large time intervals with modest capacitance values and large resistors.

Maximum supply voltage rating of the OM802 is 12V, so we have designed the circuit to suit a 6V rail. The basic relaxation oscillator circuit consists of only one 50uF / 6VW tantalum capacitor, 14 resistors and the integrated circuit. The OM 802 comes in a four-lead metal TO-18 package, identical in appearance to the silicon RF transistor BF115.



Above is the prototype trigger module and below is the wiring diagram.



Referring now to the circuit diagram, the output at pin 4 of the IC is normally high, so that the 50uF capacitor charges toward the positive supply rail via the 560 ohm resistor and the timing resistor string wired around an eleven position switch. When the voltage across the capacitor rises above the threshold voltage set by the internal circuitry of the IC, the capacitor is discharged and the output at pin 4 drops to almost zero, applying 6V across the 560 ohm resistor. When the capacitor is discharged the cycle repeats, continuously. The 1k resistor provides current limiting during the

discharge time into pin 2.

It is possible to connect a relay, shunted with a diode, in place of the 560 ohm resistor and this would result in a very simple timer circuit. However, the time for which the output at pin 4 is low depends on the overall time constant of the circuit. For example, for a timer interval of 5 seconds, the output pulse may last for about one second whereas for a ten minute interval the output pulse may last several seconds.

If the timer was used to drive a solenoid where the time of power application was not important it would be acceptable, although it would be wasteful of power. If it was used to control a motor, however, power would be applied for longer than required for one frame exposure, which would mean that several frames were exposed instead of one.

This problem has been solved by adding a single transistor stage with a differentiating RC network in the base circuit and having

## PARTS LIST

- 1 OM 802 integrated circuit (Philips)
- 1 BC158, BC205 silicon PNP transistor
- 1 EM401 silicon diode
- 1 400uF / 12VW electrolytic capacitor
- 2 50uF / 6VW tantalum capacitors
- 1 250 GDO relay (STC) and mounting socket
- 1 eleven position rotary switch

### RESISTORS

(5 pc tolerance, 1/4 or 1/2 W)  
 3 x 8.2M, 1 x 4.7M, 1 x 1.5M, 1 x 820k, 2 x 270k, 1 x 150k, 1 x 82k, 2 x 22k, 1 x 10k, 1 x 4.7k, 1 x 1k, 1 x 560 ohms

### MISCELLANEOUS

Drive system for shutter release, Veroboard, hook-up wire, batteries, knob, solder.

Note: Components with higher ratings than those specified may generally be used provided that they are physically compatible. Components with lower ratings may also be used in some cases provided the ratings are not exceeded.

the relay as collector load. It works as follows: When the output of the integrated circuit (pin 4) drops to zero, the 50uF capacitor in series with the base of the PNP transistor charges via the 4.7k resistor and the 10k resistor which is effectively in parallel. This turns on the transistor and it closes the relay. When the capacitor is charged to almost 6V the PNP transistor turns off, since its base current is provided solely by the capacitor. When the output at pin 4 rises the capacitor discharges via the 10k resistor, so that the cycle can be repeated at the end of the next timing period.

A diode in parallel with the relay protects the transistor against the voltage spike generated by the relay when the transistor turns off.

Timing resistors have been selected to give a 1,2,5,10 sequence of increasing time intervals. The longest time interval provided is twenty minutes in the prototype, but this may be increased to an hour by using a bigger timing capacitor(s). The timing capacitors must have very low leakage, which confines the choice to plastic dielectric or tantalum capacitors. We used tantalum because they are small and cheap where large values are concerned, but you

could use plastic types if your pocket can stand the strain, and your case is large enough to accommodate them.

The relay we used is an STC type 250 GDO, which has a 52 ohm coil and two sets of changeover contacts. If other relays are used the circuit should be redesigned so that the relay closes for about 1/2 second.

Average current drain of the circuit is very low and can easily be provided by four penlite (1.5V) cells connected in series in a standard penlite cell holder. A 400uF electrolytic capacitor connected across the supply is included to ensure a low output impedance from the batteries, particularly when they near the end of their service life. Service life should be almost equal to the shelf life in view of the intermittent mode of operation.

Construction is straightforward, and layout is non-critical. The prototype was built on Veroboard. This has the advantage that it can be made to take the relay socket by opening up some of the holes slightly.

The circuit may also be made to operate as a "one-shot" delay switch, by connecting the 22k resistor presently shown connected to pin 4 of the IC to the positive supply rail instead. But note that the time delays obtained will be different from the time intervals obtained when the unit operates as a relaxation oscillator.

So there you have it — a simple little trigger unit which is capable of allowing you to make a wide range of interesting time-lapse movies. But let us again stress that you should make sure you have solved the problem of actuating the camera's single frame release, before you invest in parts for the trigger.

EM 401 Diodes 20c \$1.50 per 10  
 EM 404 22c \$1.80 per 10  
 EM 408 30c \$2.80 per 10.  
 BC 107 / 8 / 9 35c \$3.20 per 10.  
 2W3638 55c \$4.50 per 10.  
 AY9140 (TT800 / TT801) \$2.50 Pr.

216 Battery clips 10c 79c / 10 \$6 per 100.

100W ceramics 10pf — .04 5c.  
 25.47 ceramics 15c, \$1.20 / 10  
 100mH Chokes 10c.

1/2W Philips 5% Resistors 3.5c \$2.75 / 100

Standard Pots 1K — 4.7m Log lin 40c.

Ganged Pots \$1 / 20.

Pre set Pots 20c.

Special Bag mixed electrolytics \$1 per 10, all useful.

LOOK! unmarked BC 108 20c

PLUS POST

## MODERN ELECTRONICS

94 Elizabeth Street, GPO Box 5402cc, Melbourne. Vic.

PHONE. 65 3761



# There's more to mid-range frequencies than meets the ear.

The graphic illustration below represents the typical frequency response expected in a good hi-fi system. A large proportion of the sound can be classified as mid-range and to hear this sound at its best a well engineered mid-range speaker is essential.

The new Plessey C6MR has been specifically designed to handle mid-range sound with excellent performance from 450 Hz to 6600 Hz and sharp roll off beyond these frequencies.

Adding the C6MR to your existing speakers and installing recommended crossover components will result in a superior 3-way speaker system. Alternatively, new 3-way speaker systems can be built based on the C6MR and any desired combination of Plessey C80, C100, C12P and 12U50 woofers and X30, C3GX and 5FX tweeters.

Plessey Crossover Inductors SOL36 and SOL42 are available to ensure extremely smooth response and minimum distortion at crossover points. With Plessey components you can

assemble high-performance multi-speaker systems that will appeal to the most discerning ear. Full application notes are available from Plessey Rola distributors or Plessey Rola direct.



**PLESSEY  
Rola**


Plessey Rola Pty. Limited.  
The Boulevard, Richmond,  
Victoria. 3121.

Melbourne, Telephone 423921  
Sydney, Telephone 720133  
Adelaide, Telephone 422920

Perth, Telephone 687111  
Brisbane, Telephone 708097

## C6MR Mid-range

Frequency response  
450 Hz to 6600 Hz  
Voice coil impedance  
8 or 15 ohms  
Power Handling 20  
watts RMS with  
recommended cross-  
over  
Speaker Diameter  
6-9/16"



Low Frequencies

Mid-range

High Frequencies

Distributors: N.S.W. General Accessories, Lawrence & Hanson Pty. Ltd. VIC General Accessories, Lawrence & Hanson Pty. Ltd. Radio Parts Pty. Ltd. QLD General Accessories, The Lawrence & Hanson Electrical Co. (Old) Ltd. S.A. General Accessories, Gerard & Goodman Pty. Ltd. W.A. General Accessories, Atkins Carlyle Ltd. TAS. W. & G. Genders Pty. Ltd. Homecrafts Tasmania N.Z. Plessey (N.Z.) Limited, Rata St. Henderson, Auckland

AR 54





# FORUM

Conducted by Neville Williams

## Enlarger Timers: What is a "half-stop"?

The solid-state photographic enlarger timer described in our May issue was a conventional, no-nonsense project yet, strangely, it stirred up more than its share of controversy — together with some resulting discussion in our own office. Perhaps other readers have had similar thoughts, without actually committing them to paper.

The first, and most elaborate, challenge was from a reader in Tasmania, who we will not further identify, because he has since retracted his statements at the instigation of his own son. It's a bit rough on Dad, when the young bloke sets you right technically!

This particular reader looked at the time intervals we had provided in our timer and jumped to the conclusion that the progression we chose (1, 1.4, 4, 5.6, 8 . . . seconds) had been based on stop numbers, as marked on the lens adjustment of cameras and enlargers. Certainly the number sequence is the same.

On this assumption, we appeared to have made a fundamental error, as follows:

In a lens mechanism it is conventional to arrange matters so that the exposure is progressively doubled or halved as the lens is clicked through its stop settings. In line with this, the stop settings are arranged so that they progressively double or halve the area of the aperture through which the light passes.

However, in defining lens characteristics and settings, use is made of the ratio: focal length to diameter NOT focal length to area. Between area and diameter there is a square law relationship, so that 2:1 area ratios become (root 2): 1 diameter ratios.

As a result, stop numbers on lenses follow a root-2 progression (1.414); each time the diameter is increased or decreased by this figure, the area (and hence the light admitted) doubles or halves.

However, the aforesaid Tasmanian reader noted that there is no square function in exposure time. He reasoned that, if you increase the exposure time in an enlarger from 1 to 1.4 seconds, you increase the effective exposure by the same ratio. You are not doubling it as you would do, if you clicked the lens from 1 to 1.4.

This made it look as though we had confused time and area. More than that we had made the same apparent mistake in an earlier timer described in August 1964. To quote our critic: "the concept of half-stop in aperture is confused with the concept of a half-stop in time."

Determined to put the record straight, our Tasmanian reader produced a complete article entitled "Solid State Phototimer — More About Time Intervals."

In careful, well-written prose, he ex-

plained about apertures, aperture numbers, "size of the hole," stop numbers and so on. He showed that, to double exposure in terms of time, it was necessary to use ratios of 2:1.

So far, so good.

He then made the point that, for close control of exposure, it was desirable to provide a facility whereby the exposure time could be increased or decreased by "half a stop." He went on to work out a revised switching system to provide "half-stop" exposure times which would be halfway between the whole numbers of seconds. These would replace the 2/5 intervals which we had apparently happened upon in wrongly applying stop numbers.

His "ideal" series would read 2, 3, 4, 6, 8, 12, 16 seconds and so on.

And here, unknowingly, he had ended up in very muddy water.

First of all, we had not confused aperture and time in either this or the earlier article. In the May 1973 article, par 3 defines the time series as a geometric progression. It states specifically that each step on the

timer is equivalent to "half a stop" on the camera lens and that the timer has to be clicked through two positions to double the exposure.

Our correspondent apparently jumped right over this in his haste to put paper to typewriter!

But, having assumed that our 1.4 series was the result of a mistake, he rejects it as having any claim to a "half-stop" equivalence. Instead, with somewhat greater effort, he comes up with a substitute series. But alas, the new series doesn't stand up to examination.

Starting with 2 seconds, the next interval is 3 seconds. Superficially that's fine: an increment of 50 pc.

But, starting at 3 seconds, his next interval is 4 — an increment of only 33pc.

Perhaps the series should run: 2, 3, 4.5 etc. But then, nowhere, does one get a 2:1 interval.

In short, what is a half-stop in terms of exposure time? Is it a valid term or can it be at best only an approximation? These were the questions we found ourselves re-examining.

In fact, a little thought will show that a cumulative 50pc series is no more practical in terms of area than it is of time. Mathematically, the only series which can be cumulative and which will fit into existing 2:1 intervals is a root-2 series.

Therefore, whether talking in terms of lens area or exposure time, half a stop can only mean an increase or decrease of 1.414. The casual definition of half a stop as a 50pc increase is wrong.

You will note that we used quotes in the May issue around the term "half a stop." There have been arguments before in these columns about the use of quote marks but let's say they signified, in this case: "what some people refer to as half a stop."

Fortunately, our rebuttal of the criticism was little more than a formality. By the time it was received, the correspondent's son had come across an article in the July 1964 issue ("Design For A Photo-Timer" by Philip Watson) setting out the reasons for the choice adopted in both the instruments

## An injustice to genuine stockists?

Dear Sir,

I read with interest the Editorial in the June issue of "Electronics Australia." In it Mr Rowe states "to be honest I believe that some of the component suppliers and self proclaimed wholesalers are themselves responsible for a certain proportion of the part supply problems experienced by our readers."

As a large quantity stockist of a small range of specialised components (as used in "Electronics Australia" and "Electronics Today" projects) I would thoroughly agree. However, in a following paragraph you state "(they) are not adverse to telling the would be constructor that the parts we have specified are not made or not available."

I only hope in writing this sentence, you realise its implications. Every week we have to advise some clients that certain parts they have ordered are "not available."

We have no doubt that many customers will now be thinking that we (and several other reputable mail order companies) may be one of the "self proclaimed" wholesalers you are referring to. You offer no advice in

your editorial as to how a constructor can judge what he is being told is the truth by the supplier, and your magazine does not list reputable suppliers so that the constructor can lean on your "inside knowledge" of the industry.

We believe that not only are the component suppliers and "self proclaimed wholesalers" responsible. When compiling our 1973 catalogue we included three "Electronics Australia" Publications on the understanding that we would be able to obtain continuous supplies.

At the present time only one publication ("Fundamentals of Solid State") is available. This means that every customer ordering the other publications receive an advice note stating "not available at present."

No doubt your editorial will place a firm doubt in their minds as to whether to believe us or not.

Yours faithfully,

R. H. Smith, M / Director  
Dick Smith Electronics Pty Ltd.



# SCOPE soldering irons

Buy a SCOPE and join the club of satisfied USERS—you need not keep it a secret, others don't. That's why SCOPE IS KNOWN AT ALL THE BEST PLACES—in the tool kit, on the bench, in the boot, on the kitchen table, in the garage, on the service truck, in the engine room, even on the roof... Wherever SCOPE goes it gives you the best service—and a host of satisfied users will agree it is the QUICKEST, the EASIEST, the SAFEST... THE BEST OF ALL SOLDERING IRONS.

## ECONOMICAL

Consumes current only whilst in use. Scope performs all the functions of other irons from 40 to 150 Watts. (Miniscope—up to 75 Watts).

## FAST

Fast heating due to the unique replaceable carbon element. Only 5 to 6 seconds' initial heating up time from cold, then practically instantaneous.

## VERSATILE

Copes with all soldering jobs—from miniature components to large solder lugs. Temperature control at your finger tips. Heat only when, where and as much as needed.

## SAFE

Low voltage operation. Scope irons operate from 2.5V to 6V.

For your complete protection and the satisfactory operation of your Scope iron, demand and use THE APPROVED SCOPE **natronic** TRANSFORMER which incorporates a specially designed ELECTRO-STATIC SHIELD.



\* Approved by electricity authorities APP. No. N/360/6894-5

## CONVENIENT

Ideal for those almost inaccessible spots. No burning of adjacent insulation.

## LIGHT WEIGHT

Scope De Luxe weighs only 3½ ozs. Miniscope 1¾ ozs.



All irons are supplied complete with a spare tip and two elements and suitably packed for presentation as a gift.

## SPARE PARTS

No expensive resistance wire heating elements to replace. Maintenance without special tools. Spare tips, carbon elements and other parts readily available from your Scope Distributor.

Scope products are available from all major electrical wholesalers and Hardware Stores throughout Australia and from H. W. Clarke, Wellington and Auckland, New Zealand.

## SCOPE MEANS A LIFETIME OF SATISFACTION



SCOPE DE LUXE



MINISCOPE

## IRH Components Pty. Limited

THE CRESCENT, KINGSGROVE, N.S.W. 2208. PHONE: 50-0111

74 RAGLAN ST., PRESTON, VIC. 3072. PHONE: 44-5021

### Interstate Agents

HOB. TAS. 342811  
LAUN. TAS. 22844  
PERTH W.A. 82271  
ADEL. S.A. 231971  
BRIS. QLD. 211933  
New Zealand  
H. W. CLARKE  
(N.Z.) LTD.



THE COMPONENT DIVISION  
OF IRH INDUSTRIES LIMITED

Please Post free SCOPE literature

NAME .....

ADDRESS .....

CITY .....

POSTCODE .....

## FORUM

subsequently described. Let's quote just three parts:

"It seemed that what we wanted was a scale in which every step would represent a change of 1.5 times and ideally, every second step a change of two times. But such a scale is virtually impossible if every step is to maintain the correct relationship to its neighbours. For example, a setting of 1.5 seconds multiplied by a factor of 1.5 gives, not two, but 2.25.

"But the factor did not have to be exactly 1.5. It could just as easily be 1.4. And 1.4 times 1.4 (1.414 more correctly) is two. Working on this basis we produced a scale having some unique features.

"The figures on the resulting scale bear a striking resemblance to the figures on the diaphragm of your camera, but this is more coincidence than anything else, and the two meanings must not be confused. Stop numbers represent a doubling of exposure, because increasing the lens diameter 1.4 times doubles the area of the lens in use, and thereby doubles the light falling on the film. On the other hand, increasing the exposure time by 1.4 only increases the available light 1.4 times. In the first case the increase is a square function, in the second a linear function."

It all ended happily. Guided by the July '64 article our correspondent redesigned the circuit to provide intervals based on the cube root of 2. This gives him the closer intervals desired while still giving him a doubling of exposure time with every third switch position.

Another letter on the same subject came to hand from P.S. of Thornbury, Victoria. This correspondent did not question our basic circuitry but, seeking closer intervals, he had modified it to produce what he refers to as one-third stop adjustments of exposure. Reference has been made to this letter in "Circuit Design Ideas."

The same letter describes a further modification, whereby exposure can be controlled by a cadmium-sulphide cell reacting to the total light reflected from the printing paper.

I must confess that the first sight of this suggestion caused me to over-react and to ask audibly who was kidding whom? Side by side on the one circuit the contributor had provided for very small increments of exposure, and then an automatic form of control which is just about as unrefined as one can get.

Perhaps the over-reaction can be excused by the number of times automatic total-light measurement is "discovered" and advanced as being the answer to the hobbyist's prayers.

Closer reading of the letter indicated that P.S. did understand the situation and that his enlarger light timing system had been contrived to cope with a variety of uses, including mass production of prints. As such, it probably works fine, but the juxtaposition of nominal one-third stop intervals and a total-light control system did look odd—rather like a tradesman turning up on a job with a micrometer and his wife's tape measure!

The point about a total-light system is that it responds to the total light passing through a negative (and on to the printing paper). It adjusts the exposure to produce a print in



which highlights and shadows average out to a certain predetermined "greyness" for the total print area.

From an "average" negative, an "average" print may indeed be quite acceptable, but there is more to it than that.

If a subject happens to be standing against a predominantly dark background, the automatic system tends to increase the printing time in an effort to bring the predominantly dark picture up to the "average" grey; in the process the subject's face will be blanched.

Conversely, in a ski setting, the automatic system will react to the abundance of light, decreasing exposure time and producing a black-faced subject against a background of grey snow!

For these reasons, one would expect provision for very close control of exposure time to be coupled, not with an averaging system, but with a sophisticated light probe enabling highlights and shadows to be examined selectively.

It is for similar reasons that total-light exposure measurements are losing favour in modern high quality cameras. The manufacturers have come up instead, with various schemes which react more selectively to individual sections of a picture.

Even then, camera manufacturers do no more than provide whole stop increments for taking pictures. Whether intervals closer than "half a stop" are justified for processing those pictures might be another area for debate.

And there we'll leave it.

## THE PARTS SITUATION

Changing the subject, we reprint on the preceding page, a letter from one of our regular advertisers, Mr Dick Smith. He is concerned lest the editorial in our June issue reflects unfairly on those stockists who are genuinely trying to give service to the users of electronic components.

A number of other suppliers expressed a similar view in personal conversation or by telephone. They point out that a lot of capital is involved in carrying substantial stocks and, in the face of admitted supply problems, they are keen that credit be given where credit is due.

Fair enough.

I must point out, however, that the editorial was not just about stockists. It was concerned with an overall shortage of components so serious that major manufacturers around the world are affected, with delivery times being quoted as long as 60 weeks. Reference was made to a long priority queue in which Australia and Australian enthusiasts have to take their place.

This should surely support rather than erode the credibility of genuinely concerned suppliers who have to tell their customers that stocks of certain components are not immediately available.

(Dick Smith names us as a co-offender because we have run out of stocks of two of our handbooks. Yes, we underestimated the demand and the time it would take to reprint or replace. But that doesn't alter the picture in regard to components.)

As part of the overall picture, Jim Rowe did make the point that some parts suppliers aggravate the position by trying to work from inadequate stocks, or no stocks at all. When the inevitable delays occur, they blame anybody but themselves.

We know that it happens because we talk with all parties, purchasers, suppliers and

## SUPPORT FOR CDI

Dear Sir,

With reference to your reply to F.S., in May E.A., I have discussed the matter of CDI with an RAA (SA's counterpart to the RAC) patrol. He stated that he understood that tests on a dynamometer did not show any increase in hp with CDI. That, however, is only part of the story.

The patrolman spends a lot of his time starting cars which won't start in the winter or in rain. He considered that about 50 per cent of these cars could have been started by their owners if they had had CDI. In other words, although it doesn't improve the performance of a well maintained car, CDI would be a benefit to those which are troublesome to start and this applies particularly to cars with automatic chokes. He named several makes which are characteristically hard to start.

The patrolman also informed me that distributor points are a constant problem with cars he goes to. Undoubtedly the fact that points are a frequent cause of trouble is the reason why Chrysler has installed a new system in their latest cars which does not have distributor points.

It is little pleasure to a motorist to own a car which performs well when it is running, but is unreliable at starting in winter. Consequently he considers that all cars that are difficult to start should be equipped with CDI.

In other words I feel that the RAC has looked at only one facet of a car's performance in reaching the conclusion that CDI is not of "real benefit to the average motorist".

K.H., (Brighton South, SA).

manufacturers (or agents). Concerning this matter Dick Smith says "I thoroughly agree." However, he goes on to ask how purchasers are to identify the "good" firms from the "not so good" ones.

Frankly, I don't think there is a simple answer to this. Dick Smith is proud of his stocks but he admits to having to advise customers from time to time that he cannot immediately fill their orders. And even if he headed a list of recommended suppliers, there would inevitably be complaints that "I ordered a thingam from the firm at the head of your list and I'm still waiting!"

And such is the perversity of circumstance that a firm not listed would have the very thingam that no one else seemed to be able to get!

Frankly, I think that one discovers good suppliers in much the same way that one discovers good doctors, good mechanics or good estate agents. You ask, you observe, you try. You reject the obviously inadequate or obviously suspect and choose ultimately the one that seems to give you a satisfactory service.

That's the very core of successful business.

The simple fact is that component suppliers are an essential link between a journal which specialises in constructional articles and a very large group of readers with an urge to build and experiment.

In an effort to ease the supply position we plan, in future issues, to publish a representative list of firms which deal directly with the consumer and which stock a range of components suitable for our projects.

We suggest you give them your support.

*Realistically speaking...*

**REALISTIC** with SEPARATE SPEAKER

a Realistic performer

a Realistic value...



SW/CW  
SSB/AM

TRANSISTORISED  
all solid state

4 BANDS  
.535 to 30 MHz  
(includes Broadcast)

240V AC  
or 12V DC  
operation

SUGGESTED RETAIL PRICE

**\$234.20**

... that's realistic too!

Weston Electronics Co.

(A division of Jacoby Mitchell Ltd.)

The popular REALISTIC DX150B which has gone from strength, to strength with amateurs, shortwave and broadcast listeners alike, now has a further improvement, A SEPARATE MATCHING SPEAKER included.

The DX150B gives long-range, world-wide realistic reception on 4 bands, including Broadcast. Fully transistorised - all solid state - no warm-up delays; the DX150B will run on dry cells if current fails or is not available; will operate from a car's cigarette lighter or any 12V DC service. A 240V AC power supply is also built in. Over 30 semi-conductors - product detector for SSB/CW, plus fast and slow AVC - variable pitch BFO - illuminated electrical bandspread, fully calibrated for amateur bands - cascade RF stage - ANL for RF and AF-zener stabilised - OTL audio-illuminated "S" meter.

Weston Electronics Company  
376 Eastern Valley Way, Roseville, 2609.  
Cables and Telegraphic Address: "WESTELEC", Sydney.  
Phone: 407 1212

Please forward free illustrated literature and specifications on Realistic.

NAME .....

ADDRESS .....

WE/60



# OUR NEW ADDRESS... CHECK BELOW

## — LARGER PREMISES BETTER PARKING —

**GUITAR AMPLIFIERS & SYSTEMS**  
10 TO 200 WATTS — RMS

**P.A. AMPLIFIERS & SYSTEMS**  
10 TO 100 WATTS — RMS

**STEREO AMPLIFIERS & SYSTEMS**  
3 TO 60 WATTS — RMS

**ALL SOLID STATE UNITS — CAN BE SUPPLIED WITH  
MULTI CHANNEL MIXING & BALANCE UNITS FOR  
VOICE & INSTRUMENT GROUP & STAGE WORK.**

**PLAYMASTER 132**

**PLAYMASTER 136**

**PLAYMASTER 138**

**DIGITAL V.O.M.**

**MAJOR STOCKISTS OF ALL GENERAL RADIO & ELECTRONIC COMPONENT PARTS — YOU NAME IT — WE WILL QUOTE**

Valves — Transistors — Zener & Power Diodes — Semi-Conductors — Diacs — Triacs — S.C.R.'s — I / C's. Speakers — Microphones — Coils — IFT's. Transformers — Inst Cases — Metalwork. Players & Changers — Meters — Relays — Condensers — Resistors — Bezels — Styli — Cartridges — Recording Tape — Probes — Instruments — Potentiometers — Crystals — Ferrite Beads — Cores — Baluns — Terminals — Co-Axial Plugs & Sockets — Multi Connectors — Printed Circuit Boards — Copper Winding Wire — Etc. — Etc. — Send for prices sheets — Post 20c.

## POPULAR KITS - TOP QUALITY - LOWEST PRICES

<p><b>INSTRUMENTS C.R.O.</b></p> <ol style="list-style-type: none"> <li>1. 5in wide range.</li> <li>2. 1963 3in cal.</li> <li>3. Audio.</li> <li>4. 1964 3in.</li> <li>5. 1964—Audio.</li> <li>6. Electronic SW.</li> <li>7. W / band Preamp.</li> <li>8. 20K ohm / Volt protected M / M.</li> <li>9. Probe for above.</li> <li>10. Protected D.C. M / M.</li> <li>11. Meterless V/meter.</li> <li>12. A.C. Millivoltmeter</li> <li>13. A.C. Solid State Millivoltmeter</li> <li>14. Solid State A.F. Millivoltmeter.</li> <li>15. Noise Distortion Millivoltmeter.</li> <li>16. Standard V.T.V.M.</li> <li>17. 1964 — V.T.C.M.</li> <li>18. 1964 — V.T.V.M.</li> </ol> <p><b>BRIDGES</b></p> <ol style="list-style-type: none"> <li>19. Standard R / C.</li> <li>20. 1964 — R / C.</li> <li>21. 1964 R / C and Signal Injector.</li> <li>22. Sweep and marker TV INST.'s</li> <li>23. Dual sweep Gen.</li> <li>24. Silicon diode sweep Gen.</li> <li>25. Silicon diode noise Gen.</li> <li>26. Pattern Gen.</li> <li>27. Trans. pattern Gen.</li> <li>28. Wild range pulse Gen.</li> </ol> <p><b>AUDIO INST.'s</b></p> <ol style="list-style-type: none"> <li>29. 1960 Audio Osc.</li> <li>30. 1962 High perf. audio Gen.</li> <li>31. Crystal locked std.</li> <li>32. Electronic tuning standard.</li> <li>33. 1965 Solid State audio osc.</li> <li>34. Direct reading A.F. meter.</li> <li>35. Sq. wave Gen.</li> <li>36. 1967 Transistor audio Gen.</li> <li>37. Additive frequency meter.</li> <li>38. A.F. tone burst Gen.</li> <li>38A. 1968 Solid state A.F. Generator.</li> <li>39. R.F. INST.'s</li> <li>39A. Trans. wave meter.</li> <li>40. "Q" meter.</li> <li>40A. Crystal Calibrator — Solid state.</li> </ol>	<p>40B. Digital freq. meter</p> <p>40C. 1969. Dip Osc. — Solid state.</p> <ol style="list-style-type: none"> <li>41. G.D.O. wide range.</li> <li>42. G.D.O. adaptor.</li> <li>43. Trans. service osc.</li> <li>44. Simple signal injector.</li> <li>45. Transistorised signal tracer.</li> <li>46. Transistorised osc.</li> <li>47. Basic test osc.</li> <li>48. Transistor test</li> <li>48A. I.F. Align Osc.</li> </ol> <p><b>MISCELLANEOUS INST. ETC. KITS</b></p> <ol style="list-style-type: none"> <li>49. 1960. Trans. Tester.</li> <li>50. 1968 Transistor test set.</li> <li>51. Valve and Transistor tester.</li> <li>52. Electronic Stethoscope.</li> <li>53. Moisture alarm.</li> <li>54. Electronic Pistol range.</li> <li>55. Transistor Geiger Counter.</li> <li>56. Light beam alarm.</li> <li>57. Burglar alarm.</li> <li>58. Flasher unit.</li> <li>59. Transistor alarm.</li> <li>60. Electronic switch.</li> <li>61. Photo Timer.</li> <li>62. Direct reading impedance meter.</li> <li>63. Electronic anemometer.</li> <li>64. S.W.R. indicator.</li> <li>65. Simple proximity alarm unit.</li> <li>66. Metal Locator.</li> <li>67. Electronic metronome</li> <li>68. Bongos Drums.</li> <li>68A. Keyless organ.</li> <li>68B. Theremin.</li> <li>68C. Laser unit.</li> <li>68D. Color organ.</li> <li>68E. Stereo Headphone Adaptor.</li> </ol> <p><b>BATTERY CHARGERS</b></p> <ol style="list-style-type: none"> <li>69. Universal unit.</li> <li>70. 1 amp unit.</li> </ol> <p><b>REGULATED POWER SUPPLIES</b></p> <ol style="list-style-type: none"> <li>71. Transistor, 9v.</li> <li>72. Transistor, fully protected supply.</li> <li>73. 1966 H.T. unit.</li> <li>74. 1966 lab. type.</li> <li>74A. Simple pwr. supply</li> </ol> <p><b>VOLTAGE-CURRENT CONTROL UNITS</b></p> <ol style="list-style-type: none"> <li>75. Vari-watt unit.</li> <li>76. Vari-tach. motor speed control.</li> <li>77. 2KW auto-light dimmer.</li> </ol>	<p>78. 4KW auto. light dimmer.</p> <p>79. Model train control unit.</p> <p>79A. Vari Light Dimmer.</p> <p>80. Model train control unit with simulated inertia.</p> <p>81. Above-hi-power.</p> <p>82. No. 81 with simulated inertia</p> <p><b>TACHOMETER UNITS</b></p> <ol style="list-style-type: none"> <li>83. 6 or 12v Std.</li> <li>84. 6 or 12v Mullard.</li> <li>85. 6 or 12v with dwell angle.</li> <li>86. Tachometer and dwell angle unit for service stations.</li> </ol> <p><b>TRANSISTOR IGNITION</b></p> <ol style="list-style-type: none"> <li>87. Ro-fo. 6 or 12v.</li> <li>88. Hi-Fire 6 or 12v. (transformer).</li> <li>88A. C.D.I. unit.</li> <li>88B. Electronic ignition.</li> </ol> <p><b>POWER CONVERTERS</b></p> <ol style="list-style-type: none"> <li>89. D.C.-D.C. 60w.</li> <li>90. D.C.-D.C. 40w.</li> <li>91. D.C.-D.C. 40w. 12v — input</li> <li>92. D.C.-D.C. 70w. 12v — input</li> <li>93. D.C.-D.C. 100w 12v — input.</li> <li>94. D.C.-D.C. 140w. 24v — input</li> <li>95. D.C.-D.C. 225w 24v — input Q.</li> </ol> <p><b>HIGH-FIDELITY AMPLIFIERS MONO UNITS</b></p> <ol style="list-style-type: none"> <li>96. Hi-Fi 3</li> <li>97. Mullard 3-3.</li> <li>98. Mullard 5-10.</li> <li>99. Mullard 5-10.</li> <li>100. Transistor 20w.</li> <li>101. Transistor 60w.</li> </ol> <p><b>STEREO UNITS</b></p> <ol style="list-style-type: none"> <li>102. Mullard 2-2.</li> <li>103. Mullard (v) 3-3.</li> <li>104. Mullard (t) 5-5.</li> <li>105. Mullard (t) 5-5.</li> <li>106. Mullard (v) 10-10.</li> <li>107. Mullard (t) 10-10.</li> <li>108. Philips Twin 10.</li> <li>111. Hi-Fi 60 Plus 60. P / M 128.</li> <li>112. Playmaster 2-2.</li> <li>113. Playmaster 3 plus 3.</li> <li>114. Playmaster unit 3.</li> <li>115. Playmaster unit 4.</li> <li>116. Playmaster 10 plus 10</li> <li>117. Playmaster 101.</li> <li>118. Playmaster (t) 105.</li> <li>119. Playmaster (t) 113.</li> <li>120. Playmaster (t) 115.</li> <li>121. Playmaster (v) 118.</li> <li>122. P.A. UNITS</li> <li>122. 10 watt std.</li> </ol>	<p>122A. Mullard 20w Solid state.</p> <p>122B. Mullard 40w. Solid state.</p> <ol style="list-style-type: none"> <li>123. 25 watt std.</li> <li>124. 25 watt std.</li> <li>125. 30 watt (t).</li> <li>126. 100 watt std.</li> <li>127. Stereo P.A.</li> </ol> <p><b>GUITAR UNITS</b></p> <ol style="list-style-type: none"> <li>128. 10 watt std.</li> <li>129. 25 watt std.</li> <li>130. 35 watt std.</li> <li>131. 50 watt std.</li> <li>132. 70 watt (t).</li> <li>133. Playmaster 102.</li> <li>134. Playmaster 103.</li> <li>135. Playmaster 40w. 116.</li> <li>136. Playmaster 60w 117.</li> <li>137. Guitar fuzz box.</li> <li>138. Guitar Waa-Waa.</li> <li>139. Reverb unit.</li> <li>140. Guitar preamp.</li> <li>140A. Guitar 50w. Solid State P / M 125.</li> </ol> <p><b>STEREOGRAMS</b></p> <ol style="list-style-type: none"> <li>141. Playmaster 105.</li> <li>142. Playmaster 106.</li> <li>143. Playmaster 107.</li> <li>143A. Playmaster 124.</li> </ol> <p><b>CONTROL UNITS</b></p> <ol style="list-style-type: none"> <li>144. Playmaster No. 9.</li> <li>145. Playmaster No. 10.</li> <li>146. Playmaster No. 104.</li> <li>147. Playmaster No. 112.</li> <li>148. Playmaster No. 120.</li> <li>149. Mullard 2v.</li> <li>150. Mullard 3v.</li> <li>151. Philips Miniwatt.</li> <li>152. P / M 127.</li> </ol> <p><b>PREAMP UNITS</b></p> <ol style="list-style-type: none"> <li>153. Transistor — Mono.</li> <li>154. Transistor — Stereo.</li> <li>155. Transistor — Silicon. mono.</li> <li>156. Transistor F.E.T. mono. 157.</li> <li>157. Transistor dyn. mic. mono.</li> <li>158. Above-Stereo.</li> <li>159. Playmaster 115 F.E.T. Stereo.</li> <li>160. Playmaster 115 mag.</li> <li>161. Sound projector.</li> </ol> <p><b>MIXER UNITS</b></p> <ol style="list-style-type: none"> <li>162. Trans 4 ch. (1966).</li> <li>163. Trans — 4 ch. (1967).</li> <li>164. Valve — 4 ch.</li> </ol> <p><b>TUNER UNITS</b></p> <ol style="list-style-type: none"> <li>165. Playmaster u / style.</li> <li>166. Playmaster No. 11.</li> <li>167. Playmaster No. 114.</li> <li>168. Playmaster No. 122.</li> <li>169. Playmaster No. 123.</li> <li>170. Philips Miniwatt.</li> <li>180. Trans — Long range.</li> </ol>	<p><b>TAPE UNITS</b></p> <ol style="list-style-type: none"> <li>181. Trans. Preamp.</li> <li>182. Playmaster 110 (M).</li> <li>183. Playmaster 110 (S).</li> <li>184. Power Unit 110.</li> <li>185. Adaptor 110</li> <li>185. Playmaster 119 Adaptor.</li> <li>186. Transistor V.O.X.</li> <li>187. Tape Actuated relay.</li> <li>188. Mullard Trans Tape Amp.</li> </ol> <p><b>RECEIVERS</b></p> <ol style="list-style-type: none"> <li>189. Fremodyne 4, 1970.</li> <li>190. Fremodyne 4 R.F. Socf. only.</li> <li>191. Synchrodyne.</li> <li>192. Communications RX.</li> <li>193. Deltahei RX.</li> <li>194. 3 Band Double Change S / het RX.</li> <li>195. Explorer VHF Transistor RX.</li> <li>196. Interceptor 3 Semi Comm. RX</li> <li>197. 1967 All-Wave 2.</li> <li>198. 1967 All-Wave 3.</li> <li>199. 1967 All-Wave 5.</li> <li>200. 1967 All-Wave 6.</li> <li>201. 1967 All-Wave 7.</li> <li>202. Transporta 7.</li> <li>203. Transistor 8</li> <li>204. 3 Band 2V RX.</li> <li>205. 3 Band 3V RX.</li> <li>206. All Wave 1970 1 / C 2.</li> <li>207. Versatile Mantel Set</li> <li>208. All-Wave Transistor 3</li> <li>209. A.B.C.</li> <li>210. 1968 F.E.T.</li> <li>210A. 1 / C TRF RX.</li> <li>210B. R.F. Preamp.</li> <li>210C. "G" Multiplier.</li> <li>210D. 1970 Communications. Solid state</li> </ol> <p><b>TRANSMITTERS</b></p> <ol style="list-style-type: none"> <li>211. 144 MHz 50W. Linear Final.</li> <li>212. 144 MHz 20W.</li> <li>213. 144 MHz 20W.</li> <li>214. 144 MHz 18W</li> <li>215. 144 MHz S.S.B.</li> <li>216. 3 Band A.M.</li> <li>217. Basic 3 Band.</li> <li>218. 5 Band. S.S.B.</li> <li>219. 1967 S.S.B.</li> </ol> <p><b>CONVERTERS</b></p> <ol style="list-style-type: none"> <li>220. 50 MHz</li> <li>221. 144 MHz. 1970.</li> <li>222. 50 and 144 MHz Crystal Locked.</li> <li>223. 1965 S / W.</li> <li>224. 1965 S / W 2 Band.</li> <li>225. 1966 3 Band.</li> <li>226. Basic S / W.</li> </ol> <p><b>V.F.O. UNITS</b></p> <ol style="list-style-type: none"> <li>227. Remote Unit.</li> <li>228. 7.8 and 9 H.F. and V.H.F</li> <li>229. All transistor.</li> </ol>
--	---	--	--	--

PHONE  
662-3506

**E. D. & E. (SALES)**  
PTY. LTD.  
118 LONSDALE STREET,  
MELBOURNE — 3000 — VIC.

PHONE  
662-3506



## CIRCUIT & DESIGN IDEAS


Interesting circuit ideas and design notes selected by the Editor from technical literature, reader contributions and staff jottings. As they have not necessarily been tested in our laboratory, responsibility cannot be accepted. Contributions to this section are always welcome.

## Modifications to Photographic Timer

I have just built the Phototimer as described in May, 1973. I felt however, that the  $\frac{1}{2}$  stop separation was a shade too coarse and so I modified it as shown in the diagram. The main time selector switch (S4) operates in whole stops from 1 to 120 seconds, while the 50uF timing capacitor has been replaced by five capacitances and the switch (S5) which allows for times  $1/3$  or  $2/3$  of a stop over or under the nominal time selected by S4.

I have also added a circuit with a CdS cell, with resistors, potentiometer and switch, S6. This arrangement allows the timer to be used as an automatic printer in that when calibrated, the cell senses the amount of light reflected from the enlarging paper during exposure and adjusts the exposure time accordingly. The cell is shaded against stray light and is mounted in a set and accurately repeatable position, such that light from the entire surface of the print is reflected onto the cell. The 1k potentiometer is fitted with a large calibrated knob.

The cell is sensitive to the darkroom safelight and this may be solved by using a suitable filter — or the light may be switched off during exposure. I have arranged to take power for the safelight from across the triac in its non-conducting state. Connected in this way, the safelight is shorted by the triac as exposure is commenced and when the enlarger is switched off, power for the safelight flows through the enlarger



lamp. With the lamp wattages shown and with the timer off, the enlarger lamp will dissipate about 2 watts, which is not enough to make it glow. The safelight is not significantly dimmed by this arrangement.

(By Mr P. Sanders, 11/44 Strettle Street

Thornbury, Victoria 3071.)


Editorial note: While we have some reservations relating to the suggested changes to the original Timer, we feel that a number of readers may be interested to try some of the ideas suggested.

## Simple Electronic Dice

This electronic dice uses only two digital DIL ICs and seven LEDs in the readout. The prototype, complete with battery, fitted into a small plastic box not much bigger than a matchbox. It has one possible drawback in that it counts up to seven. This is not a real disadvantage, particularly when it is realised that getting the dice to throw a maximum of six would add complexity to a circuit where simplicity is a prime requirement.

The circuit is basically a three stage binary counter (using only three of the four stages of the SN7493) counting pulses from a high speed clock (SN7400). The player presses a push button which allows clock pulses through to the counter. The number displayed is dependent on the previous count and the length of time the push button is depressed. The random function is obtained by the fact that the counter operates so rapidly that the player cannot possibly predict the next count.

The LEDs are connected to the counter outputs. The diodes on the counter are used to extend an inbuilt two input clearing gate to a three input gate, which is used to prevent the counter from reading zero. Binary to decimal decoding for the readout is achieved by having a multiple of LEDs to



each successive binary column, as shown in the circuit.



In the prototype all the components including the LEDs were mounted on a single printed board, which was pushed close to the front of the clear plastic box so that the readout could be easily seen. However, the

constructor may build it how he wishes, keeping in mind the arrangement of the LEDs, which are arranged so as to appear symmetrical like a normal dice for each count.

(By Mr S. Thomson, 46 Cornwall Road,  
Auburn, NSW 2144.)



# WIDE VARIETY OF ELECTRONIC PARTS...



INDICATOR LAMP • NEON • PLUG & SOCKET • FUSE HOLDER • SWITCH • TERMINAL BLOCK • CONTROL KNOB • SOCKET • BINDING POST • ETC.

## SATO PARTS

3-3-3, Ebisu, Shibuya-ku, Tokyo  
Japan  
TEL: 442-8506 TELEX: 242-2120



F-20 FUSE HOLDER



110V  
220V  
4  
COLOR  
IN  
ONE  
BN-10-4C

★CUSTOM OFFERS WELCOMED  
←WRITE FOR GENERAL CATALOG

## Mr. Sato hasn't told you the whole story.

Mr Sato would have had to buy half of this magazine to show you every part he makes and we stock.

Ten pages would be needed for pilot light assemblies alone.

Three pages for neon lamp holders.

Eight pages for terminal blocks.

One page each for fuse holders, snap switches, key switches, see-saw switches and push-on switches.

Three pages for other switches.

Three for sockets.

Two for plugs and sockets.

One each for connectors, feeder plugs and sockets, square-type connectors, and square type plugs and sockets.

Two pages would be needed for metal plugs and sockets.

One for binding posts and terminals.

Eleven pages would show you every type of Sato knob.

Lug terminal boards, clips, tips

& jacks, test prods and pin plugs, and pilot light assemblies would take a page each.

Plugs and jacks would take three pages.

That's a lot of pages.

Because Mr Sato makes a lot of parts.

And we stock more of them than anybody else.

Talk to us.

We'll tell you the story Mr Sato didn't have the space for.

### General Accessories

□ 153 Sturt Street, South Melbourne. □ 46 Milligan Street, Perth. □ 81-97 Flinders Street, Adelaide.  
□ 50-54 Lt. Edward Street, Brisbane. □ 443 Concord Rd., Rhodes, N.S.W. □ Cnr. Ingham Rd. & Echlin St., Townsville. □ Homecrafts, Tas P/Ltd., 199 Collins St., Hobart.



## Precision Tachometer Squelches Point Bounce

This tachometer circuit for automobiles with capacitive discharge ignition systems suppresses point bounce while measuring motor RPM accurately to within 1%. The circuit, which has an operating temperature range of -29°C to 65°C, can also be used as a temperature-compensated ratemeter or to eliminate relay-contact bounce.

Many automobile tachometers do not work properly with a capacitive-discharge ignition because this type of system employs the breaker points only for triggering an SCR. The voltage waveform across the

Unijunction transistor Q1 is operated with an emitter current that is larger than its valley current so that it will not turn off after triggering. When the points open, capacitor C1 charges through resistor R1 until Q1 fires (in 0.5 to 0.7 millisecond) and triggers the monostable. The current through R1 keeps Q1 on and prevents C1 from charging until the points close. If the points bounce upon closure, they will not be open long enough to allow C1 to charge and fire Q1 again.


For every point opening, the monostable produces a pulse having a fixed width and

saturation voltage, causing C2 to charge positively through R2. C2 stores the charge until  $e^-$  is greater than  $e^+$ , and the op-amp switches back to its stable state.

D2 clamps the voltage across C2 to about -0.6V, while D3 provides temperature compensation for changes in D2's junction voltage drop. Both of these diodes should be kept in thermal contact with each other. Since the op-amp is left floating so that it can be operated from a car's single supply voltage, it has a small positive output voltage when in its untriggered state, making C3 necessary to decouple the meter.

Zener diode D4 and R3 regulate the output against supply voltage variations, and the thermistor compensates for temperature variations in the base-emitter voltage of Q2. If a meter with a full-scale current rating of less than 5mA is used, the thermistor, as well as Q2 and R4, can be omitted.

(By James B. Young, in "Electronics".)



breaker points, therefore, consists of a series of 14V pulses, rather than the 200V spikes that exist in the usual kettering ignition system.


The tachometer circuit shown comprises three sections.

amplitude. Normally, the output stage of the operational amplifier produces a negative saturation voltage. But when a positive trigger from the relaxation oscillator is applied through D1, the op-amp's output switches to a positive

## DC Matching of Complementary Pairs

The emitter current at which matching is required is set up by adjusting Rb. Current meter M1 indicates this. Centre-zero meter M2 now displays the difference between the collector currents of the two transistors. The direction of deflection of M2 shows which transistor has the higher hFE. If the base-emitter drops can be allowed for, Rb may be calibrated in base current; this is useful information when the matched pair is transferred to a working circuit.

(By G. W. Short, in "Wireless World".)




## Another Constant Impedance Potentiometer

This constant impedance potentiometer is similar to the one published in February 1973, but uses only two linear potentiometers, both of the same value. It is worth noting that there are certain restrictions on the applied source and load. If the input impedance is to remain constant then the load impedance has to approach infinity and if the output impedance is to remain constant, then the source has to be an ideal current source or the equivalent voltage source with series resistance ap-

proaching infinity.

(By Mr R. Harding, 5 Maroo Street, Doncaster, Victoria 3108.)



## T. & M. ELECTRONICS

P.O. Box 57, HABERFIELD 2045

AC125	65c	TAA300	2.85
AC126	55c	TT797	1.50
AC127	65c	TT800	1.15
AC127/128	1.25	TT801	\$1.15
AC128	60c	2N706A	50c
AC187	80c	2N2646	1.30
AC187/188	1.35	2N2926	65c
AC188	75c	2N3053	90c
AD149	1.30	2N3054	1.20
AD161	1.25	2N3055	1.40
AD161/162	2.50	Mat. Pr.	3.00
AD162	1.25	2N3638	50c
BC107	35c	2N3638A	60c
BC108	35c	2N5459	85c
BC109	35c	2N5485	1.30
BC177	60c	40250	1.00
BC178	55c	40408	1.05
BC179	60c	40409	2.00
BD139	2.20	40410	2.00
BD139/140	4.60		
BD140	2.40		
BF115	65c	BA102	85c
BF167	75c	OA5	50c
BF173	75c	OA90	15c
BF177	1.20	OA91	15c
BFY50	90c	OA95	25c
BRV39	1.40	OA202	30c
D1371	1.10	IN914	25c
OC26	1.75	1N4004	25c
OC28	1.80	1N4007	55c
OC29	1.90	BYZ13	
OC35	1.75	(6amp. 200v)	40c
OC36	2.00		
OC44	45c	SILICON BRIDGES.	
OC45	45c	1 amp. 100v	90c
OC71	45c	2 amp. 200v	1.40
OC72	45c		
OC74	45c	ZENERS	
OC81	45c	BZY 88 type	30c
OC171	75c	1.5 watt	90c
OCP71	1.95	13 amp. 100v	2.00
		15 amp. 400 v	3.00

"Post 15c (Sorry no COD)"

RETURN MAIL SERVICE

SEMI-CONDUCTOR SPECIALISTS





## THE SERVICEMAN

### *Beware the obvious symptoms*

Most servicemen are proud of the practical skill they have built up over the years; of their ability to take in a set of symptoms and immediately nominate the offending component. But be on guard; symptoms can sometimes mislead.

On odd occasions sets may exhibit symptoms which appear, superficially, to indicate a well-known fault. In fact, they may be due to something completely different. If the fault happens to be intermittent as well, one can make an embarrassing mistake.

The story I am about to tell is a typical example. The fault, which I may have mentioned in previous notes, concerns a particular characteristic of the 6HG8 valve as a converter in TV tuners. As the valve ages, but before it reaches the end of its life in the normal way, it causes quite severe drift of the fine tuning adjustment, particularly on the higher channels such as 9 and 10.

This becomes progressively worse, first necessitating readjustment of the fine tuning control each time these channels are selected, then to the point where it is beyond the range of the fine tuning control, and finally to the point where it is beyond the adjustment of the oscillator slug.

Initially, this fault was, in itself, a hazard, since one could be tricked into making the necessary slug adjustment the first time the trouble occurred, only to be called back in a couple of months for the same fault. By this time it would be bad enough to necessitate replacing the valve.

Over the years, I have become so accustomed to this fault that, as soon as the symptoms appear, I simply replace the valve. Until now I have never known it to fail.

This particular set was about seven years old and I had already replaced the 6HG8 twice for this fault. On both occasions the cure had been immediate and permanent — or as permanent as it ever is.

Thus, when I was called to the set a third time for the same symptoms, after a period of over two years, I had no hesitation in nominating the same fault.

At this point it is worth digressing briefly to talk about the customer's approach to the problem. While it has no bearing on subsequent events, it was an interesting exercise in customer ingenuity, even if a somewhat risky one.

When the situation became so bad that the higher channels could not be tuned, the customer discovered that it was possible to receive his favourite channel by turning the turret slightly off its normal detent position. This is quite normal and is due to the slightly changed length of conductor as the biscuit contact is moved along the wiping contact.

Having discovered this, but not wishing to

stand alongside the set holding the tuner in the offset position, he removed the back of the set and approached the tuner from the rear.

It so happens that this tuner has a convenient slot in the rear cover, through which can be seen the rear disc holding the biscuits. These are also slotted so it was a relatively simple matter to insert a screwdriver through the cover slot, then into the disc slot, and wedge the setup so that the turret was suitably offset and the particular channel received. Naturally, once this was done it was not possible to select any other channels, but the customer had apparently regarded this as the lesser of the two evils.

Ingenious perhaps, but not to be recommended for heavy handed types!

Anyway, back to the story. Having removed the screwdriver I checked all channels and confirmed the fault. The only point that struck me as unusual was the extent of the detuning. It had affected all three high channels (10, 9, and 7) so that channel 2 was now the only one still available. While noting that it was by far the worst case I had encountered, I thought little of it and any suspicions I might have had vanished when I plugged in a new valve and everything came good.

In this model set the tuner and other controls are mounted on a sub-panel which, in turn, is screwed to the inside of the cabinet alongside the main chassis, the tuner being in the top right corner as seen from the front.

The sub-panel is held by two screws, one top and bottom. To get at the tuner it was easiest simply to remove these two screws and withdraw the sub-panel. It was when I was replacing it that the trouble started. As I was attempting to replace the top screw (the set was still running) the screwdriver slipped and hit the shield around the 6HG8. Immediately the sound and picture vanished.

Thinking that I might have a faulty 6HG8 I fetched another from the truck and plugged it in. The set came good immediately, but I was more than a little suspicious of the whole situation by this time. I moved the new 6HG8 gently in its socket and the signals vanished. I moved it again and they returned.

I tried this a couple more times with much the same result, except that I found it was becoming increasingly difficult to restore the set to normal operation. Eventually, only the most careful positioning of the valve would produce a picture, while the

slightest jolt would lose it.

It was now clear that the trouble was much more than a valve fault; it was in the tuner, and probably associated with the valve socket. It was hardly a job to tackle in the customer's home, but I decided to have a quick look for anything obvious.

So I pulled the cover off the tuner, removed a couple of the biscuits, and tried to get a look at the wiring. However, I could see only part of it, and nothing that was obviously wrong. There was nothing for it but to remove the tuner and take it back to the shop.

Back at the shop I removed the outer covers, then the complete rotor in order that I could get a good look at the wiring. There was nothing immediately obvious, so I connected it to another set and made a voltage check, moving the valve in the socket as I checked each point. This revealed nothing.

It then occurred to me that the trouble might be in the socket, the contacts possibly having become fouled or corroded. To check this I fished out a defunct valve and contrived to break away the glass envelope, while leaving the base and pins intact. Then I clipped away the elements, leaving the leads only above the base. Using the ohmmeter I measured the resistance between each pin and the associated socket contact, rocking the base in the socket as I did so. Once again I could detect nothing wrong.

That seemed to clear the socket, but I could not ignore the previous evidence that the fault was closely associated with the movement of the valve in the socket. So where did I go from here?

I decided to try a little brute force or, as a colleague is wont to say, "Abandon the scientific and resort to the primitive." I armed myself with a pair of long pliers — a pair with particularly good gripping teeth — and began a systematic "tug test" of all joints associated with the socket.

And that's how I found it. This model turret has a 5.6pF capacitor running from pin 7 of the socket (triode plate) to the chassis. The connection to the socket lug was perfect but when I tugged on the chassis pigtail it came straight out of the solder. Considering that this capacitor was directly associated with the oscillator circuit, it is easy to understand how the faulty connection to it had caused such a drastic change in behaviour.

To be fair, the soldered joint looked good. It was a nice smooth blob of solder on the chassis, with the solder seeming to flow nicely up the pigtail. Yet it was as dry a joint as any I have ever struck, the wire simply sitting in a hole in the solder.

Unfortunately, dry joints seem to be just as much a problem today as ever they were. They are insidious things, seldom apparent when the equipment is new or being tested, and often not showing up for several years. And when they do show up, they often cost a small fortune to find.

If it's any consolation, the entertainment side of the industry is not the only one plagued by them. As I mentioned on a previous occasion, my amateur friend tracked down several in a piece of communication equipment he purchased cheap after it had been discarded from commercial service. Nor was his experience an isolated one, his fellow amateurs regarding it as the usual thing. In fact, I suspect that a major reason for much of this equipment being replaced is that it is old enough for the dry joints to become troublesome.



# NEW!



# INSTANT COLD GALVANIZE...

*equals hot-dip galvanizing at 1/2 the cost*



LPS Instant Cold Galvanize is a ready to use 95 p.c. PURE ZINC compound that provides long-lasting protection from rust and corrosion.

LPS Instant Cold Galvanize is NOT A PAINT! When applied to iron or steel it generates a positive electric current that flows to the base metal. This electrochemical action fuses the zinc compound with the metal. Corrosion will attack only the outer zinc coating leaving the metal to be protected rust free. If coating is penetrated LPS Instant Cold Galvanize will sacrifice itself to protect the exposed base metal. RUST CANNOT SPREAD.

**USES:** LPS Instant Cold Galvanize should be used wherever metal is exposed to corrosive conditions such as in the construction and maintenance of:

AUTO & TRUCK BODIES	RAILROADS	TRAILERS
FARMING EQUIPMENT	WATER TANKS	FENCING
MARINE EQUIPMENT	MOTOR BIKES	OIL RIGS & PIPE LINES
METAL ROOFS & FLOORS	TV AERIALS	STRUCTURAL STEEL
MINING EQUIPMENT	SNOWMOBILES	LINES & TOWERS
OFF-SHORE STRUCTURES	GOLF CARTS	UNDERGROUND EQUIPMENT
POWER PLANTS	PATIO FURNITURE	LAWN & GARDEN EQUIPMENT
AIR CONDITIONING, HEATING, & REFRIGERATION SYSTEMS		

## TECHNICAL INFORMATION:

Passes PREECE TEST for hot-dip galvanizing  
SINGLE APPLICATION THICKNESS — approximately 1½ mils  
COVERAGE — approximately 50 square feet per pound

TOUCH DRY — 1 minute . . . can be painted over in 6 hours or 30 minutes after baking at 350° for 15 minutes

### WITHSTANDS:

- Over 3,000 hours in salt spray cabinet
- Continuous dry heat up to 750° F.
- Water temperature above boiling point
- Short period heat up to 1000° F.

## SPECIFICATIONS:

LPS Instant Cold Galvanize meets or exceeds the following specifications:

- MIL - P - 48105 weld thru primer
- MIL - P - 21035 Galvanizing repair ( U.S. Navy )
- MIL - P - 26915A for steel ( U.S. Air Force )
- MIL - T - 26433 for towers ( Temperate and Arctic Zones ) ( U.S. Air Force )
- Complies with Rule 66-3 Los Angeles and San Francisco

LPS Instant Cold Galvanize provides maximum protection when applied to clean dry metal.

Available in 16 oz. Aerosol spray-cans



LPS RESEARCH LABORATORIES, INC.  
2050 COTNER AVE. • LOS ANGELES, CALIF. 90029

(213) 478-0095

Distributed by

**ZEPHYR PRODUCTS PTY. LTD.**  
70 BATESFORD ROAD, CHADSTONE,  
VICTORIA  
Phone: 56 7231





**VISIT OUR  
CENTRES AT**

## SYDNEY

KIT-SETS AUST. (SYDNEY) P/L.  
400 Kent Street, Sydney. Phone 29 1005

## DEE WHY

HEAD OFFICE, SALES CENTRE AND  
NATIONAL MAIL ORDER DEPT.  
KIT-SETS AUST. P/L  
1st Floor, 21 Oaks Avenue, Dee Why. Phone  
982 7500 (3 lines)

## ADELAIDE

KIT-SETS AUST. (S.A.)  
50 Grenfell Street, Adelaide  
Phone 87 5505

## BRISBANE

KIT-SETS AUST. (QLD.) P/L.  
293 St. Paul's Terrace, Fortitude Valley. Phone  
52 8391

## MELBOURNE

KIT-SETS AUST. (VIC.) P/L.  
271 Bridge Road, Richmond. Phone 42 4651

NEWCASTLE DISTRIBUTOR — VARCOE BENNET  
Third Avenue, Lambton North

**IF YOU CAN'T VISIT US —  
LET US BRING OUR CENTRES  
TO YOU**

**FOR SIMPLE, CONVENIENT SAME  
DAY MAIL ORDER SERVICE  
EITHER —**


Send your cheque  
and order to:

KIT-SETS AUST. PTY. LTD.  
P.O. Box 176,  
DEE WHY, N.S.W. 2099

Phone Sydney (02)  
982 7500 any  
time, any day  
to receive prompt  
PMG/COD mail  
service. Your requirements  
are as close as your phone.

# AUSTRALIA'S LEA KITS — COMP


## PLAYMASTER 136



**\$55.00. Post / Pack \$2.00**

A high performance stereo amplifier which is easy to construct, by following the detailed instructions in the Dec. 72 issue of E.A. 13W RMS per channel. Freq. resp. 20Hz — 120KHz. Five inputs, inc. MAGNETIC. Kit complete except for Fairchild transistors (see E.A. for special offer on these).

## HIGH QUALITY TUNER



Playmaster 138 as described December 72 E.A. Quality unit includes tuning meter R.F. stage whistle Filter etc.

**\$65.00** post / pack \$2.00  
Teak case \$6.50 extra

## PLAYMASTER 132 KIT SET



45W. RMS per channel. Complete kit as per parts list includes Tuner, Push-Button switching, 4 inputs, Reg. Power Supply with overload protection. Oiled Teak cabinet ready made. All parts new and guaranteed. See June / July 71 E.A. for all details.

**Kit price: \$146.00 Reg. Post \$2.00.**

## SPEED CONTROL



**\$13.50 kit**  
P & P 75c


Will vary speed of electric drills, saws, projectors, etc. See May E.A. Can handle to 750W. MOTOR STILL MAINTAINS GOOD TORQUE AT LOW SPEEDS.

## TRANSISTOR TESTER



A very useful piece of test equipment. Tests transistors, diodes, FETS, etc., etc. Our kit complete including battery **\$14.50**, post 75c.

## E.A. 160 COMMUNICATIONS RECEIVER



**\$87.90**

Professional unit capable of receiving S.S.B., CW & AM.

Special features include R.F. tuning B.F.O., Amplified A.G.C., S Meter, Fine Tuning, Audio Section employs TAA 300 IC. Frequency coverage is 0.5 26MHz. Mains operated with zener protection. ALL NEW PARTS as per Parts list in publication. Reprint of the articles available on request.

**SPECIAL PRICE \$87.90**  
P & P \$2.00

## MUSICOLOUR II



New updated lights display as per Dec 1971 E.A. Can handle 1000W on each of 3 channels. Quality kit. ALL TOP GRADE PARTS.

**\$49.50** Post \$1.00

## NEW "ELECTRONICS AUSTRALIA" PROJECT

### E. A. DIGITAL CLOCK




A Digital Clock giving high performance at low cost. Has exceptional reliability being synchronised to 50Hz mains and can be extended to various forms to suit the application.

Features "Nixie" tube neon displays but can be adapted for LED 7 segment displays, if required.

PRICE: **\$57.00** for complete kit of parts, including "Nixies" and Kit-Sets special IC offer.

## FOR THE BUI CONSCIO



A solid state stereo amplifier — 1000 featuring silicon transistors watts music power, 10 watts RI at 8 ohms and a frequency re 18,000Hz. Ideal for rear chann **BEATABLE VALUE AT ONLY \$** Package / road freight \$3.00.

**ONLY NEW AND GUARANTEED PARTS**



# DIY ELECTRONIC SPECIALISTS

## COMPONENTS - TEST EQUIPMENT - HI-FI STEREO

### 131 TUNER



Tuner as described Feb. 71 E.A. sensitivity 15 UV. 6V operation. Another kit. Fully guaranteed. \$21.50 (Post 75c) **ed: \$26.50 (Post 75c)**

### COMPONENT SPECIALS


07	10 for	\$3.20
08	10 for	\$3.20
09	10 for	\$3.20
01	10 for	\$2.10
04	10 for	\$2.30
055	2 for	\$3.20
2155	each	\$4.80
Transformers		
1. MV5023 / 25	each	\$0.75
2. MV5082	each	\$0.60
3. 7 segment	each	\$7.00
4. Metric readout		
5. for		\$26.00
6. Segment driver / decoder to suit		\$4.00

### CDI KIT



**\$20.50**  
Post \$1.00

Described in August 1970 E.A. Will greatly improve overall performance of any 12V Car, either pos. or neg. earth. Kit complete in every detail in a diecast box. Transformer has secondary Prewound.



### STEREO AMP KIT


Also ideal for rear channel quadraphonic sound. Beautifully presented, this simple "do-it-yourself" project for a 3W R.M.S. Stereo Amp. Module comes complete with all parts and instructions. As distributors for this line, we offer a special price.

**PRICE \$27.50 Post 75c.**

### NEW KIT-SETS EXCLUSIVE — THE MOODCOLOUR 4

#### A specially designed, simple-to-construct-by-anyone

## 4 CHANNEL AUDIO COLOUR UNIT



**CREATE LIVING COLOUR THAT MOVES WITH THE MOOD OF YOUR MUSIC!!**

Designed to beat all others, this unit features:

- 4 independent channels with variable filters driving 1Kw ea.
- Brilliant definition.
- Mono or stereo capability.
- Only 100 Mv drive for full display.
- Handsome styling with black front panel and teak ends.

**A MUST FOR YOUR HI FI SYSTEM**

*Music  
Inspired  
Light and  
Colour*

**COMPLETE KIT  
ONLY \$69.50**

(Full instructions supplied)

**WIRED AND  
TESTED \$85.00.**

Reg. P & P \$2.00



Now . . . a faster, easier way for you to enjoy your favourite Kit-Sets product.

Obtaining credit from your nearest Kit-Sets Electronics centre is as easy as kit building itself. Just drop by the store, fill out an application and hand it to any of the store staff . . . they'll handle the rest. It's that easy. In a few moments you're on your way to enjoying the high quality and superb performance of your favourite kit or Hi Fi equipment . . . while you pay for it in easy instalments.


. . . get full details at your Kit-Sets Electronic Centre.

### SPECIAL OFFER

### INCREDIBLE 3 WAY — 4 SPEAKER SYSTEM

Features 2 x 3" tweeters, 1 x 5" midrange and a specially designed 12" high compliance roll surround bass driver. Comes complete with 3-way L.C. crossover and individual gain controls on midrange and tweeters. Will handle a genuine 20 watts R.M.S. and will perform to satisfy the most discerning listener. Baffle unit ONLY: \$69.00. 1 cu. ft. speaker cabinet in kit form to suit, only \$23.00. Package / post each \$3.00

### GET S



FOR THE BUDGET CONSCIOUS

### PLESSEY WIDE RANGE TWIN CONE LOUDSPEAKERS

These superb twin cone, wide range speakers provide excellent sound reproduction over a wide frequency range and can be easily added to, at a later stage if required.

	Size	Freq. Response	Power Handling (watts)	Price
C6LX	6"	54-20000	6	\$6.40
C8MX	8"	35-20000	7	\$9.50
C80X	8"	35-20000	20	\$14.90
C100X	10"	40-20000	20	\$15.50
C12PX	12"	35-13000	30	\$21.00
12UX50	12"	40-13500	50	\$47.00

3 Phodis DA-roughout, 30 \$ per channel onse of 30-sound. UN-1.00.

**BRAND NEW! AVAILABLE NOW**

KIT-SETS 1973-74 Catalogue, containing over 80 pages with the very latest in electronic components, projects, kits, test equipment, tools, servicing aids, accessories, diagrams, definitions, hints, etc. Also features a new Hi Fi Section containing our selection of the best available.

A MUST FOR ALL ENTHUSIASTS, HOBBYISTS, SERVICEMEN, AND ANYONE REMOTELY INTERESTED IN ELECTRONICS!

No other publication in Australia offers so much.

**FILL THIS CARD  
OUT NOW** and

forward it together with your cheque or money order for 65c and 20c postage to:  
**KIT-SETS AUST.**  
PTY. LTD., P.O. Box 176, Dee Why, N.S.W. 2099.

**KIT-SETS AUST.** PLEASE RUSH ME BY RETURN MAIL ( )  
**COPY / COPIES OF YOUR 1973-74 CATALOGUE**

Name .....

Address .....

..... (Postcode) .....

Cheque / money order for 85c is enclosed.



**SUPPLIED**

Why take chances? KIT-SETS AUST. does not deal in manufacturer's seconds, rejects or surplus but as Australia's largest electronics specialists, we guarantee to match or better any genuine price obtainable elsewhere



**Wouldn't it be nice if you could get one of National's new LM 321 pre amps plus one of their famous LM 308 op amps to use with it, plus data sheets and application notes all in one swell Designers Kit for 1/3 off—only \$4.95?**

**Guess what?**

<b>1/3 off</b>		<b>1/3 off</b>
To get your Designers Kit for only \$4.95 with data sheets and application notes, call or take this coupon to your nearest franchised National Semiconductor distributor (listed below). Do not mail to N. S. Electronics Pty. Ltd.		
Name _____		Title _____
Company _____		
Street _____		

**NATIONAL**

**Swell  
Designers Kits  
Here**

Victoria — Radio Parts Pty. Ltd.	30 1251
N.S.W. — Pre-Pak Electronics	797 6144
Electrobit	867 4611
Professional Electronic	28 6287
Queensland — N. S. Electronics	70 8097

Tasmania — Medhurst	34 5511
S.A. — Gerard & Goodman	23 2222
W.A. — Moncrief	25 5722



Nor does the latest equipment appear to be much better. Another colleague is a full time maintenance technician for a company which runs a large fleet of radio equipped vehicles. Over the last couple of years he has been re-equipping the fleet with all-solid-state units in place of the old valve and hybrid units.

I asked him whether the solid state units were inherently more reliable than the valve units. "Oh yes," he replied, "with no valves to wear out or go noisy there is almost nothing to go wrong — once you've got rid of the dry joints, of course."

In short, the dry joint now appears to be at the top of the list in terms of inherent faults.

What is the answer? I wish I knew. I should make a fortune. Some claim that the power wrapped joint is the solution; others that dip soldering, as used on printed boards, is superior to hand soldering. Perhaps they are both right, yet I doubt if either is the complete answer.

Reverting to the tuner which started all this, I can only confess to having been completely fooled by the symptoms. With the benefit of hindsight I can appreciate that the extreme nature of the fault was significant, and I will watch for it in future. I will also give any replaced 6HG8s a good wobble in the socket before pronouncing the job finished.

Thus we learn by experience.

My next story concerns a very different type of equipment; a rather elaborate portable radio which the owner had purchased on an overseas trip. While I never did get the full story I strongly suspect that he had "been took", in that he believed the set was capable of both battery and mains operation. In fact, he subsequently realised that it was designed for battery operation only, although there was space for a power supply and for a switch to change from one to the other.

This had happened about two years previously, and when he made another trip overseas recently he took the opportunity to purchase a power supply. This was where I came into the picture.

While on a call to service his TV set he produced the receiver and power supply and wanted to know if I could fit the supply into the receiver and provide the necessary switch. He reminded me that I had done a similar job for his father a few years previously.

I recalled the job readily enough and that it had been quite straightforward. In the circumstances it seemed a reasonable request, so I agreed. Without taking too much notice of the individual units I simply bundled them into the truck — which was my first mistake.

When I eventually found time to study the situation in detail I realised that it was not going to be plain sailing. For one thing the owner had made the classic mistake of leaving the original batteries in the unit after they had been discharged and they had oozed chemical all over the battery compartment. As a result the battery contacts were badly corroded, though nothing else appeared to have been damaged.

More importantly, the power supply was of some make in no way related to the set and, while its electrical characteristics were quite suitable, it didn't even look like fitting in the space inside the cabinet.

What to do? After some pondering I rang the owner and explained the problem. Then I suggested that I extract the individual

components from the power supply and mount them separately in the space provided, having already worked out a way in which this could be done with a minimum of trouble. There were, in fact only three components: transformer, full wave rectifier, and large filter capacitor.

He agreed readily enough, but I couldn't help thinking how much less complicated the whole exercise would have been if he had simply asked me to do the same thing, using locally available components, when he first realised that the set lacked a power supply. Still, that's the way it goes.

The job itself was relatively straightforward, the most fiddly part being to clean the battery contacts and battery compartment. Once this was done I soon had the power supply components in place and the set working from the mains.

Then I fitted a new set of batteries and flicked the changeover switch. Dead silence. Fearing a wiring mistake which might cause damage I switched off hurriedly and reached for the meter leads. A check across the battery showed a full nine volts, but this was obviously not reaching the circuit.

My first reaction was that I probably had not cleaned the contacts properly, but a closer examination seemed to rule this out. To make sure I shifted the negative probe up to the board where the battery wire joined it and the other one to where the positive lead joined the newly fitted changeover switch. When this read nine volts I moved over to the other side of the switch, suspecting a faulty switch. But no, the nine volts was still there.

I switched back to the power supply. There was a bit more than nine volts from this source, on no load, although it dropped to the correct value when I switched the set on. And the set worked.

I switched back to the battery and the set stopped. But now there was no voltage reading on the meter. I switched the set off and up came the voltage. It was as if the battery was seeing a dead short when it was switched into circuit, yet I couldn't imagine how this could happen without the power supply seeing the same short.

I switched the set on again and the voltage vanished. I moved the positive probe from the switch back to the battery terminal and it read nine volts. Well at least that was something; the fault was obviously between the battery terminal and the switch.

But you'd never guess where or why. The lead from the positive battery terminal was a solid wire insulated with plastic spaghetti. The goo from the run down battery had found its way along the wire, under the spag, and had steadily eaten it away.

Which would have been fine if it had completed the job, but it hadn't. What it had produced was a very effective high value resistor. Whether there was a vestige of copper wire left or whether the corrosion had some conductivity, I cannot say. All I know is that there was enough conductivity there to give a normal meter reading under no-load conditions. No doubt I helped by using a VTVM.

A simple fault, but one which caused me some head scratching and shook my faith in Ohm's law for a few minutes. Apart from the humour of the situation, in retrospect, the point of the story is that battery goo can find its way into the most unlikely places and cause some strange symptoms. So next time you clean up one of these spillages, make sure you clean it all up.



The QUAD Electrostatic was the first full range electrostatic loudspeaker produced commercially and is still the standard by which all others are judged. Using closely coupled moving elements some two hundred times lighter than the diaphragms of moving coil loudspeakers and being entirely free of cabinet resonances and colouration, this loudspeaker overcomes the usual major problems of loudspeaker design and provides remarkably natural reproduction of sound. This explains why the QUAD electrostatic loudspeaker is used by broadcasting and recording organisations all over the world, in applications where quality is of prime importance, and as a standard of reference by the majority of loudspeaker manufacturers.

QUAD for the closest approach to the original sound.

# QUAD

is a registered trade mark

For details of your nearest dealer write to British Merchandising Pty Ltd, 49-51 York St, Sydney 2000. Or telephone 29-1571.



# Memorex makes tape that can shatter glass.

## So what?

Sure, that proves our tape records and plays back with the precision necessary to shatter a glass.

But, you buy tape to record and play back your favourite music.

So, it's also important you know that hiss is less noticeable with Memorex. That's because we've increased high frequency response so you can decrease treble on playback.

You'll also notice less distortion at high volumes with Memorex. That's because Memorex is more sensitive than

the tape you're probably using now.

It's all because of the way we coat our tape.

First, we use smaller gamma ferric oxide particles. That means there are more of them on any given inch of tape. More places to pick up and play back sound.

Now anybody could come along and use smaller particles just like us; except for one thing. It's a tough job to coat small particles in a smooth, uniform manner. But Memorex does it. And, just how we do it is a little secret we can't even tell you.

There's one other thing we can't tell you: how Memorex Tape sounds when you use it. You'll just have to listen. Please do.



**MEMOREX** Recording Tape  
Reproduction so true it can shatter glass.

Sole Australian distributors

**LEROYA INDUSTRIES PTY. LTD.**  
266 Hay St., Subiaco, Western Australia 6008

VIC.: BJD Electronics P/L, 181 Bourke St., Melbourne 3000.  
QLD.: Brisbane Agencies, 72 Wickham St., Fortitude Valley,

N.S.W.: Linier Sound P/L, 20 Pittwater Rd., Gladesville, 2111.  
S.A.: Sound Spectrum, 33 Regents Arcade, Adelaide, S.A. 5000.  
A.C.T.: Pacific Stereo P/L, 17 Style Arcade, Manuka, 2603.



# Television — Early Systems (2)

BBC low definition service. Early receiving equipment. Disc and mirror drum systems. Transmission scanning systems. Spotlight scanning. Intermediate film system. High definition systems. Zworykin's Iconoscope. Marconi-EMI and the Emitron. Baird's 240 line system. First high definition service.

By 1928, in spite of the limitations of the low definition system, Baird and his supporters felt that it should be given a trial as a public service, via the BBC. Initially, the BBC was less than enthusiastic, feeling that the quality was not good enough, particularly as such transmissions would have to be limited to the 9000Hz modulating frequency permitted for British broadcasting stations.

But the Baird camp persisted and, in March 1929, the BBC consented to an official test. The result was acceptance, in principle, of Baird's suggestion. After somewhat protracted negotiations, an agreement was reached whereby Baird was given five half-hour sessions a week for experimental transmissions.

These transmissions commenced on September 30, 1929. Initially, only one transmitter was available, so there was no accompanying sound. In March 1930 a second channel was provided, allowing simultaneous transmission of vision and sound. Vision was transmitted on 870kHz and sound on 1330kHz.

In 1932 Baird's apparatus and engineers were taken over by the BBC and his studios transferred to Broadcasting House. These transmissions continued until April 1934, when they were curtailed to two half-hour sessions a week.

The advent of these transmissions created a great deal of interest, particularly among experimenters. They found that, for the expenditure of a few pounds, they could convert the BBC signals into moving pictures.

Results could be obtained with equipment which was almost unbelievably simple. A neon tube, a disc (which could be home-made), and a small electric motor were the basic materials. The neon tube was connected in place of a conventional radio receiver's loudspeaker, the disc mounted on the motor shaft, the neon tube mounted behind the disc, and the experimenter was in business. A typical advertisement of the day offered a complete kit for £5-9-6 which could be assembled in 45 minutes!

The neon lamp was a special design using a relatively large rectangular plate as the main electrode. When viewed through the holes of the disc, running at the correct speed (750 rpm) and in proper phase, it created the image as its light output fluctuated in sympathy with the incoming signal.

Results from such simple equipment were strictly limited. In addition to the fundamental limitation of definition, the picture was small, about 45mm x 85mm, the light output quite low, and the light neon-pink rather than white.

There was also the problem of synchronisation. Initially this was left entirely to the viewer, who had to juggle the speed of his motor, using variable resistors and/or friction brakes, to bring his disc into step, in both speed and phase, with the scanning cycle from the transmitter.

Later, a serious attempt was made to transmit synchronising information along with the picture. This was done by simply masking the top and bottom of the picture slightly at the transmitting end. Vertical scanning was being used, so this produced a brief period of no signal between each line.

With 30 lines at 12.5 pictures per second, there were 375 lines transmitted every second with the same number of breaks between them. Thus, regardless of the picture content, and the other frequencies which it produced, because of the "black" pulses, the television signal always contained a prominent 375Hz signal. This became the synchronising signal.

At the receiving end this signal was extracted and used to drive a small synchronous motor. This unit was additional to the main driving motor which was typically a series wound, brush type, "universal" motor, of about 1/30 horse power. The synchronous motor was mounted on the


same shaft and was powerful enough to slow down or speed up the main motor once the latter was running at approximately the correct speed.

As well as holding the receiving disc in synchronous speed, the synchronous motor could be used to adjust the phase, or "frame" the picture. This was done by rotating the outer case of the motor, carrying the coils, thus causing the rotor to follow it.

The synchronous motor was connected in series with the neon lamp directly in the plate circuit of the output valve. The motor windings were bypassed with a capacitor to provide a path for the higher video frequencies.

Although the scheme worked reasonably well, it was not without its problems. Since there was nothing to differentiate between the black of the picture border, and a black which could occur within the picture, the system sometimes became confused. Large black areas at the top of, and running out of, the picture were particularly prone to cause loss of sync.

Many schemes were devised to produce a bigger and brighter picture. The basic approach was to use a relatively high powered lamp (100W projector type) in



Alexandra Palace, London, where Britain's — and the world's — first regular high definition TV system was established. Two sets of vertical aerial elements are supported between the four sets of radial arms, the top set for vision, the bottom set for sound.



place of the neon lamp. Since filament lamps cannot be modulated at the frequencies involved, a variety of light valves was devised.

One of the most popular used a pair of Nicol prisms and a Kerr cell. One prism polarised the light beam which would then pass through the second prism only if its polarisation was undisturbed. The Kerr cell uses an electrostatic field to rotate the polarisation, thereby effectively

cessful, due to the enormous light loss involved.

This led to the intermediate film system. The scene was photographed with an ordinary movie camera, typically mounted on top of a van for sporting events. A light tight tube ran from the bottom of the camera into the van which was, in effect, a film processing plant.

There was no takeup spool on the camera, the film running straight from the gate into

through a stripping bath after scanning, remove the emulsion, then pass it through an emulsion coating bath, dry it, and pass it back to the camera. Thus only a relatively small loop of film was required.

Regardless of the particular system, the sound was recorded on the film at the same time, to delay it by an equal amount. It was generally claimed at the time that the small delay was of little consequence if an image of an important event could be transmitted.

A similar system was used to present large screen television pictures in a theatre. The television image was recorded on film, the film processed at high speed, and passed straight into a conventional projector.


There were many minor variations of these basic television systems suggested and tried between 1929 and 1934 and it is impossible to detail them all. What we have described should give a fair idea of the state of the art at that time.

In fact, time was running out for all such low definition systems. The truth was that, in terms of television research, they were only the tip of an iceberg. Because they had the advantage of technical simplicity and low cost, and had "arrived", the low definition systems had generated an enthusiastic following and created plenty of publicity.

But results were too poor to be taken seriously. Only the most ardent enthusiasts could derive any real entertainment from such a system, once the novelty had worn off.

Several groups of workers, in both Britain and the USA, had long appreciated this, and had set their sights on a much higher standard; the so-called "high definition" system. So, while the low definition systems temporarily captured the public imagination, the high definition enthusiasts were working hard, with little publicity, toward a goal which they believed would be really worthwhile, even if it took longer to develop and cost more to implement.

The high definition system was an ambitious concept, with many problems to be overcome. Probably the most basic was to find a substitute for mechanical scanning, since the size and complexity of the latter grew enormously as the number of lines was increased. This, combined with their unsuitability for outside broadcasts, ruled



*The Baird 30 line mirror drum scanner. Each of the mirrors on the drum is set at a slightly different angle. The Kerr cell is to the left and below the drum. The light beam from it strikes the mirror in the foreground and is reflected onto the drum via a lens. Note the synchronising motor on the rear of the drum, with a phasing control knob protruding from it.*

modulating it.

Such a cell was commonly used in conjunction with a mirror drum scanner. The mirror drum system, though more complex, was more compact. A typical drum would measure about 150mm in diameter and 40mm wide. Around the outside of the drum was fastened a total of 30 mirrors, one for each line. The modulated light beam from the light valve was focussed onto these mirrors.

The drum was mounted on its vertical axis so that, as it rotated, the beam was swept vertically from the top to the bottom of the screen. To provide the vertical scan, each mirror was set at a slightly different angle, so that each line was traced alongside the preceding one.

The beam from the drum was normally directed onto a ground glass screen, which was viewed from the opposite side. The result was a much larger, brighter picture composed of white light. Kits for this type of receiver were also marketed, particularly by Baird (Baird Television Ltd) and sold for about £25.


Transmitting equipment was somewhat similar. For studio work a mirror drum scanner converted the light from an arc lamp into a series of lines which scanned the scene, while the reflected light was collected by banks of photocells. For films a simple disc scanner was used.

The most difficult image to handle was the outdoor scene. Such a scene could not be scanned with a beam of light, and attempts to direct the image onto photocells after dissection had not been very suc-

cessful, due to the enormous light loss involved. High speed developer and fixer were used and the processed film, still wet, was taken straight to the scanning gate, which was under water. The film was then run into a tank of water until such time as it could be dried and spooled.

Typical delay time between camera gate and scanning gate was 30 seconds, although the German Fernseh A.G. company managed to reduce this to 10 seconds.

A variation on this idea, which was tried with limited success, was to pass the film



*A theoretical diagram of the drum scanner, best studied in conjunction with the other diagram on this page. Note the light path from the lamp, through a polarising prism, the grid (Kerr) cell, a second polarising prism, thence to the drum and the screen.*



# You don't need another lecture on Dolby just facts

The freedom from noise gained with the 'Dolby' system has meaning only if each and every part of the machine is designed and built to the highest standards of mechanical and electronic excellence; as all four Technics 'Dolby' cassette decks are.

To complement the Dolby system, RS279US, RS276US, and RS271US incorporate the exclusive H.P.F. \*\* head, which ensures superb high frequency reproduction. (10 year guarantee). The RS279US boasts of being the world's first 3 head cassette deck.

Additionally RS279US and RS276US have two motors, one of them a Direct Drive brushless low speed motor.

No belts, idlers or clutches so the deck is free from unevenness and vibrations. Wow and flutter is a low 0.10% WRMS.

Naturally all four Technics 'Dolby' cassette decks have CR02/Normal tape selector, automatic stop, memory rewind, lockable pause control and all the other advanced features that contribute to outstanding sound reproductions.

The fact is at least one Technics 'Dolby' cassette deck will fill your needs.

RS 276 US



RS 263 US

RS 279 US



RS 271 US

 **Technics**  
 **DOLBY SYSTEM**



Guaranteed and serviced across Australia by HACO

\* Under licence from Dolby Laboratories Inc. \*\*Trademark



them out. Campbell-Swinton's original suggestion based on the cathode ray tube was the logical alternative, but converting this general concept into practical hardware was a formidable undertaking, even allowing for the enormous technological advances which had occurred in the intervening years.

Then there was the equally basic problem of the bandwidth required. The low definition experiments had used the broadcast or short wave bands and had not generated modulating frequencies much above 10kHz; 15kHz at the most in one or two special cases.

Because an increase in the number of lines requires that the definition within each line be upgraded proportionately, bandwidth increases roughly as the square of the increase in line numbers.

Thus, while the highest possible number of lines was desirable, this requirement had to be balanced against the bandwidth problem. To make matters worse, no one was quite sure just how many lines would be needed for an acceptable picture. Suggestions ranged from 60 lines to 120, 180 and 240.

There was also the problem of handling the vision (video) frequencies before modulation and after detection. Even 10kHz for a low definition image presented problems. When someone suggested a 100 line system at 25 pictures a second it was calculated that the video frequencies would be in excess of 300kHz; a formidable figure at that time.

The suggested solution to the spectrum space problem was to use the ultra short-wave (VHF) bands. There was plenty of room there, the main problem being that they were not well understood at that time. Even while advocating their use, engineers realised that a lot would have to be learnt before it was practical. Much the same applied to the video frequency problem, though they were more confident of coping with this.

Nevertheless, a lot of real progress had been made, particularly in the USA by Zworykin of RCA. The general TV scene in the USA had run roughly parallel to that in Britain, with Jenkins, and others, experimenting with a multiplicity of mechanical systems. But as early as 1923 — only one year after Baird commenced his experiments — Zworykin had begun work on an all electronic system. By 1929 he was able to stage a demonstration which proved that such a system was possible, even though it was still very much in the laboratory stage.

In Britain the high definition champions were Electrical Musical Industries Ltd (EMI) and the Marconi Company. In the 1920s the Marconi Company had carried out extensive work on the development of a high speed facsimile system. In so doing they had encountered, and solved, many of the problems inherent in the transmission of high definition television signals.

EMI had also been conducting television experiments. Like everyone else, they faced the vexed question of "how many lines?" and, in 1931, developed an experimental 120 line film scanner. To test it, and the 120 line concept, under working conditions, they needed a VHF transmitter. They ordered it from the Marconi Company.

Thus began a close liaison between these two companies; one which was to have a marked effect on subsequent events.

Zworykin's work, particularly that

associated with an electronic camera tube, and his demonstration in 1929, had aroused a good deal of interest in the EMI team. They even considered buying the knowledge which RCA had already acquired. As it turned out, the price was too high, and they decided to "go it alone".

In the team which shouldered this task were a number of engineers worthy of special mention: J. D. McGee, A. D. Blumlein, C. O. Browne, N. E. Davis, E.

was based. A patent for a much improved version of the Emitron was issued to McGee and Blumlein in August 1934.

Other members of the team concentrated on the standards to be adopted, and the hardware to achieve it all. The number of lines was a particularly contentious issue. In finally opting for 405, the team seemed to be flying in the face of commonsense. There were many prophets of doom who maintained that the bandwidth required

*Dr V. K. Sworykin shown holding the Iconoscope which he developed. Note the similarity to the Emitron. Both were developed independently in the same general period, although Sworykin started his development much earlier.*



Green, and a number of co-workers. Blumlein is generally regarded as one of the most brilliant engineers of his time. Tragically, Blumlein and Browne, another brilliant worker, were killed in a plane crash while engaged in advanced radar research during the war.

The team's major effort, involving mainly McGee and Blumlein, was undoubtedly the production of a camera tube, similar to that being developed by Zworykin, which they called the Emitron. The patent for this was issued in 1932. (Zworykin published a description of his tube, which he called the Iconoscope, in 1933.)

While McGee appears to have been largely responsible for the Emitron itself, Blumlein concentrated on devising circuits which would compensate for the many deficiencies of this type of tube (which it shared with the Iconoscope). Later, Blumlein was also responsible for developing the television waveform on which the complete EMI television system

could never be handled; that 180 or, at most, 240 lines was not only adequate, but all that could be achieved in practice.

In spite of the sceptics, by 1934 the team felt that they had a viable system; a system which they could offer to the authorities with the assurance that it would achieve lasting public acceptance. As it turned out, the year 1934 was a significant one in television history; one in which many far reaching decisions were made.

Early in 1934, Baird demonstrated a 180 line system on VHF. The vision signals were transmitted on 50MHz and the sound on 48MHz. Mechanical scanning was used at the transmitter but the picture was displayed on a 12in diameter cathode ray tube.

Around the time Baird was demonstrating his 180 line system, EMI and the Marconi Company were making the logical move in view of their common interest in television, and the broad background of experience which, jointly, they possessed.



*An original Emitron, as used for the world's first regular television service, inaugurated by the BBC! The spherical portion contains a rectangular mosaic plate onto which the image is focused through the optical glass window on the right.*



# a turntable with a heart



Unlike conventional turntables, the Technics SL1200 has no mechanical speed reduction system such as fluttering idler wheels or vibrating belts which help cause annoying wow and flutter.

Instead the Technics SL1200 turntable has a 'heart' a Direct Drive, 35 pole D.C. brushless motor rotating at exactly  $33\frac{1}{3}$  and 45 R.P.M., which guarantees a wow and flutter less than 0.03% WRMS and a rumble better than -65 dB (DIN A) - 70 dB (DIN B).

The Technics SL1200 is a true professional high fidelity turntable using a 13" dynamically balanced 3.9 lb aluminium diecast platter set directly onto the motor (the heart) assuring glide smooth rotation.

An S-shaped statically balanced, precision built tonearm with anti-skating control is employed, plus a stylus pressure adjustment from 0.4 grams guarantees perfect tracking.

Variable pitch controls, built in stroboscope speed indicator, oil-dampened cueing device, 'feather touch' cueing control, 4 channel ready, deluxe plexiglass dust cover, adjustable audio insulated legs supporting a cast aluminium base are just some of the advanced features. Without doubt this is the finest turntable available today.

So have a heart — the Technics SL1200 Turntable.



Guaranteed and serviced across Australia by HACO



## Technics



They joined forces to form the Marconi-EMI Television Co Ltd.

About March 1934 the BBC decided to reduce the 30 line transmission to two half hour sessions a week.

In May 1934 the British House of Commons appointed a Television Committee, "To consider the development of television, and advise on . . . the relative merits of the several systems . . ." Blumlein, among others, gave evidence before the committee to the effect that Marconi-EMI could provide a 405 line all-electronic system. Baird Television Pty Ltd also gave evidence, proposing a 240 line system.

In January 1935 the report was presented to the Postmaster General. Among other things it recommended a high definition system of " . . . not less than 240 lines with a minimum picture frequency of 25 per second."

In August 1935 the BBC announced acceptance of the recommendation. Both systems were to be given a trial, operating on alternate weeks. Baird was to use 240 lines, 25 pictures per second; non-interlaced, with mechanical scanning. Marconi-EMI was to use 405 lines, 25 pictures per second interlaced, and all electronic scanning.

Each system was to have its own studio equipment and vision transmitter. A third transmitter, common to both, was provided for the sound. Vision was to be radiated on 45MHz and sound on 41.5MHz.

As a result of this announcement the pressure was really on for both organisations. Baird, still backing mechanical scanning, had to produce a 240 line system capable of handling large studio scenes, film scanning, and outdoor subjects. The fact that he did produce such a system is a tribute to his ability and determination.

EMI faced a similar situation. In early 1935 they had only a few prototype units in existence, from which they had to produce a complete working system ready to go to air. The fact that they did this in 18 months is a tribute to not only their technical ability, but to their unbounded enthusiasm and willingness to work as a team.

The BBC was also under pressure. Alexandra Palace had been chosen as the site for both studios and transmitters, mainly because it was already 100 metres above sea level, and height was important for good VHF coverage. A major job was to strengthen one of the building's corner towers and then to erect a steel tower, another 100 metres high, above it.

Internally the building had to be converted into studios, dressing rooms, administrative offices, transmitter rooms etc. Then the two companies had to supply, install and test their equipment.

By late 1936 both systems were installed and working and both went on the air for experimental periods. The system was formally opened on 2 November 1936. There were in fact, two formal opening ceremonies, one transmitted on each system. After that the two systems operated week about for the trial period.

(The receivers of the day had to be fitted with a time base changeover switch in order to accommodate the two different line frequencies; 6000Hz for the Baird system, 10,125Hz for the EMI system.)

Both systems provided similar facilities, though by quite different methods. Both could televise live studio productions, sound films, and outdoor scenes. In regard to the


latter, both suffered a common limitation; the distance between the camera and transmitter.

Initially, the maximum length of cable between the camera and the transmitter had to be limited to about 330 metres. This meant that outdoor scenes were limited to those that could be staged in the grounds of Alexandra Palace. These were devoted largely to demonstrations of various sporting techniques, golf, tennis, riding etc, by well known experts in these fields.

Apart from this problem, which was soon overcome, the Marconi-EMI system faced no serious limitations. The Emitron camera was just as much at home out of doors as it was in a moderately well lit studio.

Two film scanners were provided so that, as in normal theatre practice, a continuous program could be presented from standard reels of film. The scanners were standard intermittent film projectors, slightly modified, and arranged to run synchronously with the waveform generators. They simply projected the film image onto the mosaic of the Emitron.

The Baird system was not nearly so versatile and, while they could perform all these functions, many of them had to be done the hard way. For small scenes, such



A studio type intermediate film system similar to that used by Baird for his high definition system supplied to the BBC. Although some systems scanned the film under water, this one appears to dry it first, apparently using the heat from the lamphouse.

as three-quarter length presentations, or interviews involving two people, the "flying spot" system was used.

This was similar to that used for the old 30 line system, but upgraded to 240 lines. The light source was a powerful arc lamp, and scanning was by means of a disc punched with 240 holes in a spiral pattern, running at 1500rpm in a vacuum.

For larger scenes, it was difficult to obtain good light coverage using this method, and it was necessary to employ the intermediate film system, which has already been described. This system was also used for outdoor scenes.

For film scanning, involving either rapidly processed intermediate films or standard commercial films, a disc scanner was used, but with a novel modification. Rather than a spiral, the holes were arranged in a circular pattern, providing horizontal scanning only. The vertical scanning was provided by the film, which was moved through the gate continuously, rather than intermittently as for normal projection. This system of continuous motion is still used today, in conjunction with the cathode ray type flying spot scanners.

By February 1937 the BBC had made its

decision; it favoured the Marconi-EMI system. On 5 February 1937 the Baird system was dropped and the world's first regular public TV service settled down to the more or less routine job of supplying programs and learning what could be done.

Even at this early stage the system had so proved itself that Blumlein, representing Marconi-EMI, went to the USA to negotiate a free exchange of "know how" with RCA. By this time RCA were only too happy to agree.

The next big step was to shake off the shackles imposed by the limited length of cable between camera and transmitter. In this case there was a particular incentive; the coronation of King George VI was set down for May 12, a mere three months away. Everyone was anxious that this should be the first outside broadcast.

To do this it was necessary to develop a complete mobile TV station; cameras, control room, VHF transmitter, power plant etc, to relay the signals to the Alexandra Palace transmitter.

The system was developed and built by Marconi-EMI and delivered to the BBC just in time for the coronation. It was built into three large vans. One van carried the

camera control equipment capable of handling three Emitron cameras, plus the sound circuit, control, and microphones.

The second van carried the modulation amplifiers, a 1kW VHF radio transmitter (85MHz), and a demountable directional aerial. The third van carried generating plant for use where AC mains were not readily accessible.

As well as providing a radio link, the system could work into a cable link where one was available. A suitable cable had been provided between Alexandra Palace and Broadcasting House, and to a number of points in the West End of London.

Although the equipment was delivered to the BBC only days before the coronation, with little time for testing, they decided to attempt televising the coronation procession. In spite of these hazards, and poor light caused by overcast weather, the experiment was a complete success. As a precaution both the cable link and the radio link were used, one to serve as a backup if the other failed.

From this point on development was more of an evolutionary nature, but much progress was made before the outbreak of World War II in 1939 closed the system for the duration.



# A sound future

Music reproduction is now going under the greatest revolution since Marconi invented the wireless.

The Seventies will see the complete abandonment of stereo records in favour of the now popular 4 channel concept.

Four channels, yes—but which Brand to buy?

Our Technics engineers have designed this unit with you and your pocket in mind. It offers all the great hi fi features our name is famous

for, built-in (factory matched) Demodulator for CD-4 discrete records and decoders for those other types of 4 channel and your existing stereo material.

This unit offers you everything in one total package — no extras are required to give you true 4 channel realism.

And the cost—well nobody else can match it.

Technics SS1000 offers a really sound future.

Unit includes two rear speakers.

Technics RS 263 US "Dolby" cassette deck optional



Guaranteed and serviced across Australia by HACO

**Technics**



# University

## Test Equipment

All units illustrated come complete with batteries, leads and operating instructions and are backed by "University" sales, service and spare parts.

### Model MVA5-73

The MVA5 is a compact diode-protected multitester with 20 ranges and OFF position.

Size: 112 x 87 x 29mm.

Weight: 285 grams.


Price: \$12.00 + Tax.



### Model UC3 Oscilloscope

The UC3 is a wide range 3" Oscilloscope featuring a wide sweep (10 c/s to 300 kc/s) and is a reliable, stable, portable, compact unit that has been proven over the years.

Price: \$140.00 + Tax.




### Model CT500

The CT500 is a popular, medium priced, 22 range diode-protected multitester that is an essential with either the amateur or professional operator.

Size: 139 x 102 x 38mm.

Weight: 450 grams

Price: \$14.00 + Tax.



### Model EA77 Automotive Tester

The EA77 is a reasonably new unit in our range of Test Equipment, being mainly for the motor trade. It is a Solid State Automotive Analyser, checks R.P.M., Voltage, Resistance, Diode, Dwell, Spark, Current and Condenser.

Price: \$50.00 + Tax.



### Model MVA100

The MVA100 is a diode-protected, sensitive (100 Kohms / Volt) 26 range Tester and is a proven unit for all Radio and TV Servicemen.

Size: 178 x 133 x 76mm.

Weight: 1.36 kg.

Price: \$35.00 + Tax.



*The prices quoted are recommended retail only and most units are normally available ex stock from University or leading distributors.*

#### Among our range of other Test Equipment we have:

Vacuum Tube Voltmeters, A.C. Millivolt Meters, Audio Generators (2 Valve and 1 Solid State unit), R.F. Signal Generators, 5" Oscilloscope, Transistor Tester, L.C.R. Bridge, Resistance Decade Box, Decade Attenuator, Circuit Testers (Battery operated, hand wound operation, mains operation), Exploder Testers, Clip-on Ammeters, Automotive Tachometer and small Valve Tester.

## University Graham Instruments Pty Ltd,


106 Belmore Road, Riverwood, NSW, 2210.

Phone: 53-0644



# Equip your car with a burglar alarm

Elementary  
Electronics



by Ross Tester

Recently, I visited a relative in one of Sydney's more affluent suburbs. Shortly after I arrived, other friends arrived and parked their car behind mine in the street outside.

Later in the evening, it came time to leave, and I went outside to my car. It was there — my friend's was not. It had joined the growing number of cars stolen each day.

I do not want mine to become one of these. Therefore, there is an ulterior motive behind *Elementary Electronics* this month — as well as providing us with a project and story, it provides me with a car burglar alarm!

In considering a burglar alarm, we first had to decide which type. There are a number — ranging from very cheap to very very expensive. An example of the first would be a spring-loaded switch connected to the car door, with an outside switch to turn the device off for legitimate entry.

Another idea is to use a mercury switch; a glass tube with a pair of contacts at one end and a ball of mercury rolling round inside it. Any movement which allows the mercury to flow to the end of the tube containing the contacts closes the switch. One of these could be added to our burglar alarm if desired.

Among the more expensive types is one which works on a doppler principle. If anything moves inside the car, an alarm goes off. Such alarms are available but, at around \$250, they are a little outside my price range!

In between these extremes is a time-delay type. This involves no outside switch, but a time delay enabling you to get into the car and quickly turn off the (secret) alarm switch before the timer allows the alarm itself to function.

This is the type we shall be considering. It involves very little connection to the car's electrical system — a major worry in some cases. Primarily, it works from the switches for the interior dome light (courtesy light), but other switches may be added wherever illegitimate entry could occur: bonnet, boot, etc; or where special protection might be required: glovebox, etc.

Other forms of protection (as well as the alarm) are possible. For example, a pair of contacts on the relay could be used to disable the ignition system. This idea does have disadvantages, as we will discuss shortly.

In designing a burglar alarm for *Elementary Electronics*, we naturally had to keep in mind the cost (and complexity) of the project. We evolved what we consider to be a reasonable compromise. The complexity and cost have been kept well down, but the device is a completely practical one, which should give a good account of itself in any car.

There are two schools of thought regarding the alarm itself, which is usually (for convenience) the car horn. One idea is to have the horn operate continuously after an attempt has been made to break in, even though this will almost certainly flatten the battery in a few hours. The idea behind this is that a car with a flat battery is better than no car at all.

The other idea is to have a time-out circuit which automatically stops the car horn after a set period — say five minutes or so — and re-sets the alarm for another possible attempt by the intruder.

Both ideas have merit. The first is simple, and costs are kept to a minimum. The second has obvious advantages from the point of view of the car owner. Our alarm is designed around the latter approach.

The complete alarm has three time delay circuits; one for the above function, one to permit exit from the car after the alarm is turned on, and one to permit entry before it is turned off. While many of the components needed in the alarm may be obtained from the "junk box," where time delays are concerned it would be better to use all new


arrangements would probably save space.

The finished device needs some type of covering. Otherwise, dust may cause problems with the operation of both the relay and the trimpots. It may be a little difficult to obtain a box of the required shape — the tagboard is quite long.

The reader may be able to fabricate his own from, say, tinplate, thin aluminium or plastic; alternatively, he may care to cut the board into approximately equal halves and accommodate them one above the other with the necessary interconnections.

One of the smaller aluminium "mini-boxes" could then house the alarm comfortably. Whatever the arrangement, it would be wise to drill holes in the case to allow screwdriver access to the trimpots, in case you wish to adjust the times.

Circuit operation is relatively straightforward. As the driver leaves the car, he closes the main switch last thing before he closes the door. As the main switch closes, C1 begins to charge via trimpot R1. After a predetermined time (selected by setting R1) the voltage across C1 reaches the zener voltage, the zener conducts, and TR1 is



*The complete alarm circuitry built on a length of terminal board. The pot on the left controls the exit time and the one in the centre the entry time. A more compact assembly could employ two shorter boards stacked one above the other.*

components in the interests of reliability.

Reliability is all-important in a burglar alarm. It is inconvenient, for example, to have the alarm tripping every time it gets warm. Many automotive alarms have a tendency to do this. To check ours out on this score, we operated it for approximately half an hour in artificially elevated temperatures similar to those found in a car on a hot summer day (60°C). It worked perfectly.

While we built our alarm on a piece of resistor tagboard, there is nothing to stop those inclined using a piece of Matrix or Veroboard. Those with the ability could even design a printed board. Any of these


forward biased. The time taken for C1 to charge is the "exit time" and may be set to, typically, about 30 seconds.

Although TR1 is forward biased at this stage it does not conduct because TR2 is not forward biased. The circuit remains in this state until one of the sensing switches (door, boot, etc) is actuated. As soon as this happens TR2 becomes forward biased and both it and TR1 conduct. At the same time C2 charges very quickly via R2. It is held charged, and TR2 is held on, while ever the door switch is closed.

Because R1 and TR2 are turned on, C3 charges via R3. Once C3 reaches the zener voltage, the BC108 / TT801A Darlington pair



# PAINTON PW ROTARIES



Painton rotary stud switches are available in 1, 2, 3, 4, and 6 pole versions and with up to six banks. Quality proven by years of operation under extremes of environment and a wide variety of conditions, they are designed to give an extremely high electrical performance with maximum reliability and are Post Office approved to RC 1416A.

Improved direct link wiper provides a low capacitance and inductance connection between individual contact studs and the collector ring, and is freely pivoted to ensure constant and even contact pressure.

Contact studs and contacts are silver and gold

plated respectively. Type PW switches are rated at 0.25 amps at 250 VAC, 0.1 amps at 250 VDC and 0.5 amps at 30 VDC.

A full range is available from local assembly. Literature is available on request to the Professional Components Division.

**PLESSEY  
Ducon**

Plessey Ducon Pty. Limited  
Box 2, P.O. Villawood, N.S.W. 2163  
Telephone: 72 0133. Telex: 20384  
Melb: Zephyr Products Pty. Ltd. 56 7231  
Adel: General Equipments Pty. Ltd. 63 4844  
Bris: Douglas Electronics Pty. Ltd. 97 8222  
Perth: H. J. McQuillan Pty. Ltd. 21 4821  
Everett Agency Pty. Ltd. 8 4137  
N.Z.: Henderson (N.Z.): 64 189

AC 65

## EDGE ELECTRIX


Specialists in electronic components & equipment.

25A Burwood Road, Burwood NSW 2134 Phone 747 2931.



### ORION CASSETTE CAR STEREO PLAYER


Mod. C-CS. 12 volts, negative to earth, including speakers and all connections. READY TO GO—A REAL BEAUTY!!!!!!  
ONLY \$75 (\$2 Pack/post)



### STEREO AMPLIFIER COMPONENT KIT:

— complete with instructions and parts to make your own stereo amp.

Less case ONLY \$27.50  
(\$1.50 Pack/post)




### GARRARD 2025T TURNTABLE

with teak base and cover and Sonotone cartridge.

ONLY \$65.00 (\$4 Pack/post)

### EYE LAMP

Specially made for M/colour—green, blue, orange and red. With B/cap, \$3.50 ea. Post 50c.



Rola C100X 8 / 15 ohms	\$14.06
Rola C100 8 / 15 ohms	\$13.50
Rola X30 tweeter 8 / 15 ohms	\$9.18
Magnavox 8:30 speaker 8-ohm	\$15.50
Magnavox 3TC tweeter 8 / 15 ohms	\$4.00

### SPEAKER SPECIALS

Philips ADO160T8 tweeter	\$10.00
6.8 uf c / over capacitors	\$1.68 ea.
chokes	\$1.80 ea.
Full range of Sarlon speaker cloth—all 60" wide—\$2.70 per linear foot.	
Innerbond for speaker enclosures	\$1.80 per yard. (1 yd wide)

Full range of electronic parts at competitive prices:— eg SN7400 . . . 40c ea. IN914 . . . 20c ea.

CATALOGUE now available at 70 cents (incl post)

Fully illustrated!!!!



turns on, pulling in the relay. This relay is connected in turn to the horn relay, which operates the horn. The time C3 takes to charge is the "entry time" which may be set to, typically, about five seconds.

The legitimate user of the car will normally open the main switch (which should be concealed) within this period, and the alarm will not sound. In the event of an unauthorised entry this switch would not be operated, and the sequence would follow through as described, sounding the alarm about five seconds after the door was opened.

This chain of events will occur regardless of how quickly the door is closed after it has been opened. Suppose the thief opens the door, slips quickly inside and slams the door after him, all in less than the suggested five seconds entry time.

This is where C2 comes into the picture. Remember we explained that it would charge very rapidly when a door contact was closed. In fact it will charge in about half a second and, once charged, provides a latching function by continuing to supply forward bias for TR2 after the door switch is opened. Thus, the smart thief will achieve nothing; the alarm will still operate after the five second entry time.

This latching circuit has another function; it determines the length of time the horn will remain on after the circuit is tripped. Capacitor C2 discharges through two paths — the 56k resistor and the 1M resistor, and the 56k resistor and the base of TR2. Because the resistance of the first path is so high most of the current flows through TR2. This constitutes forward bias for TR2.

Therefore, the alarm will continue to sound until the discharge current of C2 is so small that it cannot hold TR2 on. When this happens, the relay drops out, but the circuit immediately re-arms itself in case the intruder decides to have another go.

With the component values shown, the alarm should remain on for at least five minutes, possibly longer. It would be possible to double this time by connecting another 2200uF capacitor in parallel with C3.

To make the alarm circuitry suitable for

positive chassis vehicles, simply replace the BC108s with 2N3638As, the 2N3638A with a BC108, and the TT801 with a TT800. Reverse all zener diodes and polarised electrolytic capacitors, and mark the active rail "negative" and the chassis rail "positive."


We mentioned before that a multiple contact relay could be used to both sound the alarm and disable the ignition system (many commercial alarms use this system). In this condition, the car would be impossible to start. While this is fine in theory, there are problems.

The first is that there is now one more

However, if a thief has gained access to the car without tripping the alarm, and bypasses the ignition switch, a heavy current will flow through the coil. If allowed to continue for any length of time, the coil will overheat and, eventually, may burn out.

There is also the risk that the smart thief will spot the leads to the points or coil, and if he knows anything about cars, will realise that they are foreign to the system.

Fitting the alarm is the next step. First of all, you must determine whether or not your car has a horn relay. A shop manual may help determine this (as well as give the



Complete wiring diagram of the alarm. The physical layout is not critical and any other convenient arrangement should be satisfactory. As an aid to wiring compare this drawing with the circuit below and the photograph on the first page.

thing which might go wrong in the ignition system. While this is not very likely, it must be considered. Much depends on the method of disabling.


If the relay contacts are used to open circuit the primary of the coil, there is a real reliability problem. The smallest amount of dust between the contacts might render your car inoperative.

An alternative approach is to use the contacts to short-circuit the ignition points. This has the advantage that, in normal use, the contacts will not form part of the ignition system, or be required to carry current. The risk of ignition system failure in these circumstances is extremely remote.

colour coding of the wires) but, in its absence, follow the circuit back from the horn itself to see whether it goes directly to the steering column, or via a small metal or plastic box.

If there is a horn relay, you are in business. If not, one will have to be fitted, as the small contacts on the alarm relay will not stand the heavy current (10A or more) drawn by the car horn.

The diagrams on the next page will help. Note that a negative chassis car is shown. A positive chassis car will have different wiring — but as these are now becoming rarer, we will leave wiring of these to the reader. Most modern cars will be negative chassis types.



The circuit employs three time delay networks; exit time, entry time, and "alarm on" time. Each of these is marked and, in conjunction with the text, should make it easy to follow the operation. The "alarm on" time may be increased by increasing C2.



# jaycar

PTY. LTD.

Telephone 211-5077  
P.O. BOX K39, HAYMARKET  
N.S.W. AUSTRALIA 2000  
405 Sussex St., Sydney

NOW THE NEW E.T.I.  
414 MASTER MIXER



## AVAILABLE NOW IN A JAYCAR KIT

Complete kit of parts \$188.00 p&p \$2;  
Kit of parts less national semis \$153.00  
p&p \$2

Kit of parts for one mixer/equalizer  
\$19.10 20c p&p (including semis)  
Parts for pre amp and tone controls for  
two channels \$21.00 p&p 20c  
including semis

Parts for power supply board including  
semis \$26.25 p&p 20c

Metal work \$9.90 p&p \$1

Front panels \$3.40 each p&p 20c

Timber case \$6.75 p&p \$1

All coils prewound

Kit wired and tested \$30 extra.

## E.T.I. 413 100 WATT GUITAR AMPLIFIER

(as featured in Electronics Today Dec '72)

Features • Robust  
and compact •  
Frequency response  
20Hz to 150kHz  $\pm$   
3dB • Total  
distortion .50 at 80  
watts. Complete kit  
of parts



ONLY \$65.00  
Plus \$2.00 p&p.

## PLAYMASTER 136 STEREO AMPLIFIER

(As featured in E.A. Dec '72)



Only  
\$55.00  
plus \$1.50 p.p.

FEATURES • 13 watts R.M.S. per  
channel • Frequency Response 20Hz  
to 120 kHz • Equalisation for  
magnetic pick-up • Inbuilt simulated  
Quad. facilities. Kit of parts  
excluding Fairchild Special Offer  
Transistors.

## E.T.I. 503 ELECTRONIC THIEF-TRAP

(As featured in E.T.I. May, June '71)

FEATURES • Both open  
and closed circuits • 30  
second silent entry and  
exit delay • Fire warning  
facility • Battery operation  
• Ultra reliable and  
maintenance free. Complete  
kit of parts.



ONLY \$23.00 plus \$1.00 p.p.  
(does not include batteries)

A horn relay diverts the heavy current of the horn away from the horn button and through its own contacts, which are designed to withstand the load.

The relay coil is connected between active (positive) and the horn button. The other side of the horn button is connected to chassis (negative). When the horn button is pressed, the circuit is completed, and the relay energises — thus closing the contacts and sounding the horn. Horn relays are available from motor accessory houses for a couple of dollars, if they are not already fitted.

The author obtained one from a disposals source for fifty cents!

The courtesy light circuit must then be identified and tapped into. In the author's car, this was easy, because "bullet" connectors were used and I simply pushed the


point for power to the burglar alarm, make sure that it, too, has power applied at all times.

We have shown a pilot light connected after the burglar alarm switch. The reason for this is not so much to tell you that it is on, but to act as a deterrent to possible intruders.


A commercially available alarm also uses this system, so we are, in a way, "cashing in" on their publicity. A thief will be unlikely to try to enter a car which he knows is equipped with an alarm — he is most likely to try the next one down the street.

Another idea is to use a label on each of the windows advertising the fact that there is a burglar alarm in the car.


The main switch must be mounted in an easily accessible place (remember you only



(a) BASIC HORN CIRCUIT



(b) BASIC HORN RELAY CIRCUIT



(c) HORN RELAY CIRCUIT WITH  
CONNECTIONS FOR ALARM RELAY

Your horn circuit will be either as (a) or (b). If as in (a) a horn relay should be added and the alarm relay contacts wired in parallel with the horn button.

end of the wire from the alarm into the connector along with the bullet. Other cars may not be so easy — you may have to cut the lead and re-solder it, covering with insulation tape, or fit a bullet connector.

It is possible to use a boot light switch as a burglar alarm switch (in case the boot is forced open). Most boot light switches will be wired in the same way as the courtesy light switches; positive to lamp, then to switch and chassis. If so, the lamp side of the switch can be linked to the lamp side of the courtesy light switch, and both will then perform the function of burglar alarm switches as well as their original function.

If the car has no boot light switch, now is a good time to put one in! A boot light is a very handy accessory on a dark night — and once installed, you will wonder how you got along without it.

Remember that the wiring must be as shown for the courtesy light in our diagram. Some light kits may show other wiring (the kit will have instructions). If the wiring differs from what we have shown, disregard it, as it must be done the way shown to allow the alarm to work.

Similarly, a bonnet switch may be installed to detect the bonnet being forced. This may or may not have an associated light.

One problem may occur with the horn. On a few cars, the horn is disabled when the key is turned off and removed. If this is the case, it will be necessary to either install a different type of alarm, or by-pass the key by placing the horn wire, via a suitable fuse, to a point on the fuseboard where power is applied at all times. A multimeter will soon reveal where these points are.

Incidentally, when locating a take-off

have five seconds or so to reach in and turn it off) but must be out of sight to anybody looking for it — from inside or outside. The intruder may risk a few seconds of horn blowing if he feels he has a good chance of finding the switch. One idea is to fit a push-on, push-off switch underneath the floor-mats — in a position where the feet would not normally lie — such as between the brake and clutch pedals.

In this case, there would be no chance of anyone finding the location of your switch — simply because you never reach for anything, but simply trip the switch when you get into the car.

Two switches in parallel may be wired so that the alarm is able to be turned off from the passenger's side — very important if you are ushering guests into the car. However, this arrangement may not be without its problems, requiring a certain amount of commonsense to ensure that both switches are not left in the "on" position, resulting in a false alarm when the car is re-entered.

With the installation finished, it is time to set up the alarm. With a multimeter, check the voltage at the emitter of TR1 and set the exit time. Similarly, the entry time can be set. If you wish to change the "horn on" time, it is best to do this before installation. The 1M resistor can be lowered in value till the required time is reached. It can be as low as 10k for 30 seconds "on" time. Any time below this is generally considered unsatisfactory as a deterrent.

And that's just about it for this month. Next month we will show a small modification to the alarm which will give the horn a "beep beep beep..." action instead of a single long note. Such an alarm is far more attention getting.




## Elementary Electronics Ideas Worth Trying

### Plastic Repairs

I have found the following technique very effective in repairing broken plastic parts which can no longer be replaced. Very often the ability to repair such a part means the difference between salvaging an entire piece of equipment, or discarding it.

One recent job was to repair a volume control knob from a portable radio. It had split from the centre out and rotated on the shaft no matter how hard the retaining screw was tightened.

I took a household pin, cut the head off, and bent a right angle about an eighth of an inch from each end, making it into a very shallow "U".



The knob was held in a vice in such a manner as to close the split. The pin was heated with a soldering iron and, while still hot, forced into the plastic. It is usually possible to force the pin below the surface and, while the plastic is still soft, draw it over the pin. When the plastic is cooled it can be smoothed off with glass paper and is "just like a bought one."


I have used this technique several times with great success, including one on a record player arm where the split ran across the hole for the pivot support pin. In this case I supplemented the joint with Araldite, but fitted the pin to take most of the stress.

(Mr K. Rowe, 15 First Avenue, Fivedock NSW, 2046.)

### Low-cost Battery Holder

Penlite cells are popular sources of power for small experimental projects, but providing a holder for them often presents a problem.

I have found that a match box makes a very good holder for two of these cells. All that is needed is the match box tray, three pieces of metal and two wires.



The two wires are soldered onto two small pieces of metal to make the main terminals. The other piece of metal is larger and forms the connection between the two cells. Glue holds the pieces of metal in place. (Mr L. Roberts, 1 Bruce St. Mitcham, Victoria.)

### Rubber Feet

An easy replacement for rubber feet is an set of rubber grommets mounted in the usual way near the corner of the chassis. This idea can be used in all situations where rubber feet are normally used, and often gives more "slip-proofing" than standard rubber feet. (Mr M. Fletcher, Pakenham, Vic.)

# WANTED

## COLOUR TELEVISION TECHNICIANS!

If this advertisement takes you  
by surprise—you'd better start  
learning about colour now!

Within just 2 years black and white TV will be superseded! With colour will come a huge demand for new sets and new people. You can get the basic training to get into the industry or if you are in it you must get colour tuition now! As an engineer, technician, serviceman—there's a whole new profitable career for you—if you start learning now! Get expert tuition at home, in your own time, with an ICS course. (ICS also have courses in Basic and Advanced radio electronics.) But you **must** start now. Send the coupon today.



POST THIS COUPON TODAY!

INTERNATIONAL CORRESPONDENCE SCHOOLS,  
Dept. 215, 400 Pacific H'way, Crows Nest, N.S.W. 2065.

Please send me your free brochure on Television,  
Radio and Electronics.

Mr./Mrs./Miss \_\_\_\_\_

Age \_\_\_\_\_ Address \_\_\_\_\_

Occupation \_\_\_\_\_ Postcode \_\_\_\_\_

LB3.3013





# 4 channel sound with no complications



Four-channel sound is being shown as a pretty complicated business. You add this. You add that. Maybe you've got true 4-channel. Maybe, Sony's SQR-6650 exciting 4-channel receiver eliminates the usual complicated 4-channel set-up. Built into its stylish, compact enclosure are a high sensitivity tuner, low-noise, low-distortion preamplifier, decoder for SQ matrix and other matrix systems and four power amplifiers which deliver rich 96W dynamic power for true-to-life 4-channel sound. With the SQR-6650, you can enjoy any type of 4-channel sound — discrete, SQ matrix, other matrix plus ambience retrieval from the conventional 2-channel sources. Only add speakers and a turntable system of your choice to complete your entertainment centre. It has been

generally recognised that the "SQ" system reproduces 4-channel sound closest to the original discrete source while providing full compatibility with conventional 2-channel stereo. You can thrill to the accurate spatial quality of the original concert hall right in your living room. Or you can literally be placed in the middle of a folk or rock session with your favourite singer or group. You also get the best that any other matrix system has to offer. Styling is enhanced by deluxe walnut cabinet and refined aluminium control panel with 'black-out' dial scale and versatile facilities. It is a fascinating addition to your room's decor. The SQR-6650 has everything you would ever want in a 4-channel receiver, and more! Share the Sony secret — of excellence!

# SONY®

**JACOBY**   
**KEMPTHORNE**  
SERVICES

SYDNEY: 26 2651, MELBOURNE: 329 6866,  
ADELAIDE: 93 2338/9, BRISBANE: 44 4488,  
PERTH: 81 3422, LAUNCESTON: 2 5322. Agents:  
CANBERRA: 47 9010, NEWCASTLE: 61 4991,  
WOLLONGONG: 84 8022.

For further information please fill in the Reader Service coupon in this issue.

5N5034





# CLASSICAL RECORDINGS

Reviewed by Paul Frolich

## The Bartered Bride—Bamberg Symphony Orchestra

**SMETANA** — *The Bartered Bride*. (complete opera). Marcel Cordes, Nada Puttar, Pilar Lorengar, Ivan Sardi, Sieglinde Wagner, Fritz Wunderlich, Gottlob Frick; Bamberg Symphony Orchestra, conductor Rudolf Kempe. World Record Club stereo S/4518-9-20.

This is the only full recording of *The Bartered Bride* currently available; the only other I know of is a Czech one made about 1953, monophonic and no doubt long deleted; this one, a German HMV, dates from about 1963 and is very good, with marvellously lively stereo, a great degree of presence and plenty of stage illusion thrown in.

The opera — about which, more later — occupies only five of the six sides in this set. The last side contains a series of operatic recordings by Gottlob Frick: two of Hagen's arias from Wagner's *"Twilight of the Gods"* (Berlin Opera, Konwitschny); Falstaff's aria from Nicolai's *"Merry Wives"* (Bavarian State Opera, Heger); the "Porter" song from Flotow's *"Martha"* (Berlin Symphony, Klobucar); and "In diesen heil'gen Hallen" from Mozart's *"Magic Flute"* (Berlin Symphony, Gruber).

This last side is a grand bonus and provides a wonderful survey of Frick's work; in tragedy as in comedy, one of the truly great basses of our day. More importantly, however, this bonus-side is quite a good indicator to the style and quality of the opera recording itself. The action, and the music, are heard to revolve as much around Kecal, the marriage-broker sung by Frick as around the much-liked lovers.

Also, this collection of German arias serves as a useful warning to anyone who might expect an idiomatic performance of this Czech peasant opera.

Don't get me wrong: this IS a fine performance and I would welcome it even if it was not the only one available. In some ways it is, perhaps, too good — the kind of performance one might get if the Metropolitan Opera Company undertook HMS Pinafore. The performance is sung in German — perhaps a very minor point to all but the few who understand Czech and miss the fun of the indigenous text; in addition, the performance is a very German one, a trifle inflexible, a little humourless, utterly correct and bloodless.

What faults I have to find with this performance are relatively minor ones beyond what I said above. Miss Lorengar is not always in pitch and her voice gets a little edgy in places; Wunderlich is rather too heroic for the part of Jenik and the orchestra is, after all, only a provincial one

and must be forgiven for sounding slightly provincial.

But the recorded sound is so good and the actual blemishes are so minor that this set can only have one's warmest welcome — unless, that is, one has had the good fortune of hearing this work performed by Czechs in their own language.

★ ★ ★  
**BEETHOVEN** — The complete cello sonatas. No 1, F major, op 5 No 1; No 2, G minor, op 5 No 2; No 3, A major, op 69; No 4, C major, op 102, No 1; No 5, D major, op 102, No 2. Paul Tortelier, cello; Eric Heidsieck, piano. HMV 2-record set, stereo SLS 836, with leaflet.

When I visited Europe in 1966, I made a special detour to Rheims; I had heard a great deal about Eric Heidsieck, then considered one of the finest Mozart and Debussy interpreters and this seemed to be my only hope of hearing and meeting him.

Not only did I get a friendly reception and a lot of the fine champagne made by Eric's family, but I had the good fortune of hearing him, and his pianist-wife Tania, play for some hours — Mozart, Beethoven, Schumann and Debussy. He was, then barely thirty years old, but highly acclaimed, and justly so, in France, Germany and the United Kingdom. In the years since, judging by recordings, his musicianship has been further refined and he must be counted as one of the greats among today's artists.

While Heidsieck, in his recordings, has been heard either by himself or with orchestra, Tortelier has had other partners in the past, notably with the Schneider Quartet and, in sonatas, with Aldo Ciccolini. Though he is Heidsieck's senior by at least a decade, these two great French artists make the perfect team for the Beethoven cello sonatas.

There is indeed, a great deal to admire in this set, principally perhaps the relaxed air of spontaneity. Both artists play without any evidence of pressure or nerves, intent on their own pleasure in music-making.

This approach is most appropriate in the two delightful sonatas of opus 5; I am aware that some listeners will regret the apparent absence of dramatic tension in the later works. All the same, the approach of these artists is arguably right for this music and wholly justifiable on the grounds of agreeable sound — a characteristic often absent in cello recordings.

Having thus praised the performance and, I believe, rightly, I must mention a few reservations. The use of separate microphones for the two instruments was, I think, a mistake as it interferes with the balance as heard by the performers. The other drawback, if only marginal, is occasional bad intonation from Tortelier, brought about by moments of apparent abandon.

These mistakes, if mistakes they are, are far from prominent and should not interfere with anyone's true enjoyment of this great music, so well played and successfully recorded.

★ ★ ★  
**ENGLISH STRING MUSIC** — Academy of St Martin-in-the-Fields, directed by Neville Marriner. **HOLST**: St Paul's Suite; **DELIUS**: Two Aquarelles; **PURCELL**: Chacony in G minor; **VAUGHAN WILLIAMS**: Prelude "Rhosymedre"; **WALTON**: Two Pieces from "Henry V."; **BRITTEN**: Simple Symphony. HMV stereo OASD 2831.

It is no more than about three decades ago that Dr Boyd Neel gave most of us our first taste of a string orchestra; music has come a long way since then — via the Stuttgart Chamber Orchestra, the Bath Festival Orchestra and others. Now, every sizeable town has one or more permanent ensembles of this kind.

It may be something to do with the traditional British talent for understatement — whatever the reason, England has provided us with the two groups which are probably the best all-rounders at present: the English Chamber Orchestra and this group, both of whom have been heard in Australia.

The collection presented on this disc, ranging from the well-known Purcell piece to the previously unrecorded Vaughan Williams, suggest that the English repertoire is singularly well suited to the development of such ensembles. There is, indeed, a clear trend, based on the dance and influencing English music in every period.

As usual with Marriner, all the music on this disc is treated with exuberant romanticism and made to sound lively and full of interest. The performances in themselves are not unique ones; yet, I know of no better version of the lovely St Paul's Suite nor, indeed, the other pieces excepting perhaps the Britten, in which the composer's own version seems the more persuasive.

One may, of course, have reservations about this type of collection and it will not attract everyone; unless you are opposed to the music itself, the disc will give utter satisfaction, I think. The playing is brilliant and the recorded sound rich and full.

★ ★ ★  
**BARTOK** — *Mikrokosmos*. Huguette Dreyfus, harpsichord. Record Society stereo S 6439.

This is the most fascinating keyboard recording I've come across for a long time. *Mikrokosmos*, composed between 1932 and 1939, is a collection of about 150 short pieces, ostensibly written for performance on the piano. They are contained in six volumes and I regret to have heard no more than perhaps half of these pieces.

Although all these pieces have usually been thought of as belonging to the piano, I have heard some in transcriptions for strings and even for orchestra. I did not know that Bartok, in his prefatory notes, had suggested the suitability of certain pieces for performance on the harpsichord without specifically limiting the number of such pieces.

It is, of course, idle to speculate on whether Bartok would indeed have cared for what we get to hear on this disc. It must be remembered that, in the 1930s, the building of harpsichords was not nearly as advanced as it has now become.

Julian Russell will be overseas for the next few months, and in his absence, Classical Recordings will be reviewed by Paul Frolich.



# NATIONAL RADIO SUPPLIES

332 Parramatta Road, Stanmore, NSW 2048

Phone 56 7398

## NEW RANGE OF RESISTORS CONDENSERS AND POTENTIOMETERS

### CARBON RESISTORS

Current type resistors by Philips, IRC, Ducon & Morganite in a wide range of values from 100 ohms to 10 meg. 1/2 and 1 watt.

\$1.50 per 100

Post 30c Extra

### MIXED CONDENSERS

The condensers are in most popular brands and include polyester, paper, mica ceramic and electrolytic on values to 8mfd.

\$1.50 per 100

Post 50c extra

### CERAMIC CONDENSERS & THERMISTORS

A large range of current disc & tube ceramic condensers & thermistors.

\$1.50 per 100

Post 30c extra

### POTENTIOMETERS

The pots are all current types and include switch pots, standard pots, pre-set etc.

\$1.50 per doz.

Post 50c extra

### POLYESTER CAPACITORS

Pack of 100 new polyester capacitors in 160, 250 and 400 volts working, \$3.50 Plus 50c Post and Packing.

REGRET SPECIAL VALUES IN RESISTORS, POTS, & CONDENSERS CANNOT BE SUPPLIED.

### MAGNAVOX WIDE RANGE TWIN CONE SPEAKERS

8 on 16 ohms VC. Post and packing 65c.

6WR MK V12 Watts RMS \$9.90

8WR MK V16 Watts RMS \$10.75

10WR MK V 16 Watts RMS \$11.50

12WR MK V 16 Watts RMS \$12.50

8-30. 30 Watts RMS \$17.00

3TC Tweeters \$3.75

Philips Dome Tweeter \$10.50.

### SPEAKER SPECIAL

Imported Tesla 8"

Speakers 8 ohm imp \$4.75.

Post and Packing 65c.




### PHILIPS VALVE & PICTURE TUBE DATA BOOKS

Hard covered book of over 500 pages covering all modern valves & picture tubes. List price \$1.75 — Special \$1.75.

## PLAYMASTER 136 STEREO AMPLIFIER

As featured in Dec '72 issue of *Electronics Australia*



High fidelity amplifier with an output of 13 watts R.M.S. per channel, frequency response 20Hz to 120kHz, distortion 0.2% mag. input equalised to R1AA, bass & treble controls, provision for simulated 4 channel.

Complete kit of parts including All Transistors. \$62.00 as above but less Fairchild special transistor offer \$55.00. Reg postage \$2.00 extra.

As an added feature to the 136 amp we have added provision for headphones with phone jack & switch mounted on front panel which is silver anodised with black lettering & matching knobs. We have also had a special transformer wound for this unit with separate 6v winding for indicator bezel & with electrostatic shield.

### PARTS FOR ABOVE AMPLIFIER


Metal work inc. heat sinks \$7.50 post 70c.

Circuit boards set 3 \$5.50 post 25c.

Anodised front panel \$3.70 post 25c.

Power transformer \$8.50 post 70c.

### A TRANSISTOR PREAMP FOR MAGNETIC PICKUP OR TAPE HEAD (Stereo)



Using 2 transistors per channel, as featured in "Electronics Australia" (Sept. 1971). Complete kit includes transistors, PC board, resistors, capacitors. Circuit and full details supplied.

Kit (not incl. box) \$7.90

240V Power Supply \$4.50

Metal box \$2.75 extra

State if required for pick or tape head.

### NEW LOW COST STEREO SYSTEM

AS FEATURED IN JAN. ELECTRONICS AUSTRALIA



Complete kit of parts including "Garrard" record player with auto stop and crystal pick-up. Magnavox 8WR or 6WR wide range twin coned speakers. (Cabinets not supplied). Amplifier only, less speakers and player, \$32.00. \$69.50 Post and packing \$2.50 extra.

## CLASSICAL RECORDS

Miss Dreyfus, playing a modern instrument built by Neupert, made the transcriptions heard on this disc. They are very much to my taste and I believe that they are indeed what Bartok himself would have done, had he been able to obtain so fine an instrument. I can only say that I have not heard Bartok's late keyboard pieces to greater advantage.

The disc, apart from being one of the best harpsichord recordings I know of, may well help some stubborn diehards to an easier acceptance of Bartok's music and musical ideas. It is the virtue of the harpsichord that musical lines emerge more clearly and that sounds which might seem harsh on the piano are found to be sensual.

This is beautiful music, superbly played and well recorded. Moreover, this is one of these rare occasions when an out-of-the-way overseas item is given Australian release — the Record Society, in obtaining this recording from the Harmonia Mundi catalogue, is really doing its members proud!

★ ★ ★

**TCHAIKOVSKY — The Nutcracker**  
(complete ballet). London Symphony Orchestra, conducted by Andre Previn. 2 HMV stereo SLS 834.

Except when attending the ballet, live, many years ago, I'd never heard a complete performance of this music, live or on disc. All I knew (and I dare say that goes for most listeners) was the "Suite" which contains about one-fourth of the ballet's material and discs of "excerpts." The Suite, op 71A, is by Tchaikovsky; the excerpts are anyone's — the best-remembered being those arranged by Spike Jones in the 1940's on, if I recall correctly, eight sides of 78s!

Although I got a lot of enjoyment out of this two-disc set, I really don't think it is for general music-lovers — rather for Tchaikovsky specialists and utter balletomanes. The music is really charming, including some of the rarely heard pieces, and far from boring despite the overall length — melodically each piece is novel and self-contained and most items are too brief to have allowed any turgidity to creep in. In fact, they present Tchaikovsky's inventiveness and skill at their highest.

Despite what I've said: four sides is rather a lot and I certainly don't recommend taking it all at one sitting — that way lies indigestion. The performance by the LSO is exemplary, both in breadth and in detail; Mr Previn's conducting is both meticulous and imaginative and the recorded sound and stereo balance of the highest standard.

★ ★ ★

**MOZART — Piano Concerto No 22 in E flat, K.482; Concert Rondo in D major, K.382.** Daniel Barenboim, piano and conductor, with The English Chamber Orchestra. HMV stereo OASD 2838.

Listening to this recording has been a pleasure but, also, a rather disturbing experience. Barenboim, then only 22 years old, recorded this same concerto in Vienna in 1964, with Laszlo Somogyi conducting. The recording, by Westminster, was briefly issued in Australia by the Universal Record



Club and it so happens that I still treasure it.

Although a beautiful and accomplished work, this concerto has not fared well in the LP age. Apart from an old Lilli Kraus version (with poor orchestra and sound) on Vox, the 1964 Barenboim is the best I've known to the present. This new version has many virtues — not least the intimate integration of orchestra and solo piano, brought about by Barenboim's dual role. Conducting from the keyboard is not always a safe undertaking; Barenboim is one who can risk it and the ECO respond to his every whim with joy and pride.

Make no mistake: whims there are aplenty. Freed from the restraints an older conductor, such as Somogyi, might impose, Barenboim gives free rein to his romanticism. The results are, in turn, enchanting and infuriating. There is, to me, a quite unjustifiable cadenza by Barenboim in the 1st movement — a real kitchen-sink spit of a one. On the other hand, there are moments of quite exquisite sensitivity; especially in the slow movement.

A detailed analysis of a standard concert work would be pointless; I've said enough to indicate that this will be not be to the liking of all Mozartians. At the same time, I know of no available recent recording of the work which is anywhere near as good as either recording or performance.

The Concert Rondo K.382, previously not known to me, is a work of charm rather than of great inspiration. It makes very pleasant listening in any event, a welcome filler with novelty value and it, too, is excellently played.

★ ★ ★

**WALTON — Belshazzar's Feast; Improvisations on an Impromptu of Benjamin Britten; John Shirley-Quirk, baritone; London Symphony Orchestra and Chorus, conducted by Andre Previn. Angel quadraphonic Q4 SAN 324 (also on stereo SAN 324).**

The "Improvisations . . ." which open this recording is Sir William Walton's 1970 tribute to Britten; a type of very free variations, it tells us more about Walton than about Britten. The basic melodic material was Britten's, but the complex and rich orchestral sound is wholly and unmistakably Walton's. A very fine piece, it is excellently played and most welcome.

"Belshazzar's Feast" remains one of the greatest of all choral works and I don't think I will ever fail to respond to its expressiveness or to the unique volume of orchestral sound it unleashes. There have not, to my knowledge, been any wholly bad performances of this great work on disc, though Ormandy's of a few years back was a bit clumsy and overblown. In any case, this performance is magnificent, in no way inferior to that directed by Sir William himself and, here and there, actually to be preferred to it.

Previn's quick rise to the front-rank of conductors has rested on solid work and convincing readings of great (and far from easy) works; this is one of the best yet and sure to gain him many more admirers.

This is the first quadraphonic disc I have reviewed; the record is of the SQ matrix type and it is only right to mention here that the much more expensive "discrete" system of quadraphonics is the superior one. However, I own neither one nor the other and am not yet convinced of the necessity for such equipment, given my restricted musical tastes.

If I was likely to listen to works such as "Belshazzar" with great frequency I would, I believe, invest in a modern quadraphonic system without delay. There isn't the least doubt that the system greatly enhances one's pleasure and appreciation — there is not only a sense of being inside the music but, also, far greater clarity. With music of such complexity, it is indeed exciting to be able to separate individual strands and then hear them merge again.

Both the precision and the opulence of the playing are better to be judged on such a quadraphonic disc — there is a definite, though not tragic, loss when the disc is played through a conventional stereo system. One final word: John Shirley-Quirk is in wonderful voice and by far the best soloist I've ever heard in this work.

In honour of Walton's seventieth birthday, this year, this recording is one every music-lover should hear; it may well become a standard of excellence for years to come.

★ ★ ★

**MUSSORGSKY — Boris Godounov (Opera excerpts). Gottlob Frick, Martti Talvela, Rudolf Schock, etc; Choir and Orchestra of the German Opera, Berlin, conducted by Levko von Maticic. Ariola-Eurodisc (Festival) stereo 80011.**

Although this disc of excerpts (four scenes) can hardly be described as the last word on "Boris," it includes some very remarkable performances. This opera is wholly Russian in musical content and I doubt that its full flavour could emerge in a German version, however good the individual contributions.

Apart from very fine orchestral playing and a beautifully engineered sound, the highest prize is due to Frick, in the name-part. His tragic feeling and dramatic style are utterly convincing; though he sings in German, I find his Boris at least as moving as Boris Christoff's. The other bass part, that of Pimen, is sung rather less successfully by Talvela; this is a pity — in the two Christoff versions, the Bulgarian bass tackled both parts himself and one could wish Frick had done likewise.

All other discs of "Boris" excerpts known to me end with Boris' death; this one continues with the "Revolution" scene which, dramatically as well as musically, is rather a let-down. Although I might regret this particular arrangement, it is redeemed by the lovely tenor voice of John van Kesteren; singing the small part of the Idiot, he brings the recording to a moving end.

On the whole, I think "Boris" is too beautiful and important a work to be

treated as a collection of fine tunes. If there are to be excerpts, ones from idiomatically first-rate performances — such as those by Christoff or Ghiaurov — are probably to be preferred. All the same, I found this an interesting and worthwhile experience and I am, once again, full of admiration for Gottlob Frick and his versatility.

★ ★ ★

**DELIUS — Paris (The Song of a Great City); Eventyr; Dance Rhapsody No 1. Royal Liverpool Philharmonic Orchestra, conductor Charles Groves. HMV stereo OASD 2894.**

To listeners of my generation, Delius' music always raises the ghost of Sir Thomas Beecham, without whose devoted sponsorship this composer might have remained half-forgotten to this day. When we hear a performance of a work such as "Paris," the standard of comparison is, therefore, almost automatically Beecham's.

After this preamble, I will hardly be expected to acclaim Groves and his Liverpoolians as greater than Sir Thomas and his own Royal Philharmonic Orchestra. And I don't think they are better but: they are every bit as good!

There will never be another Beecham and none else should be expected to conduct Delius quite as he did. Groves may, as it happens, be closer to the true spirit of Delius in these works. Where Sir Thomas was wilful and made his own tempi as it suited him, Groves seems to me to be able to achieve greater lyricism — the quality I most treasure in Delius' music.

A more detailed comparison of the two conductors' ways with Delius shows differences of surprising magnitude. Where Sir Thomas revelled in the sound of brass, Groves remains concerned to allow the strings a clear space in the spectrum and Groves' tempi are more evenly contrasted.

The playing of the two orchestras is not, I think very different. But, where Beecham had only mono, Groves has stereo sound and that makes things sound a great deal more interesting. For my part, I'd want to have both versions available to me — but if you have not been able to get the Beecham, this one will prove quite adequate. ②

## HI FI ANNUAL

Still available from our office or box 157, Beaconsfield, 2015.  
\$2.30.

## TRANSFORMERS FOR PROJECTS

Specialists in the small-batch production of high-quality Transformers for industrial and entertainment equipment. Transformers can be produced for any project published, or to your own special requirements.

Facilities available for vacuum impregnation in a wide variety of materials or complete encapsulation in Epoxy or Polyester resins.

Trade and retail enquiries handled throughout Australia, New Zealand and the Pacific Islands.

## TRANSFORMER WINDERS LIMITED

37 CRUMMER ROAD, AUCKLAND, NEW ZEALAND.




# THE SILVER WHIRLY THINGS ARE CORAL'S WIDE-FOCUS ACOUSTIC LENSES.

Exclusive Wide-Focus  
Acoustic Lenses.

Flat Baffle-Type  
Cabinet.

Hollow Formed  
Cone.

Airtight  
Enclosure.





# IF YOUR SPEAKER DOESN'T HAVE THEM, YOU COULD BE GETTING A PRETTY NARROW VIEW OF HIGH FIDELITY.

You're a prisoner of your stereo system, and you don't even know it. But it's an easy matter to demonstrate; where do you sit to hear your present system at its best?


You know the answer to that one. There's virtually only one position; a narrow area at the apex of a triangle formed by you and your speakers. Move back beyond it, against the wall or out to the corners and the sound starts to blur.

That's why we say you could be getting a narrow view of high fidelity. You're restricted, terribly, because many speaker systems send the high frequencies out in a narrow cone.

The cone doesn't reach the corners of the room, and consequently your seating position is ruled by where the cone of high frequency sound can reach.

What the acoustic lenses of the Coral Stage Series do is to open out the high frequency cone so the full quality can reach you wherever you're sitting. It makes it a lot easier to entertain, and you know that so long as the ears are up to it, everybody in the room can hear true stereophony, or even quadrophony, as it was meant to sound.

Take the Coral Stage 7, for instance. It can give you frequency response from 25-20,000 Hz. It can give you a clear, undistorted bass from a 12" (305 mm) hollow formed cone made of specially sensitive chemical fibre pulp. There's a 5" (127 mm) mid-range speaker, and to give you all the elusive high frequencies, a 3½" (89 mm) tweeter and 2" (51 mm) super tweeter.



You notice we've removed the speaker grille.


Look closely. Other speaker manufacturers fall short of this kind of workmanship. The grille's a fixture, so they don't worry too much about a poorly-finished baffle, ugly screws or bits of insulation poking round the speakers.

Coral worry. With us it's a point of honour to finish your speakers as though you fully intended to play them exposed, like this. We've even made the grille removable, to give you the opportunity.

Throughout the Stage Series, the woofer is set into a polished walnut baffle, flat on both sides, to eliminate acoustic bounce. The acoustic lenses on mid-range, tweeter and super tweeters stand proud of a toning fabric panel.

And the workmanship continues, beyond what you can see, ensuring that the enclosure is completely airtight, to ensure low-frequency damping and minimal vibration distortion, even under high input.

If you think that all this is gilding the lily, look at it from our point of view. We're new here. We know it doesn't matter to you that we're the world's second biggest manufacturer of loudspeakers. Or that we're getting ready to offer one of the most comprehensive ranges of high fidelity speakers to be found in Australia. So we have to produce a better speaker than you're used to, both in appearance and performance.

With the Coral Stage Series of loud-speakers, we've done it. **CORAL** 

**Sole Australian Distributors: General Accessories**

153 Sturt St. South Melbourne, Vic. 443 Concord Rd. Rhodes, NSW. 81-97 Flinders St. Adelaide, S.A.  
50-54 Lt Edward St. Brisbane, Q'ld. 46 Milligan St. Perth, W.A. Cnr Ingham Rd. & Echlin St. Townsville, Q'ld.  
& Homecrafts, 199 Collins St., Hobart, Tas.

RH518



# Select Sansui stereo amplifiers for...

Superior design  
Superb engineering  
Sparkling performance



When you're considering the purchase of a complete new stereo system, the control amplifier is the key to the whole program. So it's worthy of detailed analysis.

There are six audibly superior control amplifiers in the Sansui range . . . from 30 watts RMS to 100 watts RMS. All feature *all-silicon* transistor design — and distortion is considerably less with Sansui control amplifiers, as output stages are semi-complementary Darlington designs without input or output transformers. Transformers have always caused some distortion problems in amplifier design — but not with Sansui!

The startling difference you will notice with any Sansui stereo amplifier is the *tonal*

quality and the obvious *dynamic range*. In every price bracket your new Sansui amplifier sounds like a much more expensive unit. These are not idle words. In the review of the least expensive Sansui amplifier, the AU-101, a leading Australian journal said . . . "*... few amplifiers, regardless of price, give an overall test result as good as this*". Another review said . . . "*... better than most other amplifiers at twice the price*".

With those comments made about the AU-101 (recommended price \$149) can you imagine how effective the other models in the Sansui range are? With more power and, let's face it, higher price tags?

Let's look at the complete Sansui stereo amplifier range:



MODEL	POWER RATING at 8 ohms.	FREQUENCY RESPONSE	REC. PRICE
AU-101	30 watts RMS	20-60,000 Hz. $\pm$ 2 dB.	\$149
AU-505	50 watts RMS	20-60,000 Hz. $\pm$ 2 dB.	\$199
AU-555A	50 watts RMS	20-40,000 Hz. $\pm$ 1 dB.	\$237
AU-666	70 watts RMS	10-40,000 Hz. $\pm$ 1 dB.	\$325
AU-888	90 watts RMS	10-70,000 Hz. $\pm$ 1 dB.	\$403
AU-999	100 watts RMS	5-100,000 Hz. $\pm$ 1 dB.	\$460

**IMPORTANT:** All prices are recommended prices only. The actual cost can well be less — as trade-in valuations can make a world of difference. See your Bleakley Gray franchised dealer!

Bleakley Gray Corporation Pty. Limited,  
28 Elizabeth Street, Melbourne, 3000.

Please send me complete details about the Sansui amplifier Model .....  
and the name of my nearest Bleakley Gray dealer.

NAME .....

ADDRESS .....

POSTCODE .....

**Sansui**

Sansui Distributors: Australia, excluding W.A.:

## Bleakley Gray Corporation Pty. Limited.




Head Office: 28 Elizabeth St., Melbourne, Vic. Tel. 63 8101\*.  
Telex 31904; Sydney Office: 177 Salisbury Rd., Camperdown,  
N.S.W. Tel. 519 5555\*; Canberra Office: 25 Molonglo Mall,  
Fyshwick, A.C.T. Tel. 95 2144\*; Adelaide Office: 301 South  
Terrace, Adelaide, S.A. Tel. 23 6219; Brisbane Office: 3 Prospect  
St., Bowen Hills, Qld. Tel. 52 7333; Perth Office: 27 Oxford St.,  
Leederville, W.A. Tel. 81 4988. **INTERSTATE REPRESENTATIVES:**  
N.T.: Piltzner's Music House, Smith Street, Darwin. Tel. 3601.  
Tas.: K. W. McCulloch Pty. Ltd., 57 George Street, Launceston.  
Tel. 2 5322.

### W.A. DISTRIBUTORS:

Atkins Carlyle Limited, 1-9 Milligan St., Perth, 6000. Tel. 22 0191.

Sansui equipment is manufactured by:— Sansui Electric Co. Ltd., 14-1, 2-chome,  
Izumi, Suginami-Ku, Tokyo, Japan.





# VARIETY FARE

REVIEWS OF OTHER RECORDINGS

## Devotional Records

**THIS IS THE DAY.** The Cameron Family. Stereo, Shiloh SP-373A. (From Shiloh Productions, PO Box 379, Hurstville, NSW 2220. Price \$5.95 plus 40c postage and pack).

Although previously not known to me, the Cameron Family comprising father, mother and three daughters have travelled extensively spreading the Gospel in word and song. New Zealand, Canada, Fiji, Mexico and the USA have been on their itinerary, over and above their native Australia.

Their sound is fairly typical of a talented family or Gospel team — sincere, spontaneous, with obvious platform appeal, but just lacking the ultimate polish and production of a commercial assembled team. But, having made the point for those who may tend to listen critically, let me simply say that as a Gospel team they are good.

A covering letter from Murray Cameron explains that, for the recording, his family had the backing of a chorus and John Harding's string quartet, with arrangements by Warren Judd. The recording was made, using the facilities of EMI, Sydney, including a 16-track recorder and a Dolby system. Certainly the sound quality is excellent.

Track titles: There Never Was A Day — As The Hart Panteth — It's Jesus, He's Coming For Me — There's A Sweet, Sweet Spirit — Do You Really Care? — That's All I Need — Amazing Grace — Somebody Bigger Than You And I — One Thing Have I Desired — Therefore Being Justified — Lovest Thou Me? — I Wish We'd All Been Ready.

Those who have heard the Cameron Family will certainly be interested to learn of the release of this album, as may many others. (W.N.W.)

★ ★ ★

**SUNSHINE DAY.** The McCrary. Light LS-5605-LP. (From Sacred Productions Aust, 181 Clarence St, Sydney and other capitals).

McCrary is the family name of twelve negro brothers and sisters from Ohio. Five of them — three brothers and two sisters — are associated in this talented family Gospel group. Backed by unnamed rock instrumentalists, they present a program mainly of their own compositions:

Sunshine Day — I Never Was So Happy — Get Yourself Together — Today Is The Tomorrow — He Touched Me — Jesus People — Pray — You're Not The Only One — Your Life's At Hand — Let It Start With You.

Based on the rock idiom, with obvious and expected overtones of negro Gospel, the McCrary sound will appeal mainly to those with modern tastes or an ear for jazz and rock — the more so because the emphasis is much more on the sound than the diction.

But, if you do buy, you'll not be disappointed in the technical quality of the sound. (W.N.W.)

★ ★ ★

**DAVE PETER'S HERITAGE.** Stereo, Medallion MS-7301. (From S. John Bacon Publishing Co, 119 Burwood Rd, Burwood 3125. \$3.95.)

To judge by the picture, Dave Peter's group consists of three girls and three fellows, whose Gospel message is delivered in a gentle rock style that should appeal to the young without upsetting the oldies.

Two or three of their numbers are adaptations of traditional hymns but the rest will probably be new to you: Back Where I Started — I Need Thee Every Hour — Love Is The Way — Hello God — Shout For Joy — My Jesus I Love You — More About Jesus — Love Is Pure — Benediction.

I gather from the jacket note that hymns used by Dave Peters are available from the publishers of the record: Medallion Music Corporation.

The production is smooth and the sound quality from this American album is very clean. If you want a Gospel album that combines modern sound with old-fashioned restraint, this one is safe buying. (W.N.W.)

## Instrumental, Vocal and Humour

**PROKOFIEV.** Classical Symphony in D, Op 25. **TCHAIKOWSKY.** Serenade in C for Strings, Op 48. Vanguard Quadraphonic VSQ 30016.

Prokofiev's Classical Symphony is thought by many to be a musical joke but to treat it as such is to give it poor justice. Rather it should be listened to as a clever work full of logic and charm. The young listener, reared on some of the more enterprising pop music should appreciate it well.

Tchaikowsky's Serenade in C for Strings is a cross between a symphony and a ballet. It has a symphonic form but the famed ballet director George Balanchine has created a successful ballet to the music entitled simply "Serenade." Either way, it

is a delightful piece of music.

Featured orchestra is the English Chamber Orchestra which has earned a very high reputation under the direction of Daniel Barenboim. On this album they are conducted by Johannes Somary and they perform beautifully throughout.

Sound quality is excellent although I did not listen to the disc through a four-channel set-up with SQ decoder. Buy it for the music. (L.D.S.)

★ ★ ★

**NEW YEAR IN VIENNA.** The Vienna Philharmonic Orchestra, conducted by Willi Boskowsky. Stereo, Decca SXLA 6572.

The New Year's Eve concerts entirely devoted to Viennese music conducted by Willi Boskowsky are now a tradition in Vienna, and recordings of such events are issued annually. However, the sleeve carries the information that the recording was taken in the Sofiensaal, Vienna in April 1972, which makes the title of this disc rather pointless. Apart from this small quibble, I can recommend this delightful pot pourri of light-hearted Viennese music with considerable enthusiasm to those for a taste with this line of music. There is no finer combination in the world for this music than the Vienna Philharmonic and Boskowsky.

The program includes such perennial favourites as the Morning Papers Waltz — Thunder & Lightning Polka — Explosions Polka — Persian March (all by Johann Strauss II); Gold and Silver Waltz (Lehar); The Beautiful Galatea Overture (Suppe). Other items by Strauss are included, as well as some by Josef Strauss and less prominent composers. Sound and stereo are first rate. (H.A.T.)

★ ★ ★

**ALFRED BRENDEL PLAYS ...** Piano music of Beethoven, Schubert, Liszt, Balakirev. Alfred Brendel, piano. Stereo, Decca "World of the Great Classics" series SPA.249.

Alfred Brendel is still relatively young (42 years old) and the fact that some tracks in this selection are "electronically reprocessed for stereo" indicates the already impressive length of his recording career. The program comprises — By Beethoven: Pathetique Sonata — Bagatelle No 1 in G minor, op 119 — Six Variations on Turkish March from "Ruins of Athens" — Fur Elise. By Schubert: Impromptus No 2 in E flat and No 3 in G flat, op 90 — Moment Musical No 3. By Liszt: Hungarian Rhapsody No 11 in A minor — Paganini Etude No 3 in A flat minor. By Balakirev: Islamey (Oriental Fantasy).

Undoubtedly, Brendel has a most impressive technique, which is best seen in the more brilliant passages in the Schubert, Liszt, and above all the Balakirev, works on side 2. However, I could find little to admire in his Beethoven playing on side one. The opening passage of the "Pathetique", is marked "Grave" but I hardly feel Beethoven intended it to sound as heavy and dull as here. The Andante Cantabile is thrown away as a worthless trifle (a common fault with many pianists, probably because it has relatively few technical difficulties) and the concluding Rondo is lacking in the sparkle and dash one expects to find. The remaining items by Beethoven are student pieces and are played as such,

Reviews in this section are by Neville Williams (W.N.W.), Harry Tyrer (H.A.T.), Leo Simpson (L.D.S.), Gil Wahlquist (G.W.), and Norman Marks (N.J.M.).



# FREE!



with your subscription to

## walkabout

Sir William Dobell's "Boy on the Beach" — regarded as the finest work in the late artist's estate — is faithfully reproduced in full colour. It can be yours at no extra cost when you subscribe to Walkabout.

Walkabout: the magazine of Australia — where our top writers and photographers meet each month to explore the varied moods of our continent, be they the old world charms of Tasmania, or the barren oppressiveness of the Simpson Desert or even the colourful frivolities of our coastal resorts.

Each month, a journey across a vast continent, probing its mysteries, meeting its people, exploring their customs and traditions . . . Why not come along?

## walkabout

A year's subscription of 12 issues for someone in Australia or Papua New Guinea costs \$A6.50 (postage free); for someone overseas it costs \$A8 (bank charges included). Your Dobell print is sent post free with your first issue of Walkabout.

TO WALKABOUT, SUBSCRIPTION DEPT., SUNGRAVURE PTY LTD, PO Box 139, Beaconsfield, NSW 2015.

Please send one year's WALKABOUT to

NAME .....

ADDRESS .....

STATE ..... Postcode .....

COUNTRY .....

I enclose \$..... (cheque, money order or postal order — cross out whichever is not applicable). Please make payable to WALKABOUT.

### VARIETY FARE

without any noticeable attempt at serious interpretation. As mentioned above, the music by other composers on side 2 is much more enjoyable. The disc has clean but dated sound, and the virtually unnoticeable stereo spread common for solo performances. (H.A.T.)

★ ★ ★

**KARAJAN EXPRESS — VIENNA.** Music of Mozart, Schubert, Beethoven, Johann Strauss I & II, The Berlin Philharmonic Orchestra, conducted by Herbert von Karajan. Stereo, DGG 2727 006 two disc set.

**KARAJAN EXPRESS — PRAGUE.** Music of Dvorak — Smetana. Performers as above. Stereo, DGG 2725 002, two disc set.

Here are two releases in a series in which Herbert von Karajan conducts music associated with various European cities and countries. Beautifully packaged in glossy folding sleeves, they are certain to attract large numbers of buyers, particularly those who put their faith in the DGG company's reputation for a high quality product, and in von Karajan's reputation as an outstanding conductor. The special price of \$7.96 for the two disc sets should be a further attraction. And the Berlin Philharmonic can certainly be rated as one of the world's great orchestras. What more could you ask? Here, then, is what each set contains:

**VIENNA:** Emperor and Blue Danube Waltzes (J. Strauss II) — Radetzky March (J. Strauss I) — Divertimento No 2 (Mozart) — Serenade No 6 (Mozart) — Symphony No 8, "Unfinished" (Schubert) — Symphony No 8 (Beethoven). Most potential buyers will presumably be familiar with these very well known works, although they may know the Mozart Serenade better by the title "Serenata Notturna."

**PRAGUE:** Vysehrad and The Moldau, from "My Country" (Smetana) — Five Slovanic Dances (Dvorak) — Symphony No 9 "From the New World" (Dvorak).

I suppose learned musicologists will continue to find fault with some aspects of von Karajan's performances of all the works listed above, but I thoroughly enjoyed every moment. All sections of the Berlin orchestra are admirable, and I doubt whether any other orchestra in the world would surpass their playing of Beethoven. If the titles are on your list of requested music, buy with confidence.

Also available in this series:

**FRANCE:** 2725 004. Symphonie Fantastique (Berlioz) — Copeland Ballet Suite (Delibes) — La Mer (Debussy).

**RUSSIA.** 2725 005. Pictures at an Exhibition (Moussorgsky) — 1812 Overture (Tchaikowsky) — Symphony No 4 (Tchaikowsky).

**Italy:** 2725 003. Cavalleria Rusticana, highlights (Mascagni) — I Pagliaci, highlights (Leoncavallo) — Sonatas for Strings Nos 1 and 6 (Rossini) — Intermezzos from La Traviata (Verdi), Adriana Lecouvreur (Cilea), Suor Angelica (Puccini), I Pagliaci (Leoncavallo), Feodora (Giordano) and Manon Lescaut (Puccini) (H.A.T.)

★ ★ ★

**UNFINISHED SYMPHONY** with Rosamunde and Marche Militaire — Schubert. The Vienna Philharmonic Orchestra with various conductors. Stereo, Decca SPA 225.

The Viennese orchestras are always at their best with Schubert and there is some fine playing in this disc released on Decca's "World of the Great Classics" (\$2.99) series. I feel it is unlikely that there is a better performance of the symphony on a budget priced disc. The depths of feeling reached by the orchestra under Carl Schuricht cannot fail to move a sensitive listener. Unfortunately, a particularly inappropriate choice of a fill for side 1 moves one abruptly from the deep tragedy of the symphony's slow movement directly to the toy soldier parade ground of the "Marche Militaire."

Side 2 is taken up by the charming ballet music from "Rosamunde," where that fine conductor, the late Pierre Monteux, gives a splendidly rhythmic performance that never lets us forget that this is music for dancing.

Unfortunately the sound quality is below par. Distortion is particularly noticeable on side 2. (H.A.T.)

★ ★ ★

**SOUSA MARCHES.** Boston Pops Orchestra conducted by Arthur Fiedler. Stereo, RCA Camden CAS-2593.

The jacket notes explain that each concert of the Boston Pops conducted by Arthur Fiedler customarily begins with a march —



perhaps to provide a stirring opening, perhaps to give the audience time to settle. On this album are eight of the marches that have formed part of this custom:

El Capitan — High School Cadets — The Thunderer — Semper Fideles — Washington Post — Stars And Stripes Forever — Boston Commandery — American Patrol.

The combination of so well known a conductor and orchestra must catch the eye at the Camden budget price, although some may prefer this kind of material from a band rather than an orchestra. Playing time is about 12 minutes per side and the sound quality is normal. (W.N.W.)

★ ★ ★

**ORGAN SYMPHONY** (Symphony No 3 in C Minor, Op 78), Saint Saens. City of Birmingham Symphony Orchestra conducted by Louis Fremaux. Christopher Tobinsson, organ. Columbia Studio 2 quadraphonic 04-TWO-404.

Composed in 1866 and dedicated to the memory of Franz Liszt, Saint Saens Symphony No 3 calls for a full orchestra, plus grand organ, grand piano, piccolo, cor anglais, bass clarinet, double-bassoon and tuba. It provides a sound texture which lends itself to exploitation by the quadraphonic medium.

Encoded per an SQ matrix, the sound is inevitably of the surround variety and one is torn between the urge to turn the rear channels down to achieve predominantly frontal sound and the alternative of leaving them at normal level and being, as it were, a part of the orchestra. I chose the latter course and simply enjoyed being surrounded by sound, sometimes gentle, sometimes massive, but always clean.

And clean it is, with excellent definition and not a whisper of surface noise.

For those not familiar with the music, the detailed jacket notes cover the composer, the symphony, the conductor and the orchestra. The organ dominates the cover picture but no other details are given. But, all in all, it adds up to a record that you will be glad to have in your collection. (W.N.W.)

★ ★ ★

**A CLASSICAL SHOWCASE.** Golden Hour presents, Alshire stereo GH804. Distributed in Australia by Radio Corporation Pty Ltd.

That recent television commercial showing a bird in flight and then fading to a shot of a climbing airliner has certainly done much to popularise "Morning Mood" from the Peer Gynt Suite. This is just one reason why this "Golden Hour" Presentation is sure to sell well. As the name implies, it lasts for just over an hour making it good value. The first half is devoted to tunes from the Peer Gynt suite, played by the Hamburg Staatsoper Orchestra.

Side Two features Dukas' "Sorcerer's Apprentice" and Ravel's "Bolero" played by the London Philharmonic Orchestra. Manuel de Falla's "Ritual Fire Dance" played by the Nord Deutsches Symphony Orchestra concludes the album. Sound quality throughout the album is very good and surface noise was low. Needless to say, the performances left little to be desired. (L.D.S.)

## ASTOR QUADRAPHONIC SAMPLER

**QUADRAPHONIC SAMPLER.** Astor Quad 4D Sound. QUAB-4001.

This is a sampler, rather than a demonstration disc, which means that the producers have not sought to put together a collection of way-out tracks. More than that, they have avoided a mix of highly dissimilar elements. The result is a collection of popular orchestral items from various sources and, as such, it adds up to very pleasant listening for those whose tastes run in that direction — and that probably means a major slice of the listening audience.

Here are the tracks, abbreviated to conserve space: Chirpy, Chirpy, Cheep (John McLeod orchestra) — Spinning Wheel (Dennis Lopez orchestra) — It's Too Late (Sounds Orchestral) — Waltz from Serenade For Strings (Victor Sylvester) — Danca Das Horas (Roger's Brazilian Brass) — Oh You Pretty Thing (City of Westminster Band) — Raindrops (Button Down Brass) — She's Leaving Home (London Pops) — This Guy's In Love (David Snell) — Fantasia on Greensleeves (Geoffrey Brand orchestra) — Never On Sunday (Cyril Stapleton) — A House Is Not A Home (Tony Hatch).

Recorded to the Sansui QS format, the sound emerges with a fine surround quality, appropriate for this kind of material. (W.N.W.)

introducing

# B&W DM4

## MINIATURE MONITOR SPEAKER

*"... the DM4 is a high performance loudspeaker and certainly one which we can warmly recommend."*

See *Electronics Aust*, June 1973, page 99

ONLY 21"H x 10"D x 10"W = 1.2 cu. ft.



Throughout the world, both in the home and in the professional studio there is an established need for a small monitor loudspeaker designed and built to the highest possible standard.

We released the DM4 at the International Audio Fair October 1972 in the firm belief that the design aims have been achieved and from extensive comparison with other systems currently available we believe the DM4 may well out-perform competitive loudspeaker systems of three times the size and twice the price.

The success of the DM1 provided our design team with obvious enthusiasm to translate and extend the DM1 design and take advantage of new materials and improved design and measuring facilities which were not available some four years ago. To cite a single example, the mid-range harmonic distortion (overtone) on the prototype DM4s was so low that an additional laboratory instrument only introduced by Messrs Bruel & Kjaer some twelve months ago was purchased to finalise the design of the Bass/Mid-range unit. This instrument type 2010 costs some Two Thousand Pounds and was used to finally determine the contour of the cone on the DW200/4. Without these measuring facilities, production to the final standard would not have been possible.

The loudspeaker designer has but one goal and that is to produce a system which approaches closer than previous designs to recreating the original sound in the home or studio, and the design brief laid down for the DM4 set five areas of improvement which should be investigated.

- (1) Even greater mid-frequency linearity.
- (2) Twice the acoustical output for an equivalent distortion factor.
- (3) Three times the output from 30Hz to 60Hz provided by the DM1.
- (4) Increased sensitivity or, expressed in different terms, the requirement of a less powerful amplifier to give an equivalent volume of sound.
- (5) Increased power handling capacity to conform with higher powered amplifiers now in use.

**\$360 per pair with BMK**  
**Frequency graphs**

Available from **Convoy Techno Centre Cnr Plunkett & Maclean Sts, Sound Spectrum 33 Regents Arcade Adelaide, Arena Distributors 196 Adelaide Terrace Perth.**

**SOLE AUSTRALIAN AGENTS**

**Convoy International Pty Ltd**

Corner Plunkett & Maclean Sts, Woolloomooloo  
2011. SYDNEY Telephone (02) 357-2444



# AUDITEC AUSTRALIA PRESENTS....



A COMPLETE STEREO AMPLIFIER KIT  
BASED ON THE 001 AND 002 MK II  
PROFESSIONAL QUALITY AUDIO  
MODULES.

## Compare these specifications:

Maximum power output	per channel
(R.M.S.) into 8 ohms	25 watts
T.H.D. at rated output	0.1%
Bandwidth at 25 watts	20Hz - 50KHz $\pm$ 1dB
Bass and treble control	$\pm$ 17dB at 50 Hz and 15 KHz
Signal / noise, magnetic	better than 60 dB
auxiliary	better than 70 dB
Inputs, magnetic	4mV / 47K
ceramic / XTAL	150mV / 1M
auxiliary	500mV / 100K
Tuner	500mV / 100K

**AUDITEC AUSTRALIA**  
P.O. BOX 258,  
SPIT JUNCTION N.S.W. 2088  
Phones: 47 4166; 938 1405

**COMPLETE KIT AS ILLUSTRATED,**  
including black vinyl paint finished cover,  
anodised silk screened front panel and  
wide audio bandwidth tuner model 1005  
I.C.:

Price including sales tax \$191.25

**COMPLETE KIT WITHOUT TUNER,**  
and with front panel to suit: price including  
sales tax \$155.55. Without cover—deduct  
\$7.65 Add \$2.50 to cover freight costs

- ☐ Please send . . . amplifier kit.  
I enclose cheque / M.O. for \$ . . .
- ☐ Please send full details of amplifier kits.

NAME .....

ADDRESS .....

POSTCODE .....

EA 8 / 73

## VARIETY FARE

**THE LONDON BALALAIKA ENSEMBLE.**  
Stereo, World Record Club S / 5260.

I enjoyed this disc when it was first released here on the Deram label. It is a first class production in every way, featuring some polished playing by an accomplished body of performers. The program, consisting of those soulful Russian traditional melodies, has been very well recorded. The titles are: Pedlar's Dance — At the Gates — Remember, Remember — In the Garden — Beyond the Fast Running River — Little Apple — Russian Dance — Kalinka — There is More Than One Path — Brightly Shone the Silver Moon — Oh You My Snowball Tree — Under the Apple Tree — My Meadows — Oh, You the Night.

By using the full range of balalaika and domra instruments, a full bodied tone has been achieved. It is a wonderfully effective sound. (H.A.T.)

★ ★ ★

**THE WORLD OF ENGLAND.** Various artists and orchestras. Stereo, Decca SPA.190.

The appeal of this disc will probably be mainly to expatriot Englishmen with nostalgic memories of their homeland, featuring as it does such titles as "O Peaceful England" and "The English Rose" from Edward German's operetta "Merrie England", "Fantasie on Green-sleeves" (Vaughan Williams); and "Pomp and Circumstance March No. 1" (Elgar). As a lead in to the music there is the famous passage from Shakespeare's "Richard II" beginning "This Royal Throne of Kings" followed by a suitably patriotic burst of music in an excerpt from Walton's "Orb and Sceptre" coronation march.

Also included are: Shepherd's Dance from "Henry VIII" (German) — Pastoral Dance from "Nell Gwynn" (German) — Scarborough Fair — Early One Morning — The Floral Dance — Oranges and Lemons — Knightsbridge March (Coates) — Strawberry Fair — Eton Boating Song — Sussex-by-the-Sea.

Apart from the "Boating Song" and "Scarborough Fair," which is beautifully performed by folk singer Marianne Faithfull, the music is presented by orchestras and brass bands. The music is all very pleasant and well performed, but most of the tracks are fairly ancient (some are reprocessed stereo), so that poor quality sound will disappoint those who demand hi-fi as a pre-requisite to musical enjoyment. (H.A.T.)

★ ★ ★

**LATIN HOLIDAY.** 101 Strings Orchestra conducted by Les Baxter. Quadraphonic QS. Astor Gold QS-17.

With Les Baxter as orchestrator and conductor, the 101 Strings orchestra takes on a new role as background to a variety of percussion and wind-instruments appropriate to the title "Latin Holiday." Through the four channel medium, there's plenty going on, all of it recorded very cleanly. The eleven tracks include:

Que Mango — Tropicando — On A Warm Night — Flight In The Andes — Jungle Montuno — Boca Chica — Felicia My Love — Come Back To Paradise — Night In Buenos Aires — Morning On The Meadow.



## How do we do it, Ladies & Gentlemen?

Today, Armstrong presents the new Series 600.

a little project we have been working on for the past 3 years.

We believe we have produced one of the very best ranges of Amplifiers, Tuners and Receivers in the world. And we mean "in the world."

And, just to underline, clarify and nail it down once and for all, and we mean at **ANY PRICE.**

Armstrong Model 621 40 watts RMS per channel, you can expect results that will make most owners of other stereo equipment positively Greengage. Green with envy.

And yourself as happy as any Hi Fi stereo enthusiast can rightfully expect to be.

**We can tell you the truth.**

**It's a knack Or a gift.**

**To achieve such results — what ever it is, it's definitely an Armstrong and nothing else.**

**SPECIFICATION: AMPLIFIER POWER OUTPUT:** 40 watts per channel 8 ohms, at less than 0.08 pc harmonic distortion. **FREQUENCY RESPONSE** 25 Hz-25 kHz + 1 dB. **HUM AND NOISE** unweighted, all inputs better than -65 dB. **DAMPING FACTOR** into 8 ohms better than 50. **FM TUNER FM SENSITIVITY** IHF 75 ohms 1.5 mV. **FULL LIMITING** 1 mV. **DISTORTION** 1 kHz, 40kHz deviation less than 0.2pc **SIGNAL / NOISE RATIO** 100 mV. 65dB. **SELECTIVITY** 56 dB. **CAPTURE RATIO** IH F 1.75dB. **AM TUNER COVERAGE** 145-1625 kHz LW & MW continuous tuning. **SENSITIVITY FERRITE AERIAL** IHF 250mV / metre, external aerial IHF 25mV. **SELECTIVITY** 60 dB.

**ARMSTRONG**  Made in England

Sole agents for Australia

**RECORDED MUSIC SALON**

11 Collins Street  
Melbourne 3000.

**TRUE FIDELITY**

C. Pinczewski  
Tel 63 6257



As the notes suggest, it's a characteristic Les Baxter mix of European, African and Latin American, easy enough on the ear but with melodic themes that happen rather than flow. Perhaps you had better sample a track or two, in case there's another in the quad series that you'd prefer. (W.N.W.)

★ ★ ★  
ALEXEYEV BALALAIKA ENSEMBLE.  
Stereo, Chapter 1 (EMI) CHS. 810.

If you bought and enjoyed the London Balalaika Ensemble which I reviewed on its original release a few years ago, and again recently when reissued by World Record Club, you will welcome the new release as a very good companion disc. It has two well known standards in "Song of the Volga Boatmen" and "Two Guitars", but apart from these the title will probably be unfamiliar. Two pieces were composed by members of the Ensemble ("Atalanta", based on a story from Greek mythology, and "Land of My Sixteenth Year," concerning the musings of an old peasant dreaming of his youth); and another track is an arrangement of a love song by Shostakovich.

The remainder are typical traditional peasant tunes arranged by the group.

The Alexeyev Ensemble are a fully professional body of musicians, with wide performing experience, and one does not have to be an expert to appreciate the high standard of their playing. Only instruments of the balalaika and domra families are used, but these range from the high pitched prima to the sombre double bass, and produce a satisfyingly full-bodied sound. All this adds up to a most satisfying disc which should please anybody with a taste for traditional music and instruments. The sound quality is quite satisfactory. (H.A.T.)

★ ★ ★  
THE BEST OF LAURINDO ALMAIDA.  
Stereo, Capitol SENC.9976.

This is a collection of tracks from previously issued Almeida discs, some of them more than 10 years old: Moonlight Sonata, first movement (Beethoven) — Arioso (Bach) — Claire de Lune (Debussy) — Schon Rosmarin (Kreisler) — Pavane for a Dead Princess (Ravel) — Farucca (Falla) — Preludes Nos 2, 5, 8, 10, 11, 12 (Ponce) — Fandanguillo (Turina) — Tango Espanol (Albeniz). Technically, Almeida cannot equal the leading guitarists now recording, but he is certainly capable of providing a pleasurable performance, and no doubt his many admirers will find plenty to enjoy in this selection. The age of the recordings shows in the sound quality. So don't expect the ultimate in hi-fi. However, the sound is clean enough and should satisfy all but the most critical. (H.A.T.)

★ ★ ★  
SOUSA MARCHES. Men O' Brass. Conducted by Harry Mortimer. Studio 2 stereo TWO 385.

There are several facets to this album which add interest to a fine presentation of Sousa marches. The first is that "Men O' Brass" are joined by the City of Coventry Band who have as musical director Albert Chappell. They add to the Fairey Band and the Foden's Band to form a mighty ensemble.

Apart from the two celebrated marches "King Cotton" and "El Capitan" and a clever medley called "Semper Sousa", the marches on this album have never been

## Whistle while you work

24 GREATEST POLKAS. Lawrence Welk & Myron Floren. Stereo, Interfusion (Festival) IFTL-267/8. Two-record set \$7.95.

This is an excellent record to do household chores by — I know, because I was just so engaged while to four sides were playing! For deliberate listening, one might come up with a different verdict, because the format and tempo remain virtually unchanged from beginning to end. But, as background, to which you don't expect to listen deliberately, except when a tune grabs your attention, it's a happy workaday sound.

Without attempting to list the twenty-four tunes, they include the inevitable Beer Barrel Polka, Tavern in The Town, Kit Kat, Champagne and so on.

The quality and surface is good. (W.N.W.)

recorded by Brass Bands before. They are all excellent and Sousa fans are well advised to listen and buy. Sound quality is outstanding.

The nine remaining tracks are: The Picador March — The Corcoran Cadets — The Directorate March — Fairest Of The Fair — Beau Ideal — The Freelance March — National Fencibles — Our Flirtations — The Occidental March. (L.D.S.)

★ ★ ★  
CLASSICS GO LATIN. Brian Fahey and his Orchestra. Studio 2 Stereo (EMI) TWO 392.

The title is sufficiently indicative of the contents. The collection of classical tunes is presented in the typical modern style, with

Latin American rhythm, and comprises: Ritual Fire Dance (Falla) — Air on the G String (Bach) — Scherzo from Midsummer Night's Dream (Mendelssohn) — None But the Weary Heart (Tchaikowsky) — Ave Verum Corpus (Mozart) — Toreador's Song from "Carmen" (Bizet) — Overture to "Marriage of Figaro" (Mozart) — Solveig's Song (Grieg) — Gavotte (Popper) — Themes from "Polovtsian Dances" (Borodin) — Ave Maria (Bach-Gounod) — Themes from "Capriccio Italien" (Tchaikowsky). There have been many discs of this type, but the high standard of musicianship and the clever arrangements lifts this one above the average, and the high quality sound adds to its attractions. (H.A.T.)

★ ★ ★  
MORNING HAS BROKEN. Tony Fenelon playing the Conn Theatre Organ. Stereo, Festival FL34814.

Melbourne organist Tony Fenelon continues to add steadily to his growing list of long playing albums — and to his standing as a popular organist. The instrument used for this one is the Conn 650 electronic theatre model, an instrument which can very closely simulate the sounds of its pipe counterpart. In this recording the instrument tends to lack some of the sparkle that it has "in the flesh", possibly because some of the tracks, at least, have been re-recorded to include additional parts played on piano by the same artist.

The twelve tracks comprise: Yellow Bird — Sentimental Journey — Early In The Morning — Skye Boat Song — Sweet Sue — That's Entertainment — Anna — If I Ruled The World — Windmills Of Your Mind — Les Bicyclettes De Belsize — Black Bay Shuffle — Morning Has Broken.

## ACOS REPLACEMENT LONG LIFE CARTRIDGES

Acos 90 Series — a family of pick-up cartridges covering all the main types needed today, each fitted with Diamond Stylus at no extra cost.

GP91-1 MONO CRYSTAL Stereo Compatible \$6.95  
GP91-2 HIGH OUTPUT MONO CRYSTAL

Stereo Compatible ..... \$6.95

GP92 MONO CERAMIC Stereo Compatible \$7.55


GP93 STEREO CRYSTAL ..... \$8.55

GP94-1 STEREO CERAMIC ..... \$8.95

GP94-5 STEREO CERAMIC FOR TRANSISTOR

AMPLIFIERS ..... \$9.95

GP104 MINI STEREO CERAMIC ..... \$9.95



All cartridges fitted with DIAMOND STYLUS at no extra cost



PRICE \$5.55

### Microphone Inserts

#### Mic 43-3

A Rochelle Salt (crystal) microphone insert in a die-cast case with expanded aluminium grille.

Dimensions ..... 43-66mm diameter

8-73mm deep

Output at 1KHz ..... 52dB ref. 1V/dyne/cm

Response ..... 30-7,000Hz

Capacitance ..... 800 picofarads

Ideal Load ..... 5 megohms

TECHNICAL DATA SHEETS SENT FREE ON REQUEST

Sole Australian Agents

AMPLION (A'ASIA) PTY. LTD.

31 Majors Bay Rd., Concord, Sydney, NSW. Phone 73 1227



# BIG NAME

**SMALL PRICE (UNDER \$100)  
AND TOP QUALITY TOO!**



## ROTEL® 210

Australian Hi-Fi said "It is a delight to report on the Rotel 210 which impressed us no end for quality and performance. It is stylish, well-constructed and performs more than adequately".

The 210 is a solid state 20 transistor, 30 watt pre-main amplifier with tape recorder output. 8 watts

RMS channel at 8 ohms. Harmonic distortion less than 0.5% at rated output. As "Australian Hi-Fi" said, "Rotel 210 gives an effortless clean sound". If you want to hear performance regardless of figures, hear the best value for money amplifier ever to hit the Australian market —Rotel 210!

Available from:

N.S.W.	M & G Hoskins Pty. Ltd., 37 Castle St., Blakehurst 2221 Telephone: 54 1464
Q'LD	Stereo Supplies, 95 Turbot St., Brisbane 4000 Telephone: 21 3623
S.A.	Challenge Hi-Fi Stereo, 6 Gays Arcade, Adelaide 5000 Telephone: 23 2203
TAS	Audio Services, 72 Wilson St., Burnie 7320 Telephone: 31 2300
VIC	Encel Electronics Pty. Ltd., 431 Bridge Rd., Richmond 3121 Telephone: 42 3762
W.A.	Albert TV & Hi-Fi, 282 Hay St., Perth 6000 Telephone: 21 5004

Sole Australian distributors:

**INTERDYN**

INTERNATIONAL DYNAMICS (AGENCIES) PTY. LTD.,  
P.O. BOX 205, CHELTENHAM, VIC. 3192



## VARIETY FARE

On both organ and piano, Tony Fenelon exhibits all the skill and musicianship that we have come to expect of him and the album makes for pleasantly varied listening. It's just a pity that the recording itself doesn't have a trifle more presence and "sparkle". (W.N.W.)

★ ★ ★  
**MUSIC FROM WALT DISNEY'S FANTASIA.** Various orchestras and conductors. Decca Phase 4 Stereo PFS 4260.

This is not music from the sound track of the film as the title might be misconstrued. The only close connection with the sound-track is the performance by the London Symphony Orchestra under Leopold Stokowski, of the edited version of Moussorgsky's "Night on the Bare Mountain" which Stokowski prepared for the film. The other tracks are: Toccata and Fugue in D minor, presented in very florid orchestral dress by Camarata and the Kingsway Symphony Orchestra; Sorcerer's Apprentice, (Dukas) played by the London Philharmonic under Bernard Herrman; Dance of the Hours (Ponchielli) presented by Stanley Black and the London Festival Orchestra.

If you are looking for a souvenir disc of the film, the excellence of the Phase 4 recording adds to the musical attractions of this one. (H.A.T.)

★ ★ ★  
**JAMES BOND.** Various orchestras and artists. United Artist stereo UAL 387/8. 2-record set \$7.95.

Some time ago I reviewed an album of James Bond movie themes and found it a skull-numbing experience. Having survived it, I was confronted with this 2-record set which is great for pounding obstinate spies into submission. Some of the tracks taken in isolation (which I suppose is where they should be taken) are okay but four album sides are more than enough. If you are keen on persecution by high-fidelity, the sound quality is fine. There seems little point in listing the tracks. (L.D.S.)

★ ★ ★  
**THE BENNY GOODMAN STORY, Vol 1 & 2** MCA Enhanced for Stereo MAPS 1009, MAPS 1261 Astor release.

These two records are not sold together as an album but, as they are from the same film sound track of 'The Benny Goodman Story', I have reviewed them together. The original release dates back to the film some years ago; I presume that the re-release is to coincide with the recent Australian appearance of Goodman and his quintet. If you missed the live performance, you probably saw the ABC televised recording and enjoyed it as much as I did. Volume 1 has: Let's dance — Down South — Camp meeting — King Porter Stomp — It's Been so long — Roll 'em — Bugle Call Rag — Don't be that way — You turned the tables on me — Goody Goody — Slipped Disc — Stomping at the Savoy — One O'clock Jump.

Volume 2 carries on with: Memories of you — China Boy — Moon Glow — Avalon — And the Angels Sing — Jersey Bounce — Sometimes I'm happy — Shine — Sing Sing Sing. Among the personnel are some of the old greats such as Lionel Hampton, Gene Krupa, Harry James, and Teddy Wilson.

These are two records I'll certainly keep a place for in my collection. (N.J.M.)

★ ★ ★  
**WOODY HERMAN, GOLDEN FAVOURITES.** MCA MAPS 1070. Enhanced for Stereo. Astor release.

Most of the twelve tracks on this disc are tunes associated with Woody Herman's Orchestra of the thirties and forties and as such help to recapture some of the listening pleasure of those days. His signature tune, The Woodchopper's Ball, heads the list with other old favourites such as: The Golden Wedding — Yardbird Shuffle — Down Under — Blue Flame — Irresistible You — Chip's Boogie Woogie — Las Chiapanecas. I presume the record has been reworked from original masters. If this is so, they have done an excellent job, although the "Stereo enhancement" gives more of a two channel effect than one usually likes. If you like the music of the era give this one an audition, I think you'll buy it. (N.J.M.)

★ ★ ★  
**TWO FACED BACH.** Miguel Ramos at the Hammond organ, with Orchestra. Hispavox stereo HVL 34789. Festival.

Purists tend to throw up their hands in horror at the modernisation of old masters such as Bach, sometimes with justification. In fact, this disc serves to point up the very strong rhythmic base of much of his music and, as such, I found the record very enjoyable. The first item is "THE" Toccata and Fugue, followed by a group of short suites that are pleasantly familiar, even in an uptempo rendition such as this. The quality is superb. (N.J.M.)

★ ★ ★  
**TEQUILA COCKTAIL.** Pepe Jaramillo and his Latin American Rhythm. Stereo Columbia SOEX 9781.

Pepe Jaramillo's very pleasant brand of piano playing backed by Latin American rhythm will be familiar to most buyers of discs of popular music. One of my favourite discs of this type is his "Latin Piano in Japan" which I invariably include in discs selected as background music for parties and other social occasions. This latest disc is going to complicate the matter of choice as it will be joining the short list of party discs, despite some deficiencies in sound quality, simply because it is such very pleasant listening.

The titles are: Tequila Cocktail — Good Morning Starshine — I'll Never Fall in Love Again — The Shadow of Your Smile — My Way — The Fool on the Hill — Corazon Contento — Adios Amor — Loneliness — For Once in My Life — Yesterday I Heard the Rain — The Look of Love. Presumably the occasional distortion noticeable (which seems to affect only the piano) was caused by overloading somewhere in the recording chain. Despite this, the disc can be regarded as good buying at its \$2.99 price. (H.A.T.)

★ ★ ★  
**DREAMLAND FILM MELODIES.** Nils Tibor at the Hammond organ. Stereo. Ace Of Clubs series 299 SCLA-7048.

By coincidence, I listened to this recording next in line to Tony Back's Hammond, reviewed elsewhere. The contrast could not be greater and, if my description of Tony Back's music put you off, then the chances are that Nils Tibor will be your choice, particularly at the Ace of Clubs price. To be sure, Nils Tibor stays with conventional Hammond voicing but, against a restrained



## SPARE PARTS

For radios, taperecorders, cassette players, record players, amplifiers, etc. Available from stock for the following brands:—

— NEC —  
— DOKORDER —  
— MARLUX —  
— BIGSTON —  
— TOBISONIC —  
— PAROS —  
— TAKT —  
— TAYA —  
— LARK —  
— KENT —  
— TEPPAZ —  
— GLOBE —

Big range of AC & DC motors, cartridges & R/p heads.

Express repair service to all brands at the cheapest price.

**Tiger** ELECTRONICS PTY. LTD.

431 KENT STREET,  
SYDNEY. 2000.  
(Between Market & Druiett Streets)  
TELEPHONE: 29 4337



# Never before has this little noise accompanied this much music.

If you're sophisticated enough to be reading this magazine, you're probably familiar with the two main characteristics of cassette decks: hiss and nonlinear frequency response.

Which should make you thoroughly unfamiliar with the performance capabilities of our new HK-1000. As the charts indicate, it behaves more like reel-to-reel than a cassette deck:


Signal-to-noise (unweighted) is  $-58$  dB with Dolby and  $-70$  dB in the audible hiss level above  $4,000$  Hz. The frequency response curve is essentially flat from less than  $30$  to beyond  $15$  kHz,  $\pm 1.5$  dB, with CrO<sub>2</sub> tape. (This curve is due largely to the way we drive our heads. Instead of the conventional constant *voltage* drive to the head, the HK-1000 is designed for constant *current* drive. Many studio model reel-to-reel decks are designed the same way.)

Because of a new low in noise and a new wide in frequency, the HK-1000 brings you a new clarity in music.


Ours is the first cassette deck designed for maximum phase linearity. Square wave response is better than every other cassette deck and even some expensive reel-to-reel decks. And the better the square waves, the cleaner and more transparent the music.

Discriminating audiophiles will also appreciate the wide selection of controls to take control of. There are two "peak-reading" VU meters; automatic shut-off in all transport modes; separate controls for recording playback and microphone levels; a "memory" rewind feature that lets you key a selection to the exact start location; a Dolby test oscillator; both record and Dolby playback calibration adjustments on the top panel; and so on.

The HK-1000 is also designed so you can use it often



## Noise.



## Music.

closing the doors of expensive hand-built cars.  
For complete details and specs, write



Sole Australian Distributors & Importers,  
**JERVIS AUSTRALIA PTY. LTD.**  
P.O. Box 6, BROOKVALE. 939-2922.

**harman/kardon**  
*the music company*





## VARIETY FARE

background of rhythm, he plays a dozen tuneful melodies that are currently as much a part of the electronic organ repertoire as were certain chestnuts in the theatre pipe era: Love Story — Fascination — A Man And A Woman — More — True Love — Moulin Rouge — Moon River — Lara's Theme — This Is My Song — Never On A Sunday — Goldfinger — Born Free.

Stereo is used to advantage and there are enough effects and gymnastic touches to show that Nils Tibor has plenty of ability to draw upon. If, as a popular organ enthusiast, you want music for dining and relaxing, this should fill the role very nicely. (W.N.W.)

★ ★ ★  
**HAMMOND DANCE PARTY 2. Tony Back.**  
Interfusion Stereo (Festival) IFTL-34786.

If you should need any convincing, this new album will demonstrate the number of mod popular effects that can be extracted from the Hammond T-200 series organ, when teamed with a Sharma 5000 professional organ speaker and organist Tony Back. But be warned: Tony Back has no time for the usual organ imitative sound; his forte here is tempo, bass line, keyboard gymnastics, waa-waa effects and exploitation to the full of a rotating sound field loudspeaker system.

In line with the title, Tony Back locks most of it to percussion for dancing (mod style) but the title also suggests the alternative of "easy listening". If you do so listen, you'll find that the eleven tracks take in bits and pieces of 29 "golden melodies" such as: Born Free — Exodus — Aquarius — King Of The Road — Smile — Walk On — There'll Never Be Another You — Superstar — and so on.

If you like way-out Hammond, then Tony Back's your man. If you don't, then find something more relaxed to spend your money on! (W.N.W.)

★ ★ ★  
**JIM REEVES ON STAGE, With the Blue Boys.** RCA stereo LSP-4062.

Generally, live performances on record are flat, in my opinion. But this album of Jim Reeves demonstrates his stage personality so well that you can't help enjoying it. One realises why he was so popular apart from the fact that he was a very fine country and western singer — he had such a fresh, lively personality.

Side one has Jim acting the goat quite a lot in between short stints of singing. On side two he sings more. Both sides are enjoyable. Sound quality is very good.

Some of the songs sung by Jim are: The Blizzard — Am I Losing You — Bimbo — Stand At Your Window — Danny Boy — Tennessee Waltz — Guess Things Happen That Way. (L.D.S.)

★ ★ ★  
**PIETRO PERO AND HIS ROMANTIC PIANO.** Stereo, Astor SF 311. Three record boxed set.

The list of popular traditional melodies, evergreen light classics printed on the back of the box will attract a great many buyers, with such well-known tunes as Come Back to Sorrento — O Sole Mio — Cielito Lindo — La Paloma — Hymn to the Sun — Song of

India — Kashmiri Song — Fantasia Impromptu — Liebestraum — One Fine Day — Blue Danube — Tales of the Vienna Woods — Claire de Lune — Moonlight Sonata — The Swan, Schubert's Serenade . . . and so on, 30 tracks in all.

If this kind of material appeals to you and the special price tempts you, a word of warning before you rush out to buy the set. Pietro Pero's playing style is what may be called "modern interpretation", with rhythm percussion in support. Many people who like their music played straight will find little to enjoy in this treatment of their favourite melodies. Those who favour the "swinging" treatment will not be disappointed. Sound and stereo are of normal modern standard. (H.A.T.)

★ ★ ★  
**MANDOLIN SPECTACULAR.** Mandolin Ensemble, Stereo, Columbia (EMI) SOEX 9998.

This is another of the Japanese Toshiba recordings released here on EMI's \$2.99 Columbia label. As usual, the recording is technically first class, and the Japanese performers display a high degree of competence with western style instruments. What is unusual here is the selection of titles. Japanese record producers have tended to stick closely to standards and evergreens, so one would expect to find the well known Mandolin titles (O Sole Mio, Come Back to Sorrento, etc.) Instead one finds the following little known titles: Mandolin Congress (Bracco) — Nell' Oasi (Eliseo Mui) — Suite Marinara (Amadeo Amadei) — Gli Orazii ed i Carizir (D. Cimaroso) — Mazurka — Concerto (C. Munier) — Grenade Morisque (Matias M. Garcia) — Dante e Beatrice (C. Grazioni — Walter).

Unfamiliar music but tuneful enough to appeal at first hearing and having the kind of qualities which should have lasting appeal. (H.A.T.)

★ ★ ★  
**WHEN IRISH EYES ARE SMILING.** Bing Crosby, MCA stereo DL 78262. (Astor Gold Star series).

**A NOSTALGIC HOUR OF BING CROSBY.** MCA Gold stereo MAPS 6328.

A wave of nostalgia is sweeping the United States and Australia is getting some of the backwash. (Sorry about that.) But after all, we used to like Bing Crosby too. Why not go out and buy one of these albums as a memento? They are a lot of fun. The first disc is devoted to tunes with an Irish flavour while the second covers everything from "Blue Hawaii", "Mississippi Mud" and "White Christmas".

Sound quality is variable from good to lousy but most buyers won't worry about that as long as they can follow the words. The same can be said for the "re-processed" stereo — it is of no consequence. The second disc has more tracks but the first is more listenable. (L.D.S.)

★ ★ ★  
**THE LITTLE ANGELS.** Philips Stereo 6308 137.

On their recent Australian tour, the National Folk Ballet Of Korea charmed audiences with their artistry in song and dance and this Philips release is a pleasing souvenir of their visit. The sound quality varies somewhat. Possibly the record is a mixture of studio and live performance, and the presence of audience applause on some tracks could be a clue to this.



## SPEAKERS action packed sound

### 8 NEW LOUDSPEAKERS FROM THE BIGGEST GUITAR SPEAKER MANUFACTURER IN THE U.S.A.

**12" Economy Model 25 Watt R.M.S.,** 10 ounce magnet, 1" voice coil, 70-7000 Hz., C.T.S. patented ALUMINEX bobbin for maximum power dissipation. Recommended Retail Price \$21.

**12" 60 Watt R.M.S.,** 18 ounce magnet, 1 1/2" voice coil, lead model 80-7000 Hz., bass model 50-4000 Hz., Spring Post Terminals 8 ohm impedance, Recommended Retail Price \$38.

**15" 60 Watt R.M.S.** 28 ounce barium ferrite magnet, 1 1/2" voice coil, lead model 70-8000Hz., bass model 30-4000 Hz., spring post terminals, 8 ohm impedance, Recommended Retail Price \$48.

**15" 100 Watt R.M.S.,** Massive 54 ounce magnet, 2" diameter ALUMINEX voice coil, lead model 80-8000 Hz., spring post terminals, 8 ohm impedance, Recommended Retail Price \$70.

**18" 100 Watt R.M.S., SUPER GIANT** big bass sound 54 ounce magnet, 2" voice coil, 20-3000 Hz. Recommended Retail Price \$94.

*All C.T.S. speakers feature vented aluminium dust caps to relieve air pressure generated in the area of the gap. For further details and stock contact:*

#### CONTACT:

**AUDIO ENGINEERS (VIC)**

2A Hill St., Thornbury 44-3295

**NATSOUND PTY. LTD.**

261 Elizabeth St., Melbourne  
67-8158

*Trade Enquiries Welcome*



# Hear. Here.



## The incomparable BSR TD8S 8-track stereo tape cartridge player.

This superb machine literally speaks for itself. This cunningly designed and engineered unit produces an extremely high quality stereo sound reproduction from an eight track cartridge. One cartridge will provide four separate stereo programmes of up to one hour and twenty minutes in length. The machine will then repeat the programme indefinitely. Track switching is completely automatic or can be selected by a simple push button selector. Each track is indicated as it is being played. An integral solid state 3-stage pre-amplifier gives a fully corrected frequency response ideal for feeding into the auxiliary input on a suitable power amplifier. Motor temperature is controlled by an integral force-ventilation system. The heart of the machine is a four pole dynamically balanced synchronous motor which delivers an unwavering constancy of speed independent of normal voltage fluctuations. The TD8S is undoubtedly the highest

quality 8 track cartridge player available. But why not hear the superior sound of this brilliant machine for yourself at your nearest retailer of sound equipment, because as we said before, the TD8S literally speaks for itself.

### Technical Data

Number of tracks: 8 (4 stereo channels);  
Tape Speed:  $3\frac{1}{4}$  in. per sec. (9.6 cm/sec);  
Programme Selector: Automatic and manual; Tape Head: Nortronics 4 track with hyperbolic face; Pre-amp Output: 3 stage 750 mv (nominal) 1 Kc Standard Reference Level Tape; Track Playback Sequence: 1 and 5, 2 and 6, 3 and 7, 4 and 8 and infinite repeat; Wow/Flutter: Less than 0.3% total; Frequency Response: Better than 50-10,000 Hz; Power Supply: 210-250 volts, 50 Cycle AC; Dimensions: Cabinet: 261 mm x 206 mm x 99 mm; Net Weight:  $5\frac{1}{2}$  lbs.; Cartridge Dimensions: This unit will accept standard 8 track cartridges measuring 139 mm x 101 mm x 22.5 mm.

BSR (A'asia) Pty. Ltd. Southern Section  
Industrial Estate St. Marys New South Wales  
Telephone 623.0375 and 623.0376

### Wholesale Distributors

Goldring (N.S.W.) Pty. Ltd.,  
26-28 Ricketty St., Mascot. 2020 Phone- 669 6088  
Goldring (Vic.) Pty. Ltd.,  
162 Pelham St., Carlton. 3053 Phone-347 5177  
Goldring (Qld.) Pty. Ltd.,  
35 Balaclava St., Woolloongabba. 4102  
Phone-91 4972  
Goldring (S.A.) Pty. Ltd.,  
76-78 McLaren St., Adelaide. 5000 Phone-233 488  
Goldring Sales and Service (Canberra)  
Unit 5, 83-85 Wollongong St., Fyshwick. 2069  
Phone-95 8248  
Goldring (W.A.) Pty. Ltd.,  
32 Northwood St., Leederville. 6007 Phone-84988

**BSR McDONALD**  
**TD8S**

BSR 118R2



## VARIETY FARE

There is a mixture of Western hits such as: Mother of mine — Get me to the church on time — Dominique — Amazing Grace, and other well-known show tunes together with a number of traditional Korean songs. The Little Angels are obviously well trained and their fresh young voices are a delight to listen to. (N.J.M.)

★ ★ ★  
LOUIS ARMSTRONG'S HELLO DOLLY.  
MCA Stereo KS 3364. Astor release.

The showmanship of the late Louis Armstrong shines through on every track of this enjoyable record. Such all-time favourites as: Hello Dolly — It's been a long long time — A kiss to build a dream on — Hey, look me over — Moon River — Be my life's companion — Blueberry Hill — Jeepers, Creepers — A lot of lovin' to do — Someday — I still get jealous — You are woman, I am man.

The overall quality is excellent. (N.J.M.)

## Jazz and Rock . . .

NEWPORT IN NEW YORK '72. The Jam Sessions, Vol 1. Atlantic stereo SD 1012.

Two long performances, "Jumpin' at the Woodside" of 21 and a half minutes and "Lo-Slo Blues" of 22 and a half minutes make up an album of jazz from last year's New York Jazz Festival.

Those on stage were Cat Anderson and Jimmy Owens on trumpets (Owens playing a fluegelhorn by the sound of it), Charles McPherson on alto saxophone, Buddy Tate, tenor sax, Milt Buckner organ, Roland Hanne piano, Charlie Mingus bass and Alan Dawson drums.

I'm always suspicious of jazz tracks which try to stay funky for a whole LP side. No need. Each of the eight band members maintains a surprising degree of concentration.

"Jumpin'" is tight, clean and exciting, everything that you would expect an up-tempo improvisation to be.

The "Blues" predictably has the best and worst of the album aboard. Cat Anderson does some crowd pleasing with a stratospheric chorus. Mingus eclipses him with an extraordinary bass solo. The track then settles down and Mingus comes back with a solo of extraordinary charm. (G.W.)

★ ★ ★  
FLANAGAN'S SHENANIGANS. Pearce-Pickering Ragtime Five plus guests.  
Swaggie mono S1309.

Recorded in the Hobart studios of the ABC, this veteran group continues to play easy-going, unfussed jazz.

Trumpet player Bruce Dodgshun is new to records. His playing fattens "The Jazz Parade", "Shut Up Boona Baby", "I've Got a Feeling I'm Falling" and "Pennies from Heaven".

The group is basically a piano and clarinet contrapuntal outfit but it is able to turn on exceptional colourations to meet the needs of a guest. Singer Kay Stavely, for instance, brought about a metaphorphosis in Pickering and had him playing big, melodic tenor saxophone in the Chu Berry style on "Carelessly".

"I'll never Be the Same" has similar

playing although the guitar and voice intro seems miffed.

Ian Pearce at piano is the strength of every performance. The lyricism of Pearce and Pickering has resulted in an LP of jazz of great spirit.

Michael Colrain is the drummer on most tracks. Bass playing is shared by Ron Roberts, Des Conrades and Barry Johnson. Ken Chaffey is on guitar and banjo. (G.W.)

★ ★ ★  
THE LONDON CONCERT. Duke Ellington.  
United Artists stereo UAL 273 / 4.

Ellington has managed to continue to provide exciting jazz with a band which, in October, 1971, had undergone considerable personnel changes.

The record was made in London, just a year after the 70th birthday concert album. It is a fine sequel to that set. None of the tunes are repeated. Using new saxophone players Norris Turney and Harold Minerve, Ellington launches into a new suite "Togo Brava, Brava Togo" dedicated to a west Africa State. It too, is typical of Ellington's major works, suggesting a life cycle from birth to manhood. (G.W.)

★ ★ ★  
FILTHY. Papa John Creach. Grunt stereo  
FTR 1009-G.

Creach plays hot violin in the Stephane Grappely style. He even sounds good amongst the dreary accompaniment on this record. Imagine a teenybopper chorus of females, a rock band, and a dubbed-in brass and horn section!

Creach has a good blues voice which comes over well on a number of tracks.

"Far Out" shows his skill with the violin. There's disconcerting use made of a Jew's Harp on many of the tracks. I consider that this is a most unsuitable jazz or rock instrument. Another blues singer of merit, Big Joe Turner, sings on "Give Me an Hour in Your Garden". He has to suffer the drummer on the session who plays every number loud and predictably. (G.W.)

★ ★ ★  
TOMMY, JIMMY AND EDDIE, 1923-29.  
Swaggie mono S1299.

These records were made after the Dorsey brothers, Tommy and Jimmy, had left Paul Whiteman to form their own band. Guitarist Eddie Lang was present on each of the 17 tracks on the disc. Eddie either solos or gives that particular Lang lift to the rhythm section.

The LP opens with Tommy Dorsey on trumpet playing in duet with the great jazz trumpeter Leon McConville on "Bugle Call Rag". Jimmy Dorsey provided the soaring clarinet and Arthur Shutt was on piano. It is a magnificent track, summoning the listener to sit down and enjoy the entire disc.

Tommy, Jimmy and Eddie used their names to head the bands, with the exception of the two earliest cuts, made with the clarinet player Boyd Senter. Senter was more a caricature of a jazz player than a stylist in his own right.

Mildren Bailey made her recording debut on the track "What Kind o' Man is You". The terrible lyric is the only concession to commercialism on the whole album.

Some of these tracks were around on re-issue in the forties. It's good to hear them again and appreciate the hard biting trumpet style that Tommy had in those days — quite the opposite of his later sentimental trombone playing. (G.W.)

# HiFi EQUIPMENT

*you want to know . . .*

- HOW TO SELECT IT?
- WHAT TO PAY FOR IT?
- WHERE TO BUY IT?

*. . . then you need the  
Electronics Australia*

## HiFi-STEREO ANNUAL

*\$2.00 plus postage*

**USE THIS COUPON**

To: ELECTRONICS AUSTRALIA  
P.O. BOX 157 BEACONSFIELD 2015.  
AUSTRALIA

Please send me . . . . . copies of the "Hi Fi Stereo Annual" at \$2.30 posted within Australia. \$2.00 plus postage for overseas buyers (plus estimated for 13oz. posted weight). Please enclose only cheque, money order, Australian Postal Order etc. NOT CASH.

NAME . . . . .

ADDRESS . . . . .

POSTCODE . . . . .

A SPECIAL 25% DISCOUNT is available on single copy rate for bulk buyers of not less than 12 copies to retailers, radio clubs, youth groups. Please enclose remittance with order including estimated parcel postage or freight.



# ENCEL SLASHES PRICES ON TANDBERG STEREO TAPE DECKS!

## ENCEL'S SCOOP PURCHASE OF LATEST MODEL TANDBERGS IS A TREMENDOUS SAVINGS OPPORTUNITY!

*Only Australia's foremost hi-fi authorities could do it! And you won't find Tandberg at or near Encel's price anywhere in Australia!*

*Check the features of the dramatically-styled Tandberg Series 3300X stereo tape deck, unmatched for performance by any other machine in its price class.*

- Tandberg Crossfield recording technique ensures superb sound quality.
- Specifications exceed DIN standard 45500 by an ample margin.
- Large illuminated peak equalised recording meters.
- 4 sound-heads — separate playback and recording heads provide sound-on-sound and other special effects.
- Three speeds, 7 1/2, 3 3/4, 1 7/8 ips.
- Mixing ● Photoelectric ● Front jack for stereo headphones.
- Records mono / stereo from receiver / tuner, or from its own microphones.

**ALSO AVAILABLE: 4000X, and 3 motor 9000X**



**UP TO \$200 (OR MORE) OFF LIST PRICE**

**Trade up now!**

**ONLY AT**



**431 Bridge Rd., Richmond  
3121. Tel. 42 3762.**

*Australia's foremost hi-fi authorities.*



# PRODUCT REVIEWS AND RELEASES

## High performance player from Haco

Record playing equipment seems to be under constant improvement and refinement in performance. An excellent example of this trend is a new direct drive record player from Haco, the Technics SL-1200.



An eye-catching product, the new player combines a 2-speed turntable having very ambitious specifications with an arm intended for use with any of the currently available high quality cartridges. It is a player which would command respect in any hi-fi listening situation.

The "Technics" 1200 is mounted in a metal and plastic housing, meant to be free-standing rather than mounted on a wooden plinth in the usual manner. The main base is finished in a metallic grey lacquer, with a smoke coloured acrylic lift-up lid fitted with friction hinges to keep it up when required.

The whole unit rests on four pillar type shock absorbent feet, which could be removed to set the unit into a recess cut into a cabinet. The overall dimensions, cover included, are 450mm wide, 370mm deep and 162mm high.

The die-cast aluminium turntable has a strobe pattern cast into the sloping rim. This is illuminated by a neon lamp in a small metal pillar on the left hand corner of the base, adjacent to the speed selection switch and vernier speed adjustment.

This is intended for use with two separate speed control knobs, one for 33 and the other for 45rpm. The speed can be adjusted "spot on" or set deliberately high or low where this is required for a special reason.

As mentioned in the introduction, the SL-1200 employs the direct drive principle, the motor being integral with the turntable and

operating at the same spindle speed. The idea was exploited in some early 78rpm turntables and involved a multi-pole synchronous motor almost as large as the turntable itself. These motors were generally plagued by hum fields, however, and did not lend themselves to multi-speed applications.

Electronic circuitry solves these problems in the new Technics turntable, making possible a much more compact drive assembly, with two-step speed

change, vernier speed adjustment and very precise regulation at any setting.

The direct drive principle used has the great advantage that it avoids the generation of high frequency vibration components normally produced by motor unbalance, gearing, idler wheels or belts, which often contribute their own unwanted song to the recital.

The electronic drive and speed control circuitry for the brushless DC motor is mounted on a printed wiring board fitted with plug-in connectors. We could not inspect the motor in detail but we presume it is fitted with a tachometer or similar velocity feedback device to ensure accurate control. The power supply transformer is well isolated, both mechanically and electrically from any sensitive area, particularly the pickup's arc of travel.

The tubular arm of light alloy carries a lightweight offset headshell, fitted with a standard EIA screw collar attachment. The playing weight adjustment is provided by a counterweight moved by a smooth rack and pinion mechanism.

The adjustment knob carries a collar graduated in grams, so mounted that as you turn the knob back to reach balance, after fitting the cartridge, the collar comes to a stop, reading zero. As you turn the knob back from this balance point you get a direct reading of playing weight on the scale. There would be a change in accuracy of the scale, depending on its position on the arm, but this should be of little consequence.

Anti-skating compensation is taken care of with a small, graduated knob at the base of the arm. The makers claim a noise and rumble figure better than -60dB — which we found to be conservative. In fact we could not measure any noise component attributable to the mechanics of the player when using the silent run-out grooves on a CBS test record.

We were not in a position to measure wow and flutter directly but observations of sine wave signals from the test record, STR 100, showed a remarkably steady pattern on an oscilloscope.


At a retail price of approximately \$300 it is a player for the well-lined pocket but the performance is of a correspondingly high standard. And with really only one moving part in the turntable, reliability and wear should present no problems.

Technics Turntables are distributed in Australia by Haco Distributing Agencies Pty Ltd, at 57 Anzac Parade, Kensington, 2033. (N.J.M.)

## McMURDO: Prototype push-button switch kit

A comprehensive isostat kit containing all the hardware required to develop prototype push-button switch banks is now available.

Contents of each kit includes; 2, 4, 6 and 8 change-over modules, together with AC modules, springs, circlips, brackets and a range of illuminated and plain buttons in a variety of styles. A demonstration switch bank and complete instructions for assembly are included. McMurdo (Australia) Pty Limited, PO Box 321, Clayton, VICTORIA, 3168.





## Philips SM130 'Sound Module': large sound from a small space

After a decade or more of stereo record reproduction, most of us have become accustomed to living with two rectangular loud speaker enclosures in the lounge room. With the advent of 4-channel sound the space question has cropped up again, but the new SM130 "Sound Module" from Philips could well solve a lot of problems in this area.

Bearing little resemblance to the usual concept of a loudspeaker enclosure, the "Sound Module" measures 60cm x 75cm; but it is only 8cm thick, a fact that greatly simplifies placement. They may be hung on the wall, or used as a fire screen or incorporated as part of a room divider.

To merge with differing decor arrangements, a choice of front panel fabrics is available in abstract patterns, as well as a choice of wood finishes for the frame.

The back is sealed against tampering (a most unsporting move!) but, through the rear grille cloth, one can make out the shape of a large ceramic magnet at the centre of the sound panel and another smaller magnet up in one corner, presumably providing the tweeter function.

The sound panel, ostensibly of rigid polystyrene foam, replaces the normal paper cone of a more conventional loudspeaker and is driven by the two voice coils. These share the signal by means of a simple crossover network.

With over a quarter of a square metre of radiating surface, the panel has an area much greater than any normal loudspeaker and consequently can move a greater amount of air for a given movement of the diaphragm. At the same time, of course, it has to do this without the assistance of a conventional enclosure.

The large piston area, plus the large high-flux magnet assembly, would make one expect high acoustic efficiency and this was borne out in our comparisons with other

loudspeakers of well known performance. The Sound Modules are certainly modest in their drive power requirements.

Laboratory tests revealed a system with a somewhat "forward" sound, indicating strength in the middle register. A reasonable amount of bass boost is necessary to even out the response. The main diaphragm resonance occurs at 65Hz; below this the output falls off rapidly, emphasizing the need for bass boost.



On average program material the system produces clean and pleasant sound but, on complex musical passages, there is some evidence of intermodulation.

The mount-anywhere slimness of the "Sound Module" would facilitate its use, not only in awkward domestic situations but in shops, restaurants etc where an ordinary enclosure would look out of place.

At \$149.00 each, they are not exactly an economy model, but their power handling rating of 30W, their acoustic efficiency and ease of placement should recommend their use in a wide range of situations. They are available from Philips sales departments or from hi-fi outlets.

## Two new op amps from Philips Elcoma

Two new operational amplifiers, the TCA490 and the TCA520B, have been released by the Elcoma Division of Philips Industries Ltd.

The TCA490 is a low noise, dual operational amplifier with a wide application range. An output noise voltage amounting to only a fraction of a millivolt makes the TCA490 suitable for applications ranging from industrial control systems to low distortion stereo preamplifiers.

Available with specified output noise voltage limits of 125uV, 250uV, or 400uV rms, the dual op amp has a typical voltage gain of 15,000 and a typical common mode rejection ratio of 100dB.

Salient features of the TCA520B are its ability to operate with any supply voltage from 2V to 20V and to deliver output voltages within 0.1V of the supply voltage. Typical slewing rate is 50V/us. A principal application foreseen for the new op amp is as a TTL-compatible comparator. Encapsulation of the TCA530B is 8-pin DIL.

For further information contact Elcoma at Mars Road, Lane Cove, NSW 2066.

## PCL-2 PRINTED CIRCUIT PROTECTOR

FROM THE  
**ELECTROLUBE** TROUBLE SHOOTERS



Protects printed circuit boards from severe environmental attack and resists high humidity. Acts as a soldering flux: Unnecessary to remove lacquer before replacement of component.

PCL-2 is a spray-on flexible protective coating, will not discolour or crack and keeps out moisture-contamination.

Available from leading electrical wholesalers.



Information on PCL-2 and other ELECTROLUBE products is available from the Australian agents:

**RICHARD FOOT (AUSTRALIA) PTY. LTD.**

63 HUME STREET, CROWS NEST, N.S.W. 2065. Telephone: 43-0326.

R.F.1547B



## RH 521: An amplifier continental style

There is no dearth of high quality amplifiers on the market these days but the RH 521, a new release from Philips, stands out with its crisp, continental styling. It is well worth consideration by anyone planning to up-date their hi-fi system in the immediate future.

The front panel is styled in brushed aluminium, while the case has a satin finished walnut top and leather-grain vinyl end panels. The top two-thirds of the panel is occupied by two output meters at the left-hand end and a large volume control knob at the right.

Below this level, slightly recessed, are four slider controls for balance, bass, presence and treble. Two small pilot lights, also in the recess, indicate power on and mono-stereo respectively.

Twelve rocker type switches, with individual and inter-locking mechanisms as necessary, cover input selection, mode, speaker selection and power. The contour or loudness function and the scratch and rumble filter are controlled by two alloy knobs, sharing the lower line of the panel.



Facilities for microphone and headphone connection are conveniently to hand via two DIN sockets, concealed under a hinged flap at the left hand end of the front panel. They are concealed almost too well, in the sense that the facility could easily be overlooked!

Sharing the back panel with the massive heatsinks are five DIN sockets for pickup, recorder, tuner, auxiliary and monitor. In addition there are four DIN type loudspeaker sockets for front and rear loudspeakers in the "Stereo 4" mode or for main and extension loudspeakers in normal stereo operation. A mains voltage selector rounds off the back panel compliment.

For the "Stereo 4" mode, the rear loudspeakers are connected substantially in series to provide an inexpensive form of simulated quadraphonic reproduction.

Removing the timber top reveals a well packed interior but service accessibility should present no special problems. Access to the underside of the pre-amp board is via a perforated metal bottom cover. Other boards are supplied with sufficient lead length to allow removal from the chassis for check or repair.

The power amplifier follows normal quasi-complementary symmetry practice, with overload protection afforded by an SCR 'crow-bar' that removes the drive to the output stages under fault conditions.

With the wide range of controls on this amplifier, the user can tailor the response curve to suit almost any requirement. The bass control gives plus and minus 14dB while the treble control yields plus 14 and minus 16dB. The presence control gives a

plus and minus 6dB variation around 2kHz. This latter control can produce quite a clarifying effect on speech, either recorded or 'live', where clarity is the prime requirement.

Rumble and scratch filtering is provided with three options: rumble plus scratch, rumble alone, or scratch alone. The attenuation slope in each case is 12dB per octave, with the 3dB points at 80Hz and 7kHz respectively.

The contour or loudness control provides three levels of bass and treble boost at low volume settings, with a maximum of 20dB at 50Hz and 9dB at 10kHz.

On test, the RH 521 met or exceeded most of the manufacturers specifications within normal instrumental tolerances. Output power was measured at 30.25 watts per

channel before clipping. After a long run at full sine wave power the output before clipping did fall to 27.5 watts, as a result of slight bias shift due to heating, but as continuous sine wave operation is most unlikely in practice, this is an academic point.

Frequency response is quoted as being plus 0.5, minus 1dB from 20Hz to 20kHz; we found it to be down 1½ dB at 20 Hz.

Distortion at 20W per channel was 0.15pc, compared to the quoted figure of 0.1pc. Signal-to-noise was good at 80dB, with open circuit input, although the claimed figure is 90dB. Other parameters, such as cross talk, were found to match or better the published figures.


Square wave response was virtually "text-book", with no sign of ringing. Likewise, capacitive loads caused no embarrassment to the amplifier. Stability under a variety of load conditions would appear to be one of its strong points.

A listening test with a variety of records bore out the test-bench results, with an effortless, high-quality performance. With the pickup lifted from the record at normal room level one had to get within an inch or two from the loudspeaker to detect any hiss or hum.

With the range of control facilities provided, the RH 521 should find ready appeal amongst the discriminating buyers with \$309 in their pocket. This and other products in the Philips hi-fi range are available from Philips' sales departments in each state or from selected retailers. (N.J.M.)

## BATTERY CHARGER REGULATED BATTERY ELIMINATOR

Multi Voltage 4.5, 6, 7.5, 9 V



TYPE PS164

- Unlimited operation of Battery-operated Transistor Equipment from 240 Volt AC Mains at negligible power cost.
- Output regulated to prevent speed variation in Tape Recorders motors. Constant Voltage to radios, etc., gives more undistorted power at high volume.
- Approved by Electric Supply Authorities.
- Double Insulated for extra safety.
- Ideal for 4.5, 6, 7.5, or 9V Transistor Radios, Tape Recorders, Small Transistorised Amplifiers and Test Equipment, etc.
- Filtered to ensure hum-free operation.
- Output selected by rotary switch, recessed to prevent accidental alteration

### Technical Specifications:

Input 220/240V 50Hz.  
Output 4.5, 6, 7.5 or 9V DC Regulated,  
Maximum Current 0.3 Amps.  
Regulation — less than 10%.  
Ripple — less than 0.25% RMS.  
Dimensions 3½ ins. x 2½ ins. x 2 ins.  
(90 x 65 x 50mm.).



### A & R - SOANAR GROUP

#### SALES OFFICES


**VIC:** 30-32 Lexton Rd., Box Hill.  
89 0238.  
**NSW:** 4 Close St., Canterbury.  
78 0281.  
**SA:** 470 Morphett St., Adelaide.  
51 6981.

#### INTERSTATE AGENTS

**QLD:** R. A. Venn Pty. Ltd.,  
Valley. 51 5421.

**WA:** Everett Agency Pty. Ltd.,  
West Leederville. 8 4137.





## THE ELECTRIC VOICE

The Rubin buzzer. It has all the advantages you want for a communication system. And more. The electric signal is restrained; effective but not annoying. The Rubin buzzer is totally insulated; neither heat nor electricity is conducted. Mounting is above earth. And the Rubin buzzer, because of its small compact size,

is adaptable for use anywhere. The Rubin buzzer (AC/DC) is the complete internal communication system. It is a signalling device. A warning device. Whenever the situation demands that a simple message has to be sent, you should be using the Rubin buzzer. The Electric Voice. For further information contact:



**E. S. RUBIN**  
& Co. Pty. Ltd.

N.S.W.: 73 Whiting Street, Artarmon 2064. Telephone: 439-2333. Telex: 21175. SOUTH AUSTRALIA: 49 Woodville Road, Woodville 5011. Telephone: 68-1111. Telex: 82529. VICTORIA: 138 Berkeley Street, Carlton 3053. Telephone: 347-6588, Telex 30948. QUEENSLAND: Telephone: 78-6424. WESTERN AUSTRALIA: Telephone: 21-7861.


## NEW PRODUCTS

### Low cost 7-seg LED indicators

At only \$2.36 each in quantities of 1000, these new LED numeric indicators are ideal for commercial applications.

Now at prices equal to, or less than comparable gas-discharge display tubes and many LED displays, a new series of Hewlett-Packard solid-state numeric indicators is especially suited for commercial applications. With uniformly lit, diffused segments, the characters appear sharp and clean, and thus are pleasing to the eye. Calculators, television receivers, radios and digital clocks are among many uses to which they can be put.

Two 0.3inch high, single-digit units are announced. The Model 5082-7730 contains a left-hand decimal point; the Model 5082-7731 has a right-hand decimal point. Both have the same pin configuration and same package outline as the MAN-1, Data-Lit 10, and similar Led displays, although the character height is larger. The use of the standard DIP package allows for socket or printed circuit board mounting. Individual



digits can be close packed on 0.4 inch centres, but the larger character height allows other spacings where desired.

Electrically, the displays are IC compatible. Forward voltage per segment or decimal point is 1.6 volts. Luminous intensity is 250 microcandelas per segment typically. Operating current is typically 10mA per segment when strobed.

Both displays, built on rugged lead frames, are arrays of eight discrete diodes optically "stretched" to a uniformly lighted diffused bar. Only one LED per segment is required because of a unique funnel-shaped "light pipe" that lights a bar 5 times the length of the LED chip.

To improve contrast, the entire front surface of the display, except for the emitting areas, is finished in a uniform flat black. An additional filter may be used to further lower ambient reflections and improve contrast.

Pricing structure is based on quantity as follows: 1-99, \$3.16 ea; 100-999, \$2.60 ea; 1000, \$2.36 ea.


For further information, contact Hewlett-Packard Australia Pty Ltd, Marcom Department, 22-26 Weir Street, Glen Iris, Victoria 3146. Phone 20 1371.

R5780



## A compact loudspeaker system from Goodmans

If you are in the market for a compact loudspeaker system capable of a very pleasing performance, the Goodmans "Minister" would be worthy of your attention. It combines Australian cabinet work with a pair of imported drivers — one woofer and a dome tweeter.




Tastefully finished, the Goodmans Minister measures 48.2cm x 26.6cm x 25.4cm. It is available in either teak or walnut veneer and a matching wooden surround encloses the recessed and padded grille cloth. The veneer finish is carried right around the outside to allow the cabinet to be positioned either vertically or horizontally, as required.

Internally, a 20cm (approx) diameter bass drive unit (a nominal 8-inch type) operates in conjunction with a 2.54cm dome tweeter. The bass driver is of quite modest appearance but the specially treated cone and roll surround indicates that it has been specially produced for the job in hand.

Apart from the cone design, the characteristics of the system at the bass end would be influenced by a vent tune 16cm long and 5cm diameter and by a generous fill of light bonded fibre. Presence of the fibre would undoubtedly modify the resonance of the enclosure so that its behaviour would probably fall midway between that of a fully sealed or fully vented system.

Both screw terminals and a DIN socket are provided on the back panel and the connecting lead supplied has a din DIN plug on one end and spade lugs on the other. Since the lead can be used either way with the loudspeakers, the user can present either lugs or the connector to the amplifier.

Tests with an audio signal revealed a very smooth performance over the whole audible range, with a just perceptible peak in response around 65Hz. With the amplifier tone controls set for flat response, the bass fell off rapidly below this but, in practice, overall balance would be restored with a little bass boost.



When we played a variety of records through the "Minister," we were quite impressed with the overall performance. The response is not as "forward" as some systems we have heard but this is offered more as a comment than a criticism.

Acoustic efficiency of the system is fairly low and Goodmans themselves state that a ten watt per channel amplifier is necessary to provide adequate sound levels for

domestic use. At the same time a power rating of 20 watts would indicate that they should not be driven beyond the requirements of a normal listening situation.

At a retail price of \$84 each, the "Minister" represents good listening and good value if you are after a compact speaker system. They are available from selected hi-fi retailers in all states. (N.J.M.)

## Updating for colour television

The Institution of Radio and Electronics Engineers and the University of New South Wales have jointly organised a Workshop on Colour Television to be held at the University from 13-17th August. The first meeting of the workshop is to be opened by the Minister for the Media, Senator Doug McClelland.

The aim of the workshop is to bring together those who will be associated with the Australian change from monochrome to colour TV, to discuss common problems, and also to make available some of the recent experience of overseas television authorities. To the latter end, six prominent colour television experts from overseas will be in attendance: C. E. Anderson from Ampex, C. R. Longman and F. G. Parker from the BBC, Joe Roizen from IVC, C. Siocos from CBC, and H. Thielcke from NDR.

Abstracts of the papers to be used to start the discussions will be made available to delegates prior to the meetings. Delegates are expected to be senior engineers from both commercial and government broadcasting organisations. Registration fee is \$2.

Further information from the General Secretary of the IREE, or from Dr J. Hiller, University of NSW.

## DIGITAL VOLT/OHMETER



- \* 0.1% DC ACCURACY
- \* AUTO-POLARITY
- \* 3½ DIGITS WITH 100% OVER-RANGE
- \* 10 MEG. INPUT RESISTANCE
- \* DUAL SLOPE INTEGRATION
- \* LOW COST

**SCIENTIFIC ELECTRONICS PTY. LIMITED**  
42 Barry Street, Bayswater, Vic. 3153.  
Telephone — Melbourne 729-3170 Sydney 25-3955  
Brisbane 47-4311



# LAFAYETTE

27 MHz Two-Way Radio

## MICRO-12

**\$139.50**

(Crystals Extra)



PMG Type Approved.  
(Licence Required).

### 5-WATTS 12 CHANNELS ONLY 5" W x 1 1/4" H x 7 1/2" D

- Operates on 12 volts DC Negative Ground (Easily convertible to Positive Ground).
- Highly Sensitive Receiver with RF Stage.
- Variable Squelch for Silent Standby.
- Automatic Noise Limiting.
- Mechanical IF Filter on 455 KHz for High Selectivity.
- 0.7 Amp. Drain on Transmit.
- Zener Diode Voltage Regulation.

The Lafayette Micro-12 embodies exceptional performance with compact size. Incorporates the design features which have made Lafayette world leaders in 27 MHz Two-Way Radio. Supplied complete with microphone, power leads and bracket.



## HE-20T

**\$169.50**

(Crystals Extra)

PMG Type Approved (Licence Required).

### 5-WATTS 12 CHANNELS PLUS TUNABLE RECEIVER

- 12 volts DC Negative or Positive Ground and 117 volts AC (also available for 240 volts AC).
- Crystal Controlled Transmit and Receive.
- 455 KHz Mechanical Filter.
- TVI Trap and Pi-Network Output.
- May also be used as PA Amplifier with External Speaker.
- Automatic Noise Limiting.
- Size 11 1/4" W x 4 1/2" H x 8 1/4" D.



### 1-WATT 3 CHANNEL WALKIE-TALKIE

- 3 Switchable Crystal Channels.
- High Level Modulation with "Range Boost".
- Extra Sensitive Receiver — Better than 1uV.
- Sturdy Metal Case.
- Battery Meter.
- Socket for External Power Supply.
- Automatic Noise Limiter.
- Variable Squelch Control.
- Jacks for External Earphone and Antenna.
- Supplied with Crystals for 27.240 MHz Operation.

HA-310 \$72.50 each. PMG Type Approved (licence Required)

**ACCESSORIES** — A large range is available. Antennas, Coaxial Cable, Connectors, 27 MHz Crystals (many frequencies in stock), etc.

## LAFAYETTE ELECTRONICS

LAFAYETTE Transceivers

also available at —

BRISBANE: CUSTOM SCIENTIFIC ELECTRONICS  
PTY LTD, 74-76 Annerley Rd, Woolloongabba.  
91 6433.

LAUNCESTON: L. A. HEYWARD, 8 Herbert St.  
31 3098.

Division of Electron Tube Distributors  
Pty. Ltd.

94 HIGH STREET, ST. KILDA,  
VIC. 3182. Phone 94 6036.

Trade Representatives: SA: Tyquin Distributors Pty Ltd, 13 Deacon Ave. Richmond. Phone 57 8153.  
WA: Athol M. Hill Pty Ltd, 613-615 Wellington St, Perth. Phone 21 7861.

## NEW PRODUCTS

### New speaker kits from Plessey Rola

Plessey Rola has introduced two new high fidelity cabinets in kit form for enthusiasts interested in both top performance and keen value.

Designated CK1 and CK2, the kits have been designed for optimum performance with the Plessey C80 woofer and two C3GX tweeters in the CK1, and the recently released C100 woofer and X30 tweeter combination in the CK2.

Extremely simple to assemble and finish in the required timber toning, the Plessey do-it-yourself kits represent a considerable saving over fully finished enclosures of similar performance. Anyone who can use a screwdriver could complete two cabinets for a stereo system in just one afternoon's work. The finished product is a high quality,



high performance unit with a most attractive appearance.

The CK1 kit makes up a 1.8 cu ft cabinet. With the recommended Plessey speakers, frequency response is 44 Hz to 20 kHz and power handling capacity 20 watts RMS. A 2.5 cu ft cabinet is produced from the CK2 kit. Fitted with the recommended speakers this system has a frequency response from 40 Hz to 30 kHz and 20 watts RMS power handling.

Kits are available from Plessey Rola distributors and other leading hi-fi dealers. Further information may be obtained from Plessey Rola Pty Limited, The Boulevard, Richmond, Victoria.

### Directory error

Butterworths & Co (Aust) Ltd advise that due to an oversight their name and address has been omitted from the 1973 Sydney telephone directory. The company may be contacted at: 586 Pacific Highway, Chatswood, NSW. Telephone 412 3444.



## NEW PRODUCTS

### IC breadboard from McMurdo facilitates IC systems design


A new IC breadboard to assist in the design and production of electronic equipment has been developed by McMurdo. It provides a rapid and economic means of interconnecting integrated circuits, thus facilitating the speedy checking of designs and also providing a means of quickly assembling temporary test units.

Designated P/N 2150-99-90, the unit comes complete with 10 IC sockets, 75 mixed colour jumper leads, and a 24-contact Redline edge connector.

All kinds of integrated circuits, including flat pack, TO5, and dual-in-line are catered for, and in addition, provision is made for including special circuits made up from discrete components. Interconnections are made with ready-made plug-in wire links, which enable units to be wired up many times faster than by conventional means. The IC sockets, which are 16 contact 0.300 inch row types, are fitted with an unload ing key.

Price of the complete breadboard kit, including 75 leads and the edge connector, is \$35 plus sales tax.

For further information contact McMurdo (Australia) Pty Ltd, 242 Blaxland Rd, Ryde, NSW 2112. Telephone 807 1944. Also at 17-21 Carinish Rd, Clayton, Victoria 3168. Telephone 544 3033.



### Wide angle deflection and large screen Trinitron systems from Sony

The Sony Corporation of Japan has announced the technical development of a super-wide-angle deflection Trinitron colour TV tube, together with a new wide screen Trinitron system.

Sony first developed the epoch making Trinitron colour TV receiver in 1968 and, since then, has produced and shipped out more than 3,700,000 sets. Then in April 1972 they brought out an improved wider-angle Trinitron tube with a deflection angle of 114 degrees and vastly improved picture quality.

In the meantime, Trinitron colour TV sets incorporating new advanced techniques have been continuously developed, and now Sony has succeeded in producing receivers for the Japanese market incorporating an 18-inch 120 degree Trinitron and a 20-inch 122 degree Trinitron.

The Trinitron system has several unique features. These include: a single gun producing three in-line electron beams, narrow-necked picture tube, aperture grille with continuous vertical slits, and a large electron lens. Also, the closer the electron gun is to the phosphor screen, the better the colour picture resolution obtained. As a result the colour resolution of the new wide-angle tubes is very good.

Sony has incorporated a GCS (Gate Controlled Switch semiconductor device) in the horizontal deflection circuit of the new sets, and developed a specially designed lightweight deflection yoke. This has produced a super thin colour TV set, with a

depth of only 35.2cm in the 18 inch 120 degree wide-angle tube and 37.0cm in the 20 inch 122 degree tube.

The new wide screen Trinitron colour tube developed by Sony measures 27 inches diagonally and incorporates the 114 degree wide-angle deflection system.

A high resolution colour picture is obtained because the special electron lens system reduces the beam spot magnification, and the number of picture elements is increased as a result of the large screen.

### STC-Cannon Components

As from 1st July, 1973, the Components Division of Standard Telephones and Cables Pty Ltd and Cannon Electric (Aust) Pty Ltd have been amalgamated to form a new company under the name of STC-Cannon Components Pty Ltd.

All orders on the Components Division of STC will now be supplied by STC-Cannon Components and all future correspondence and orders should be addressed to STC-Cannon Components Pty Ltd, Moorebank Avenue, Liverpool, NSW 2170, tel 602 0333, or to 248 Wickham Road, Moorabbin, Vic 3189, tel 95 1566.

## There's a place for you in the growing world of electronics

Whether you're a hobby enthusiast or have professional ambitions, a Stott's course will help you find it.

Every day the number of applications for electronics in industry, science and business increases. It's a field which offers valuable career opportunities in manufacture, installation, servicing and sales—but only for people with thorough training.

That's why Stott's have just introduced an important new course, **Introduction to Electronics**. It combines both the theoretical and practical aspects, and includes a number of experiments to give you experience in the construction of electronic equipment. Extensive kits are supplied with the course.

Other Stott correspondence courses will help you become expert in the theory and practice of radio communications, or give you the know-how to get an Amateur Operator's certificate: **Radio for Amateurs Course**:

From radio basics, to intricate principles. Receiver design and construction. Latest techniques in electronics. Everything you'll ever need to know, made easy to understand by top radio engineers.

**Amateur Operator's Certificate:**

Gives you the background knowledge and the skills you need to pass the PMG exams and get your Certificate of Proficiency.

Make your place in the world of electronics. Start today by sending in the coupon below.

EA873

**TECHNICAL CORRESPONDENCE COLLEGE**

159 Flinders Lane, Melbourne, 3000. 383 George St., Sydney, 2000. 290 Adelaide St., Brisbane, 4000. 45 Gilles St., Adelaide, 5000. 89 St. George's Terrace, Perth, 6000. P.O. Box 3396, Singapore 1.

Please send me, free and without obligation, full details of your courses in Radio and Electronics.

Mr., Mrs., Miss ..... Age .....

Address .....

..... Postcode .....

No sales counsellor will call.

STC441



# EXTRA-DYNAMIC

THE AUDIOPHILE TAPE




NEW ASTOUNDING MATERIAL

**TDK**  
"MAGNETITE"

## ● THE CASSETTE DESIGNED EXPRESSLY FOR PURE SOUND


Performance data show ED superiority, but Your Ears also tell the difference of ED Cassettes. There is linearity of frequency



response from low to high frequency range. No need for Cro selector to correct for excessive high response and low frequency drop off. Any good recorder can now give balanced high fidelity recordings.

## ● THE IDEAL CASSETTE FOR NORMAL BIAS

The bias required is normal, that is the target for any magnetic tape. ED is the dynamic tape which suits almost every cassette recorder. No necessity for special bias settings. The superior performance of ED is achieved by the highest and even the lowest priced recorders.



## ● THE MATERIAL IS PURE-BLACK MAGNETITE

TDK research has brought magnetite to cassettes for the first time. TDK Electronics Co, Ltd is a pioneer in the field of electromagnetics, and has now achieved the stabilisation of Magnetite material for recording tapes for the first time.

**Convoy International Pty Ltd**

Corner Plunkett & Maclean Sts, Woolloomooloo  
2011. SYDNEY. Telephone (02) 357-2444

# FERGUSON

Manufacturers of: Electrical/electronic equipment, wound components and lighting control equipment.

## VERSATILE RANGE OF LOW HEIGHT POWER TRANSFORMERS


These transformers comply with the requirements of Australian Standard C126, where applicable, with respect to insulation and winding construction.

If forming part of a prescribed item, to be submitted to an Electricity Authority, it is essential to ensure proper earthing facilities, adequate ventilation and segregation of primary and secondary leads.

All the transformers in this range are suitable for connecting to 240 Volts 50 Hz., single phase supply and are nominally rated at 20VA. Dimensionally they are identical, with height limited to 1 1/2", width 2-3/8", length 4-5/16" and mounting centres 23/32" by 3-27/32 inches.

Each transformer is provided with two identical secondary windings which permit series or parallel operation, are fitted with round pin terminations and are supplied with a set of six leads with shrouded receptacles.

The tabulation sets out against type numbers the nominal rating and the voltage obtained for various loads when the windings are connected in series, 240 Volts being applied to the primary winding:—



TYPE No.	NOMINAL RATING	5VA	10VA	VOLTS OUTPUT @:		
PF3596	6V @ 10VA	13.0	12.6	12.0	11.5	11.0
	6V @ 10VA	(0.39)	(0.80)	(1.25)	(1.74)	(2.28)
PF3597	7 1/2V @ 10VA	16.6	16.0	15.4	14.7	14.1
	7 1/2V @ 10VA	(0.30)	(0.63)	(0.98)	(1.38)	(1.77)
PF3598	9V @ 10VA	19.8	19.2	18.0	17.6	16.7
	9V @ 10VA	(0.25)	(0.52)	(0.84)	(1.14)	(1.50)
PF3599	12V @ 10VA	26.4	25.6	24.6	23.5	22.4
	12V @ 10VA	(0.19)	(0.39)	(0.61)	(0.85)	(1.12)
PF3600	15V @ 10VA	33.0	32.0	30.0	28.9	28.0
	15V @ 10VA	(0.15)	(0.31)	(0.50)	(0.69)	(0.89)
PF3601	20V @ 10VA	43.5	42.2	40.7	39.1	37.3
	20V @ 10VA	(0.13)	(0.24)	(0.37)	(0.51)	(0.67)
PF3602	25V @ 10VA	54.0	52.2	50.4	48.4	46.2
	25V @ 10VA	(0.09)	(0.19)	(0.30)	(0.41)	(0.54)

Approximate current in Amps shown in brackets.

FERGUSON TRANSFORMERS PTY. LTD.

HEAD OFFICE 331 High St., Chatswood, 2067

Telephone: 40-0261

## AGENTS

TAS.  
Associated Agencies Pty Ltd  
25 Barrack St., Hobart, Tas, 7000  
Phone: 2-1843.

A.C.T.  
A.C.T.I.E.C. Pty Ltd  
21 Patterson Pde.  
Queanbeyan, N.S.W., 2620  
Phone: 97-3579

QLD.  
Keith Party & Co Pty Ltd  
Waterloo St., Newstead, Qld, 4006  
Phone: 51-5461

W.A.  
H.J. McQuillan Pty Ltd  
57 Division St.  
Welshpool, W.A., 6106  
Phone: 68-7111

S.A.  
K. Farmer Sales Pty Ltd  
141 Gilles St.  
Adelaide, S.A., 5000  
Phone: 23-4702

VIC.  
Ferguson Transformers Pty Ltd  
181-183 Hawke St.,  
West Melbourne, Vic., 3003  
Phone: 329-7437



## NEW PRODUCTS

### AWA launches new radiotelephone

Amalgamated Wireless (Australasia) has released a new series of smaller and more advanced two-way radiotelephones for mobile use, the "Fleetmaster Carphone" series. Included are units for both the VHF and UHF bands.

The "Fleetmaster" range employs state-of-the-art circuit and design techniques to provide mobile units and base stations to suit all likely user requirements. Mobile units are available for all VHF and UHF bands, and in power ratings of 10 and 25 watts. The matching base station equipment is available in 25 and 50 watt ratings.

A special feature of the "Fleetmaster" receiver is the extended range switch, which may be used for improved fringe area operation. The receiver is so small that it may be mounted directly in the dashboard space normally provided for a standard car radio. Extruded aluminium sections are used to provide extreme ruggedness and stability. Push-pull controls are used for on off, muting and channel selection, for convenience and foolproof operation. The channel indicator is illuminated to facilitate convenient night operation in taxis and similar applications where multiple channel operation may be used.

The equipment includes "Sel-call" and "Quiet-line" facilities to allow individual calling of up to 700 mobiles on one system.

The new Fleetmaster range will be produced concurrently with the 25M and 15M Carphones that have been standard equipment with many users over recent years. Both the Fleetmaster and the older Carphones are backed by AWA's solidly



based engineering expertise and quality control.

The Engineering Products Crystal Section has also announced the development of a miniature monolithic crystal filter, type 3Q62099, for 30kHz and 25kHz channel equipment. The filter has a centre frequency of 10.7MHz, 6dB bandwidth of +7.5kHz min, and 80dB bandwidth of +20kHz maximum; insertion loss is 4dB, and input output impedance 3.3k. Enquiries for the filter may be sent to PO Box 96, North Ryde.

## RADIO DESPATCH SERVICE

RADIO and ELECTRICAL WHOLESALERS  
869 GEORGE STREET, SYDNEY

### FOR ALL YOUR METER REQUIREMENTS

#### UNIVERSITY GRAHAM MOVEMENTS ONLY

VT2 50 Microamp	\$7.59
VT2 100 Microamp	\$6.90
VT2 500 Microamp	\$6.33
VT2 1MA	\$6.21
VT3 50 Microamp	\$6.90
VT3 100 Microamp	\$6.21
VT3 500 Microamp	\$5.64
VT3 1MA	\$5.52
VT4 50 Microamp	\$6.67
VT4 100 Microamp	\$5.98
VT41MA	\$5.29

#### COMPLETE INSTRUMENTS

University Graham CT500P 20K OPV	\$15.53
University Graham M770 20K OPV	\$46.00
University Graham MVA100 100K OPV	\$40.25
University Graham MVA6 VTVM	\$63.25
University Graham MVA7 VTVM	\$63.25
University Graham USG20D Sig. Gen.	\$52.90
University Graham UAG20D Audio Osc	\$63.25
University Graham UC3 3" CRO	\$161.00
Trio 1303 3" CRO Trans.	\$155.25

ALL PRICES NETT

### AVE moves: in two directions

Australian Video Engineering (AVE) became a wholly Australian-owned company on the 1st April, 1973, and is no longer connected with the Philips Group of Companies.

In addition to established agency products such as International Video Corporation, Ikegami Tsushinki Co Ltd, Grass Valley Group, Dynasciences, and Electronic Engineering Company of California, AVE is extending its product range with such manufacturers as Audiotronics Corporation of California, makers of ruggedised audio equipment for education, and Tamron CCTV Lenses.

Several new items of equipment are now being marketed by AVE. These include a low cost PAL colour camera (the IVC-91), 3M video tape, and a mass memory recorder (the MMR-1) capable of recording up to 85 million bits on one reel of tape. A new PAL colour cartridge recorder, the VCR-100, will be offered in October.

In addition to this range, a programmable broadcast cartridge recorder system, the BCR-200 has been developed. It has facilities for playing commercials and programmes in any random sequence.

Australian Video Engineering have moved to new premises at 231-233 Victoria Road, Rydalmere, 2116. Tel 638 6400.

## NATIONWIDE ELECTRONICS

P.O. Box 20, Berowra Heights 2082

### SPECIALISTS IN ELECTRONIC COMPONENTS

#### SEMICONDUCTORS

A15A (OA 679 100) \$ .80	BF115 \$ .74	MEL12 \$ 2.50	2N3053 \$7.70
AA119 .32	BF178 8.40	MPF102 1.25	2N3054 1.40
AC128 .94	BPX25 2.90	MPF121 1.25	2N3565 .42
AC187/188 2.10	BPX29 2.90	MJ2955 4.50	2N3441 2.80
AD139 2.23	BFY50 1.06	MJ3055 3.00	2N3564 .74
AD149 2.17	BFY52 1.35	NE555 1.40	2N3567 .55
AD161/162 2.90	BRV39 1.50	OA90 .28	2N3568 1.22
AF116 1.21	BT101/500R 4.47	OA91 .25	2N3569 1.40
AF124(AF114) 1.92	BTY79/600R 6.60	OA95 .33	2N3638 .74
ASV26 1.69	BYX214/200R 1.18	OA200 .43	2N3638A .89
AS215 2.48	BYX21 mounting 1.18	OA202 .48	2N3641 1.82
AY1110 1.40	C20D 6.47	OC44 1.60	2N3642 .89
AY8149 1.90	C103YY 2.20	OC926 .75	2N3643 1.20
AY9149 1.90	C106B1 2.16	ORP12 L.D.R. .65	2N3644 .65
AY8171 1.70	C106D1 3.64	PA263 I.C. 4.85	2N3645 .74
AY9171 1.70	C106F1 1.78	SC45D 10A Triac 7.50	2N3646 .65
BA100 .39	C106Y1 1.40	SE4010 .76	2N4250 .76
BA102 1.02	C122D 4.32	SL403D 6.50	2N4342 2.66
BA145 .41	C211 brimistor .65	SN7400 .90	2N4360 1.50
BC107 .40	D13T1 1.50	SN7402 .90	2N5459 1.36
BC108 .40	EM401 .30	SN7403 .90	2N5457 1.50
BC109 .40	EM404 .30	SN7410 .90	2N5485 1.81
BC108B .55	EM408 .70	SN7420 .90	2N5476 4.00
BC109B .55	EM410 .70	SN7430 .90	2SH12 2.29
BC109C .55	FuL914 1.40	SN74121 1.50	3814 F / CH 38.00
BC147 .50	IC709 1.50	ST4 .98	734 F / CH 5.46
BC148 .50	UA723 2.60	TAA300 3.50	9602 F / CH 4.50
BC149 .50	UA741c 1.90	TAA840 3.66	9307 F / CH 4.70
BC157 .50	LM301A 1.50	TT800 1.46	40406 2.74
BC158 .50	LM372 3.00	TT801 1.46	40407 2.37
BC177 .50	LM280 3.00	1N914 .25	40408 2.38
BC178 .50	LM309K 4.50	2N301 2.60	40409 3.15
BC179 .50	MC1469R 4.80	2N2160 3.22	40410 3.09
BCY70 .75	MB1 1.40	2N2646 1.50	40440 3.10
BD139/140 4.50	MB4 2.07		40669 2.99

**PLEASE ALLOW 25¢ TO COVER PACKING AND POSTAGE — ALL NEW AND GUARANTEED COMPONENTS**



# BOOKS & LITERATURE

## Memories, memories . .

**SEMICONDUCTOR MEMORIES**, edited by D. A. Hodges. Published by IEEE Press, New York, 1972. Soft covers, 216 x 277mm, 286pp, many illustrations. Price in Australia \$6.00 (Clothbound \$11.95).

A volume in the IEEE "selected reprints" series, designed to provide help for the hard-pressed engineer in learning about new devices and the application techniques which have been developed around them. This volume provides a convenient source of some 31 important recent papers on the field of semiconductor memory technology, for the computer and digital system designer and user.

The papers are divided into seven categories, designated by the editor as follows: 1 — Introduction to Semiconductor Memories; 2 — Bipolar Transistor Memories, Technology and circuits; 3 — MOS Transistor Memories, Technology and Circuits; 4 — Interconnections, Packaging and Economics; 5 — Reliability, Maintainability and Testing; 6 — System Examples; and 7 — Serial Memories and Content-Addressable Memories. A concluding section is used by the editor to give his conclusions and projections for future

A specialised volume, of course, but one which should be found of considerable value by the busy design engineer unable to plough through each and every issue of the learned journals.

The review copy came from John Wiley Sons Australasia Pty Ltd, who distribute IEEE Press publications in this country. (J.R.)

## Colourful work

**NEWNES COLOUR TV SERVICING MANUAL**, Volume 1, by Gordon J. King. Published by Newnes Butterworths, London, 1973. Hard covers, 253 x 188mm, 232pp, many circuits and diagrams. Price in Australia \$14.25.

Yet another book by the indefatigable Gordon King; this time a manual discussing the circuit, operation, setting-up and adjustment of nine major British colour TV receiver chassis of contemporary design. It has been written both as a study guide for the student and as a reference for the service technician. While it does incidentally give a good deal of basic information about PAL colour decoding, it is basically intended as a circuit study and complement to Mr King's other volume

"Colour Television Servicing," which was reviewed in these columns previously.

Naturally the receivers discussed are all of UK manufacture, and designed for the British PAL standards. However because these standards are quite close to those set down for Australian colour (the main difference being a vision-sound carrier separation of 6MHz, as opposed to our separation of 5.499MHz), the educational value of the book for Australian readers should be almost as high as for those in the UK.

The book is quite well produced, with the general explanatory material written in Mr King's usual highly readable prose. Some of the material which is pretty obviously taken from manufacturer's servicing literature is a little variable, as are the quality of the circuits and diagrams, but this is understandable in view of the enormous cost which would have been involved in completely unifying the text and re-drawing the illustrations. The only other aspect I found mildly irritating is that the text is set in unjustified measure (columns with ragged right-hand sides); but this is perhaps only a personal reaction.

All in all, the book gives a good insight into PAL colour receiver designs of 1972-73 vintage, and as such should be of considerable interest and value to anyone trying to gain background in this area. For the serviceman looking for a way of becoming familiar with the sort of circuits he is likely to encounter in the first Australian colour sets, it would be a good choice.

The review copy came from the local office of the publisher, Butterworths Pty Ltd. Copies should be available at all major and technical bookstores. (J.R.)

## LARGEST RANGE IN AUSTRALIA OF ELECTRONIC AND RADIO BOOKS

Mail order available, prompt attention. See below for this month's new publications.

Mechanical World Electrical Year Book 1973	\$5.40
Philips 1973 Pocketbook	\$2.00
Kwik-Fix TV Service Manual F. H. Belt	\$7.40
Simple Short Wave Receivers F. A. Balowin	\$2.80
TV Fault Finding J. R. Davies	\$1.70
Beginner's Guide To Practical Electronics R. H. Warring	\$3.90
Video Recording Record & Replay Systems G. White	\$9.50
The A.R.R.L. Antennae Book Published By The American Radio Relay League	\$4.35

Postage 35c Local  
Postage 65c Interstate

**McGILLS**

Authorised Newsagency Pty. Ltd.,

187 Elizabeth Street,  
MELBOURNE, VIC. 3000  
Phone 60 1475

## THREE BASIC TEXTBOOKS ON COMPUTER PROGRAMMING

Based on material first published in our associated British publication "Computer Weekly", these well-produced books provide a sound and thorough introduction to problem-orientated computer program languages for the engineer, scientist, technician and student.

- **FORTRAN BASICS** by Brian Hollocks
- **BASIC ALGOL** by W. R. Broderick & P. J. Barker
- **BASIC PL/1** by Jeff Maynard

Each book is printed on high quality offset paper, with stout covers from glossy card, and measures 154 x 249mm. Excellent value at \$2.00 plus postage.

Please send me a copy of the book(s) indicated below. I enclose . . . . . (cheque, money order, Aust Postal Order, etc, NOT CASH), being \$2.00 plus 30c postage per book. Overseas buyers estimate postage on 11oz posted weight. (Post coupon to Electronics Australia, PO Box 157, Beaconsfield, 2015.)

☐ Fortran Basics ☐ Basic Algol ☐ Basic PL/1

NAME .....

ADDRESS .....

POSTCODE .....



## Fine for courses

**ELECTRONIC CIRCUIT ANALYSIS**, by J. T. Wade, P. L. Edwards, and J. E. Clark. Published by John Wiley & Sons Australasia Pty Ltd, Sydney, 1973. Hard covers, 158 x 248mm, 640pp, many circuits and diagrams. Price in Australia \$18.50 (soft cover edition \$15).

A book written by three local technical academics to serve as a text for technical college students in electrical and electronics engineering, and also for students studying electronics as a supporting strand of another discipline such as chemical or mechanical engineering. It adopts a deliberately phenomenological approach to active devices, treating them largely as black boxes exhibiting certain basic behaviour, in order to avoid the heavy going and confusion which can be produced by highly sophisticated models. There is also considerable emphasis on the concept of "engineering approximation" as a practical design philosophy.

There are some 24 chapters, the treatment progressing from introductory concepts such as rectification and clipping, through diode, transistor and FET configurations, to vacuum tubes. Appendices at the rear of the book deal with basic semiconductor theory, tutorial problems, 8 sample test papers, and a topic index.

The text is clearly and concisely written, and is well served by illustrations. It is strongly orientated for use as a textbook for technical college courses, however, and because of this may be of less value to other readers. The emphasis is on mastering the practicalities of circuit analysis and design — at least to the extent of passing the appropriate examination. Those seeking a deeper insight into such basic concepts as device operation and switching logic will need to supplement it with additional reading.

For the intended purpose, however, it should certainly be found very suitable. It is well planned, well written and as up-to-date in approach as one would find in any published text.

The review copy came from the publisher, who advises that copies should be available from all major bookstores. (J.R.)

## Sound colour text

**COLOUR TELEVISION THEORY**, by Geoffrey H. Hutson. Published by McGraw-Hill Publishing Co Ltd, London, 1971. Hard covers, 195 x 254mm, 326pp, many circuits and diagrams. Price in Australia \$10.80.

A book which has already become justifiably popular as a text in technical colleges and universities. It is mainly concerned with the PAL development of the NTSC system, and is written for the engineer, technician or student who already has a good working knowledge of monochrome television principles.

There are 17 chapters, whose headings give a good idea of the overall scope and treatment: 1 — Light; 2 — Colour Television Signals; 3 — Colour-Bar Signals (NTSC and PAL); 4 — Basic PAL Coder, Transmitter and Receiver Arrangements; 5 — Receiver Display Devices; 6 — Convergence: General Principles; 7 — Convergence and Raster-shape Correction Circuitry; 8 — Chrominance Signals: General Principles of Quadrature Amplitude Modulation and Demodulation; 9 — Chrominance Signals:

Principles of PAL Quadrature Modulation and PAL-S Demodulation; 10 — Chrominance Signals: Basic Principles of PAL-D Demodulation; 11 — Synchronous Demodulators; 12 — PAL-D Decoder Techniques: Chrominance Signal Delay-lines and Associated Circuitry; 13 — PAL-D Decoder Techniques: V-Channel Switching Circuitry; 14 — Chrominance Amplifiers and Associated Circuitry; 15 — Subcarrier Reference Oscillators and Associated Circuitry; 16 — Colour Difference and Luminance Amplifiers; 17 — EHT Systems and Receiver Design and Development. At the end of the book are two data appendices and a topic index.

The text of the book is clearly written, and presents the material in a logical manner. It is well served by illustrations and does not depend upon slabs of mathematical analysis, which should make it of value to a very wide range of readers.

In short, a very good choice for anyone seeking a sound basic text on colour TV theory in general, and PAL in particular.

The review copy came from the Australian office of the publisher, but copies should be available at all major bookstores. (J.R.)

## Repeat program

**1973 WORLD RADIO AND TV HANDBOOK**, 27th Edition, edited by J. M. Frost. Published by World Radio-TV Handbook Co Ltd, Denmark. Price in Australia \$5.95 plus postage.

This latest edition of the standard world broadcasting reference handbook was reviewed in the March 1973 issue by our short-wave correspondent Arthur Cushen. Since then a second copy has been received, from Technical Book and Magazine Company Pty Ltd of 289-299 Swanston St, Melbourne. This firm advises that they can post copies to readers in Victoria for 50c postage, and to readers in other states for 70c.

## Right from scratch

**A COURSE IN RADIO FUNDAMENTALS**, fifth edition, by George Grammer. Published by the American Radio Relay League, Inc, Newington, Connecticut. Soft covers, 167 x 242mm, 184pp, many illustrations. Price in Australia \$3.20 plus postage.

A completely rewritten fifth edition of the ARRL's well-known basic text, the first edition of which appeared in 1942. Unlike earlier editions it is completely self-contained, and does not use the ARRL Handbook to provide any of the reference material. Revision and updating have almost doubled its size over the previous editions, making it particularly good value for money.

There are 26 chapters, which start with electrical fundamentals and basic circuit behaviour and progress through device theory and similar topics to more advanced concepts such as feedback, RF amplification, neutralisation and impedance matching. Each chapter concludes with tutorial problems, the answers to which are given at the end of the book along with suggested experiments and a data appendix.

As one would expect, the book is well written and prepared. The text is clear and

## NEW BOOKS

JUST A FEW OF THE THOUSANDS ALWAYS IN STOCK. CALL IN OR WRITE GIVING YOUR REQUIREMENTS. All books reviewed in "Electronics" can be ordered from us

### JUST RECEIVED

HOW TO LISTEN TO THE WORLD New 7th Edn.	\$4.40
RADIO AMATEUR'S HANDBOOK 1973 A.R.R.L.	\$6.95
WORLD RADIO & TV HANDBOOK 1973 (Complete Guide to World's Short-Wave Stations):	\$5.95
A.R.R.L. ANTENNA BOOK	\$4.35
A.R.R.L. RADIO AMATEUR'S V.H.F. MANUAL	\$4.35
AMATEUR RADIO TECHNIQUES — Pat Hawker (RSGR)	\$6.05
BASIC ELECTRICITY — 5 volumes combined:	\$14.65
BASIC ELECTRONICS CIRCUITS — 2 volumes combined:	\$7.30
BASIC ELECTRONICS — 6 volumes combined:	\$16.50
BASIC INDUSTRIAL ELECTRICITY — 2 volumes combined:	\$7.30
BASIC SYNCHROS & SERVOS — 2 volumes	\$7.30
BASIC TELEVISION — Technical Press, Three volumes in one — Just out!	\$11.45
ELECTRIC GUITAR AMPLIFIER HANDBOOK	\$5.45
GENERAL ELECTRIC SEMICONDUCTOR DATA BOOK	\$8.75
HI-FI AND TAPE RECORDER HANDBOOK — King	\$6.80
PAL RECEIVER SERVICING BY D. J. Seal — A new book! Profusely illustrated in colour, highly recommended!	\$11.90
PIN POINT TRANSISTOR TROUBLES IN TWELVE MINUTES	\$7.35
RADIO & ELECTRONIC LABORATORY HAND- BOOK SCROOGIE. New 8th Edition	\$15.00
R.C.A. SOLID STATE POWER CIRCUITS	\$8.50
R.S.G.B. RADIO COMMUNICATION HANDBOOK	\$13.76
SYLVANIA TECHNICAL MANUAL — Receiving Tubes / Picture Tubes and Semiconductors	\$5.15
TRANSISTOR AUDIO & RADIO CIRCUITS, Genuine Mullard circuits	\$3.50
TRANSISTOR EQUIVALENTS — European, American & Japanese	\$3.00
TV SERVICING GUIDE Arranged by Trouble Symptoms — Deane & Young. Our best seller!	\$4.00

MAIL ORDERS BY RETURN . . . PLEASE ADD  
50c per parcel postage (Vic), 70c per parcel  
interstate

### TECHNICAL BOOK & MAGAZINE CO.

295-299 Swanston St.  
Ph. 663 3951 MELBOURNE 3000. Ph. 663 2849

concise, and well served by illustrations. A quantitative approach is taken wherever appropriate, but never beyond the level served by elementary algebra.

In short, a particularly good basic text on modern radio fundamentals, and one which would be ideal both for individual study and for use by class and club groups.

The review copy came from Technical Book and Magazine Company, of 289-299 Swanston Street, Melbourne, who advise that they can supply copies by mail for 60c postage within Victoria, and 80c for other states. (J.R.)

### HI FI ANNUAL

Still available from our office for \$2.00,  
or from box 157, Beaconsfield, 2015  
for \$2.30 posted.





# AMATEUR BAND NEWS & NOTES

by Pierce Healy, VK2APQ

## Rules for Remembrance Day Contest

The annual WIA Remembrance Day Contest rules, and details of award and certificate hunters' clubs are featured in this month's notes. There are also preliminary details of the proposed OSCAR-8.

Probably the most unusual contest, anywhere in the world, is the Remembrance Day Contest. Sponsored by the Wireless Institute of Australia for Australian and, more recently, New Zealand amateurs, it was inaugurated to perpetuate the memory of Australian amateurs who paid the supreme sacrifice in World War II.

The contest has no outright winner but is very popular among amateurs in Australia and New Zealand, even though many of those now participating knew little, if anything, about amateur radio when the contest was first held.

### REMEMBRANCE DAY CONTEST

A perpetual trophy is awarded annually for competition between divisions of the WIA. It is inscribed with the names of those who made the supreme sacrifice and so perpetuates their memory throughout amateur radio in Australia.

The name of the winning division each year is also inscribed and the division receives a suitably inscribed certificate.

**OBJECTS:** Amateurs in each VK call area, including Australian Mandated Territories and Australian Antarctica, will endeavour to contact amateurs in other VK and in ZL call areas, on all bands.

Amateurs may contact any other amateurs on the bands above 52MHz, (i.e. intrastate scoring contacts will be permitted on the VHF/UHF bands).

**CONTEST DATE:** 0800 hours GMT Saturday, 18th August, 1973, to 0759 hours GMT on Sunday, 19th August, 1973.

All amateur stations are requested to observe 15 minutes silence before the commencement of the contest on the Saturday afternoon. An appropriate broadcast will be relayed from all divisional stations during this period.

#### RULES:

- There are four sections:
  - Transmitting — phone
  - Transmitting — CW
  - Transmitting — Open
  - Receiving — Open
- All Australian amateurs may enter whether fixed, portable, or mobile. WIA members and non-members are eligible for awards.
- All amateur bands may be used and cross-mode operation is permitted. Cross-band operation is not permitted.
- Amateurs may operate on both phone and CW during the contest, i.e. phone/phone, CW/CW or phone/CW. However, only one entry may be submitted for sections (a) to (c) in Rule 1. An open log will be one in which points are claimed

for both phone and CW. Refer to Rule 11 concerning log entries.

- For scoring, only one contact per band per station is allowed, except that a second contact on the same band using an alternative mode is permitted. On 52MHz and above, additional contacts may be made after two hours from the previous contact. Arranged schedules for contacts on the other bands are prohibited.
- Multi-operator stations are not permitted. Log keepers are permitted, but only the licensed operator is allowed to make contact under his own call sign. Should two or more wish to operate any particular station each will be considered a contestant and must submit a log under his own call sign. Such contestants shall be referred to as "Substitute Operators." Their operating procedures must be as follows:—  
Phone: Substitute operators will call "CQ RD, or CQ Remembrance Day" followed by the call sign of the station, the word "log", and their own call sign, e.g. "CQ RD from VK4BBB log VK4BAA".  
CW: Substitute operators will call "CQ RD de" followed by the call sign of the station, an oblique stroke, and their own call sign, e.g. "CQ RD de VK4BBB / VK4BAA".  
Contestants receiving signals from a substitute operator need record only the call sign of the substitute operator.

- Entrants must operate within the terms of their licence.
  - CYPHERS: Before points may be claimed serial numbers must be exchanged and acknowledged. The serial number of five or six figures will be made up of the RS (telephony) or RST (CW) reports plus three figures that will increase in value by one for each successive contact. If any contestant reaches 999 he will start again with 001.
  - Entries must be set out as shown in the example, using one side of paper only and standard WIA log sheets if possible.  
Entries must be clearly marked "Remembrance Day Contest 1973" and must reach the Federal Contest Manager, WIA, Box 638, GPO Brisbane in time for opening on Wednesday, 20th September, 1973. Early entries will be appreciated.
  - Scoring will be based on the table shown.  
Portable operation: Scores of operators working outside their own call area will be credited to that call area in which operation takes place, e.g. VK5-ZP / 2 will contribute towards VK2 total score.
  - All log sheets to be set out as in the example shown and in addition will carry a front sheet showing the following information:
  - The Federal Contest Manager has the right to disqualify any entrant who has not observed the regulations or has consistently departed from the accepted code of operating ethics.  
The Federal Contest Manager also has the right to disallow illegible, incomplete, or incorrectly set out logs.
  - The ruling of the Federal Contest Manager of the WIA is final and no disputes will be entered into.
- AWARDS:** Certificates will be awarded to the top scoring stations in sections (a) to (c) of Rule 1 in each call area, and will include top scorer in each section of each call area operating exclusively on 52MHz and above. VK1, VK8, VK9, VK0, ZL1, ZL2, ZL3, ZL4, and ZL5 will count as separate areas for awards. There will not be an outright winner. Further certificates may be issued at the discretion of the Federal Contest Manager. The Division to which the trophy will be awarded shall be determined in the following way:  
To the average of the top six logs shall be added a bonus arrived at by adding the ratio of logs entered to the number of state licensees (including limited licensees), multiplied by the total points from all entries in sections (a), (b) and (c) of Rule 1.  
VK1 scores will be included with VK2, VK8 with VK5 and VK0 with VK7. Also VK9 logs and score will be added to the division which is

### EXAMPLE OF TRANSMITTING LOG

DATE / TIME GMT	BAND	EMISSION AND POWER	CALL SIGN WORKED	RST No SENT	RST No. REC'd	POINTS CLAIMED

### EXAMPLE OF RECEIVING LOG (S.W.L.)

DATE / TIME	BAND	EMISSION	CALL SIGN HEARD	RST No. SENT	RST No. REC'D	STATION CALLED	POINTS CLAIMED
Aug. 73							
14 0810	7MHz	A3(a)	VK5PS	58002	-----	VK6RU	1
14 0812	" "	" "	ZL2AZ	59007	-----	VK3K1	2
14 1035	52MHz	A3	VK4ZAZ	56010	-----	VK5ZDR	2
14 1040	" "	" "	VK3ALZ	59025	-----	VK3QV	1

### VK SCORING TABLE

To	VK0	1	2	3	4	5	6	7	8	9	ZL1	2	3	4	5
From	VK0	—	6	6	6	6	6	6	6	6	2	2	3	4	1
"	VK1	6	—	1	1	2	3	5	4	6	5	1	2	3	4
"	VK2	6	3	—	1	2	3	5	4	6	5	1	2	3	4
"	VK3	6	4	1	—	2	1	4	3	6	5	2	2	3	4
"	VK4	6	3	1	2	—	3	6	5	4	3	3	3	3	4
"	VK5	6	5	2	1	3	—	4	3	3	6	4	4	4	5
"	VK6	6	6	2	1	4	2	—	3	5	6	4	4	5	6
"	VK7	6	5	1	1	3	2	5	—	5	6	2	2	3	4
"	VK8	6	5	1	1	2	3	6	4	—	3	4	4	6	6
"	VK9	6	5	1	2	3	4	5	6	1	—	5	5	6	6

### ZL SCORING TABLE

To	VK0	1	2	3	4	5	6	7	8	9
From	ZL1	6	1	1	1	2	2	5	3	5
"	ZL2	6	1	1	1	2	2	5	3	5
"	ZL3	6	3	3	3	4	4	6	4	6
"	ZL4	6	4	4	4	5	5	6	5	6
"	ZL5	1	6	6	6	6	6	6	6	6

geographically closest. ZL scores will not be included in the score of any WIA division.

All contacts made during the contest must be shown in the log submitted, see Rule 4. An invalid contact must be shown but no score claimed.

Entrants in the "Open" sections must show CW and Phone contacts in numerical sequence.

Logs for all sections shall show at least five valid contacts. The trophy shall be forwarded to the winning Division and will be held by that Division for the specified period.

Radio clubs and other organisations, as well as individual amateur operators, are cordially invited to submit news and notes of their activities for inclusion in these columns. Photographs will be published when of sufficient general interest, and where space permits. All material should be sent direct to Pierce Healy at 69 Taylor Street, Bankstown, 2200.



#### RECEIVING SECTION (Section d):

1. Open to all short-wave listeners in Australia and New Zealand, but no active transmitting station may enter.
2. Contest times and logging of stations on each band are as for transmitting.
3. Logs shall be set out as in the example. The scoring table to be used is the same as for transmitting entrants and points must be claimed on the basis of the state in which the receiving station is located. A sample is given to clarify the position. It is not sufficient to log a station calling "CQ", the number he passes in a contact must be logged. It is not permissible to log a station in the same call area as the receiving station on the MF and HF bands, i.e. 1.8MHz to 30MHz, but on bands 52MHz and above, such stations may be logged more than once per band, for one point, on each occasion.
4. A station heard may be logged once on phone and once on CW for each band.
5. Club receiving stations may enter for the receiving section but will not be eligible for the single operator award. However if sufficient entries are received, a special award may be given to the top receiving station in Australia. All operators must sign the declaration.

**AWARDS:** Certificates will be awarded to the highest scorers in each call area. Further certificates may be awarded at the discretion of the Federal Contest Manager.

**Note:** The "one operator — one log" does not hold any longer. In future an operator may, in addition to his own log, submit a club and/or divisional station log. However, more than one log under any one call sign is not acceptable.

#### AWARDS AND CERTIFICATES

Awards and certificate hunting is said to be the amateur equivalent to contests requiring physical skill or endurance, or which rely on patience and other skills exhibited in more subdued manner.

In whatever type, participants often come under adverse criticism due to their total pre-occupation, above all else, to add to their achievements. In spite of such criticism, it is one of the popular facets of amateur radio that has an intriguing challenge for many operators.

Two international organisations cater for those interested. Details of these organisations have been supplied by two well-known Australian amateurs who represent these organisations.

#### The Award Hunters' Club International

The Award Hunters' Club International (AHC) is incorporated in Finland and divided into six Continental Sections. These Sections are independent but all follow the same general principles in the membership rules. The Club was established at the end of 1957.

The "AHC" headquarters has the following main tasks:—

1. to co-ordinate the activities of the continental AHC Sections.
2. to keep a register of World Awards and Certificates (published as the "AHC Bulletin").
3. to maintain the "XL-Club" as a goodwill recognition to highly skilled amateurs all over the world.

Award hunters may join their own Continental Section.

AHC-O covers amateurs resident in Oceania which includes Australia, New Zealand and Pacific areas.

**Requirements for membership:**

1. Basic membership requires a minimum of twenty-five different certificates and must comprise the following:—
  - (a) At least ten official certificates, i.e. certificates sponsored by the International Amateur Radio Union member societies.
  - (b) Not more than ten certificates may be from one's own continent.
  - (c) At least four continents must be represented in the list of certificates submitted.
  - (d) Certificates issued on contacts on national or international basis only will count.
  - (e) Regardless of class or endorsement, the same certificate may be counted only once.
2. Endorsement stickers will be available for 50; 100; 150; 200 and 250 certificates. At least one third of the certificates submitted for endorsement must be official. (Note local certificates may be used for endorsement purposes.)
3. General restrictions:
  - (a) Contest certificates do not count.
  - (b) Certificates available only to members of certain clubs or countries do not count.
  - (c) Different classes or endorsements of the same certificates do not count separately except in case they represent single-mode and/or single-band operation (single-band-single-mode

counts together), or in the case of century certificates representing additional centuries 200, 300 etc.

- (d) Certificates given for similar or practically similar requirements do not count as different awards, except in the case of annual awards bound to calendar year or any part of it.
- (e) The mixed version of the certificate is omitted when any single-mode and/or single-band endorsement is submitted for credit.
- (f) Club membership certificates do not count except the DXCC, A-1 Operators Club and the XL-Club.
- (g) Certificates having a political background do not count.
- (h) Certificates issued for three contacts or less do not count.

A summary of official awards is available from AHC Headquarters.

4. Application: Send your continental AHC secretary a list of your certificates giving the abbreviations of the award names in alphabetical order, full names of the awards, number and/or date of issue, possible endorsements. Certify the correctness of the list with your own signature. No other certifications are necessary, but any falsification in the application will lead to disqualification.
5. Fees: Registration fee, giving life-long membership, is based on \$US1.00. Equal amount of any currency or IRC's may be used upon agreement with your Continental AHC secretary.

The Continental Sections may fix an active membership fee in order to finance their inter-continental activities. This is an internal matter and does not affect the general lifelong membership.

Sufficient return postage should be included in all correspondence from applicants or members to the AHC-Hq / AHC Continental secretary.

6. The decisions of the AHC International Board will be final and right to change the rules is reserved. The continental secretary for Oceania (AHC-O) is Alan Shawsmith, VK4SS, 35 Whynot Street, West End, Brisbane, Q 4101 Australia.

#### The International Certificate Hunters' Club

In the note received from Alan his comments were: "Are you interested in obtaining awards of merit and achievement? AHC will bring you the latest, most accurate and up-to-date information on all the worthwhile awards from every continent."

"Award Hunters cop a lot of criticism and some of it is justified. To many, awards are of little value. However, AHC aims to keep the standard up by the rule that all those who seek membership must hold a certain number of official awards."

Alan extends an invitation to those interested to write to him for further details.

The International Certificate Hunters' Club is an amateur achievement, honour, service fraternity open to amateurs worldwide. Membership cannot be bought, it must be earned.

Chapter No 66 of the "CHC" has been formed in Australia, the officers are:

President: Alex Slight, VK2ZA.  
Vice-president: Jim Cunningham, VK3APL.  
Secretary / treasurer and Awards Custodian: Jack Gutcher, VK3APU.

Some details of membership and an award sponsored by the Australian chapter were received from Alex Slight, VK2ZA. These should interest active operators.

Membership is not a simple matter of making application and paying dues, but is dependent upon a points system which covers many aspects of amateur activity. Such as, membership of the national radio society, regional radio clubs, offices held therein, contributions to amateur radio magazines, various DX certificates and awards held etc.

In other words, membership is a good measure of the involvement of the prospective member in amateur radio. A minimum of twenty-five points is required for full membership and a minimum of twelve points for associate. Any amateur who would like full details should write to any of the three officers at their call book address, or to CHC Executive Secretary, Cliff Evans, K6BX, 3212 Mesa Verde Rd., Bonita, California 92002 USA, enclosing one international reply coupon (IRC) and a self-addressed label.

With the object of stimulating activity on all amateur bands, particularly the lower bands, 3.5MHz and 7.0MHz, and to encourage Australian amateurs to go mobile and portable to offer co-operation and assistance to fellow amateurs here and overseas, two Australian awards have been instituted, based on the 125 Commonwealth Electorates.

The basic award will be given for working 25 electorates, with specified numbers in each state. The major award will be issued for working all 125 electorates.

The two awards are known as the "Australian

Commonwealth Electorates Award" or "ACE" and the "ACE 125".

Full particulars of the awards, which are open to amateurs worldwide, may be obtained by forwarding 20 cents in stamps to — J. C. Gutcher, VK3APU, 17 Foulds Court, Montrose, Victoria 3765.

To quote a comment by Alex, VK2ZA — "Don't be surprised if some fellow amateur says 'What is your federal electorate OM?' — please note it is the federal not state electorate that is required."

"Well do you know? — you would be surprised how many vote but don't know their electorate. Perhaps these awards will also help to generate further knowledge and interest in our own country."

The formation of the Australian chapter and inauguration of the award was inspired by the "New Zealand Counties Award," originally sponsored by CHC Chapter No 67 in New Zealand but now sponsored by the NZART, the New Zealand national society.

It has been stated that making contacts with stations in all of the 112 New Zealand counties is much more difficult than the DXCC award. At the present time only two amateurs in Australia, VK2ZA and VK4LZ, have gained the award.

Amateurs in Australia and overseas have been impressed by the trouble to which New Zealand amateurs will go to provide contacts from counties in which there are no resident amateurs. Many have travelled many miles to operate mobile or portable from such counties. Even to the extent of flying across to Stewart Island.

#### AMSAT-OSCAR NEWS

During the weekend 23rd-24th June, 1973, state coordinators of the WIA project AUSTRALIS group met in Melbourne to discuss operation of OSCAR 6, currently in orbit, and OSCAR 7 which is being prepared for a possible launch in 1974. Also, a suggestion that OSCAR 8 be constructed in Australia.

The WIA OSCAR project group would like to receive any ideas that Australian amateurs may have on frequencies and systems which might be incorporated in OSCAR 8.

At the time of compiling these notes the information on AMSAT-OSCAR-B (OSCAR 7) was that three translators would be incorporated in the package. These would be a 70cm to 2m translator and two 2m to 10m translators. One will have somewhat higher power than the present OSCAR 6, and the other, more or less identical to OSCAR 6, will be used as a backup system. Only one translator will be operative at any one time.

Present plans for the 70cm translator call for an up link range of 432.125MHz to 432.175MHz and a down link range of 145.925 MHz to 145.975MHz. The unit will employ frequency inversion, so that, neglecting Doppler shift, an input at 432.125MHz will be retransmitted at 145.975MHz. Input using upper sideband will be retransmitted as lower sideband. When this translator is in use, a telemetry and codestore beacon will be heard on 145.980MHz.

The 2m to 10m translators will employ identical frequency bands. The uplink range will be the same as OSCAR 6, 145.900MHz to 146.000MHz. As with OSCAR 6, frequency inversion will not be used. The 2m to 10m mode will incorporate two beacons, as with OSCAR 6, one at 435.100MHz, the other at a frequency in the 10m band to be decided.

In addition to the OSCAR 6 configuration, in which the beacon at 29.450MHz is used in conjunction with a downlink range of 29.450MHz to 29.550MHz, two alternatives are under consideration. Were it deemed desirable for the beacon to remain at 29.450MHz, the downlink range could be shifted to 29.350MHz to 29.450MHz. Alternatively, the beacon could be moved to 29.500MHz and the downlink placed at 29.400MHz to 29.500MHz. Many users have expressed regret that the OSCAR 6 downlink extends above 29.500MHz, since tuning that range is inconvenient with several popular receivers in current use. As a consequence, OSCAR 6 activity has been concentrated in the lowest 50KHz of its passband.

Information from AMSAT indicates that the lifetime of one year expected of OSCAR 6 will be achieved. There is some evidence of battery degradation but this is not necessarily an indicator of shortened life.

However the complete co-operation of all users in relation to radiated power limitations and operating schedules is essential.

#### WIRELESS INSTITUTE ACTIVITIES

##### The FM Repeater Scene

To give an up-to-date précis of the situation regarding FM repeater channels, requires the proverbial crystal ball; particularly if the information is to be read four to six weeks after it is written.

Since last month's comments were written there appears to be nothing which warrants any change in the thoughts expressed.

Official statements, from four of the six WIA divisions, were published in the June issue of the Institute's magazine "Amateur Radio". However, as the WIA journal is circulated only to members, it must be



difficult for nearly 50 per cent of Australian amateurs who are not members to evaluate the situation.

Unfortunately space does not permit a complete review of all the facets of the confusing situation.

However, to sum up the problem in a few lines:

The Victorian proposal demands a major change in the current FM repeater and simplex frequency channels, on the basis of possible interference to amateur satellite users in the 144.80MHz to 146.00MHz section of the band. Other points are stated, but the emphasis is placed on the amateur satellite service.

The New South Wales view insists that only a minor change is necessary, that is, move the 145.9MHz channel 4 repeater output. This is confirmed by a statement received from AMSAT that 145.80MHz to 146.00MHz is the portion of the band to be used for the amateur satellite service. Other points are made, relating to technical aspects involved.

There are many side issues that have been brought into the confrontation. All seem to cloud the basic point from which the controversial proposal has snowballed — the possibility of interference to users of amateur satellite OSCAR 6.

Now WIA internal political overtones and inter-division lobbying are adding to the confusion.

One submission which was conspicuous by its absence in "A.R." was that from the federal repeater committee (formerly the FRS). Particularly as this committee has the task to consider all proposals and make recommendations to federal executive. Federal executive, in turn, should seek ratification of such recommendations by all divisions by postal vote or, should any one division request, hold the matter over for discussion at the next federal convention.

In view of the responsibilities and procedure outlined above, it is understood that quote "... a postal vote is under way to divisions." (QSP A.R. p2 June 1973). But the recommendations to be voted on are not those of the FRC, but those being sponsored by the council of the Victorian Division.

However, the report of the FRC, dated 12th May 1973, is published in the June issue of "Tuned Lines," the official journal of the VHF & TV Group of the NSW Division. Also in that issue is a chronological summary of events; discussions which took place and proposals put forward during the period Easter to mid-May 1973.

A rider to the FRC report may sum the situation up: "The above report was sent to Federal Executive for publication in the June issue of A.R. but communication from Peter Dodd (Business Manager, Federal Executive), indicates that it is unlikely to appear as 'there were no reports from either Australia or VHF advisory committee to balance it'.

"This attitude would seem to follow the previous one of not presenting information of an anti-change nature to members."

From the tone of the rider, which appears in the form of a statement after the names of the members of the Federal Repeater Committee, it will no doubt be realised that the FRC report does not favour any major change.

The irony of it all is that WIA Federal Executive has announced the appointment of three members from NSW as the FRC, but had not thought fit to let members know the committee's recommendations.

#### CUSTOMS DUTY

Most welcome news this month concerns customs duty on amateur equipment. Apparently continuing representations to the authorities by business organisations, the WIA, "Electronics Australia", and numbers of individual amateurs have at last borne fruit.

While matters are not finalised at the time of writing, the authorities are currently modifying the regulations to permit duty free entry of typical six-band transceivers covering the 10, 15, 20, 40, 80 and 160 metre amateur bands.

Even though the formalities may still be sufficiently formidable to deter all but the more enthusiastic individuals, the way would seem to be open for local distributors to import such items duty free, and to pass this saving on to their customers.

A point to remember about the situation is that the Radio Branch, PMG's Department, when announcing the approval for the use of unattended VHF repeaters by Australian amateurs in 1968, stated:

"The Department suggests that, wherever appropriate, the local WIA organisation should co-ordinate applications..."

It was this suggestion that brought about the Wodonga meeting in 1969 which drew up a frequency plan for repeater and simplex operation in the 145MHz to 146MHz segment of the band. Also, the formation of a Federal Repeater Secretariate. To date all applications have been co-ordinated through the FRS.

#### Radio Museum

The council of the NSW Division, WIA, is endeavouring to gather old radio units and components suitable for historical display, showing the type of amateur equipment used in the years gone by.

Anyone having such items, wishing to assist the project, is invited to contact the Administrative Secretary, 14 Atchison Street, Crows Nest, 2065.

#### Central Coast Amateur Radio Club

The Gosford Show Society has again offered space to the Central Coast Amateur Radio Club at the district show, 22nd and 23rd September, 1973. The club appreciates this gesture and will be arranging an exhibit to publicise various aspects of amateur radio. Members will erect antennas for the event and it is hoped that these may be permanent, as the site is the venue for their popular annual field day.

Already preliminary discussions have been held regarding the annual field day, normally held early in February.

The final date will be decided when information is available from other clubs holding events in February.

The CCARC hold meetings on the first and third Friday of each month. Visitors welcome.

For details contact the secretary, Barry Gibbins, Gosford, telephone 25 1746 or write to Box 238, PO Gosford 2250.

#### Geelong Amateur Radio Club

The third Geelong Hamfest was held on 26th and 27th May, 1973. The event was organised by a joint committee of members of the Geelong Amateur Radio & TV Club and the Geelong Radio and Electronic Society. The committee members were:—

Bob Wookey, VK3IC; Harry Michael, VK3ASI; Will Chandler, VK3ZSN; Mike Trickett, VK3ASQ; Colin Lowne, VK3ZZS; Bill Erwin, VK3WE and Alan Bradley, VK3LW.

The event proved to be the most successful yet, with 140 registrations, and an attendance of more than 250. This number posed quite a catering problem, but this was handled very successfully by the hard working ladies of both clubs. Appreciation of their efforts was shown by the enthusiastic applause from all present. The committee also thanked all who generously donated tasty dishes for the meals.

Prizes and technical literature were donated by R. H. Cunningham, U.E.S. Geelong, Lafayette Electronics, HI-Q Crystals, Radion Parts Pty Ltd, Motorola Semiconductors and Schlumberger.


Trade displays were provided by Fred Bail — Bail

# NOISE?


## get the measure of DAWE

- with the Sound Level Meter type 1400G.
- Meets BS 3489 and IEC 123 standards.
- Highly stable ceramic microphone unaffected by temperature and humidity.
- Measures sound levels from 24dB to 140dB.
- Compact and portable—weighs 2 3/4 lb.
- Filters available for every purpose — Dawe types 1461, 1462, 1463, 1464, 1465.

TECNICO ELECTRONICS



Premier Street, Marrickville, N.S.W. 2204. Tel. 55 0411  
2 High Street, Northcote, Vic. 3070. Tel. 489 9322  
Adelaide: 67 2246, Perth: 25 5722.



## FET-TYPE ALL TRANSISTORIZED, HIGH SENSITIVITY ELECTRONIC VOLT-OHM METER



MODEL VT-108

This is a new FET-type, electronic Volt-Ohm Meter equipped with a "Memory" circuit which will prove to be an indispensable asset on any electronic production line, service bench or educational facility because of its wide versatility, ease of operation and efficient panel layout. All-transistorized for instant voltage and ohm value readings and compact portability. It boasts exceptionally high sensitivity for accurate measurements. A special feature of this advanced multimeter is a built-in "Memory" circuit which memorizes measured values temporarily for instant recall reference of the user.

#### SPECIAL FEATURES

1. High sensitivity for wide-range voltage measurements.
2. All transistorized (FET) type circuitry for compact, lightweight utility.
3. Neat, efficient panel layout.
4. Powered by four (UM-3) batteries for portability. Batteries service one month of continuous use.
5. "Memory" circuit stores measured value for instant recall reference after completion of measurement.
6. Measures AC voltages with frequencies range from 15 Hz to 5 MHz.
7. Taut-band suspension type meter, ruggedly constructed both electrically and mechanically, for dependable, accurate readings at all times.

# PARAMETERS

PTY. LTD.

SYDNEY 43-6577 • MELB 90-7444 • ADEL 51-6718 • BRIS. 785422  
• PERTH 812866 • NEWCASTLE 614321 • WOLLONGONG 740278.



Electronic Services, and Alf Forster — Brownbill Amplifiers.

All contests were keenly contested and the following were awarded prizes.

1st 144MHz AM Scramble — 1st VK3ZDW; 2nd VK3NM; 2nd 144MHz AM Scramble — Equal 1st VK3-BMD, VK3ZDW; Equal 2nd VK3NM, VK5DK. Sniffer Hunt — 1st VK3AUI; 2nd VK3YAV. 80 metre contest — 1st VK3BEV; 2nd VK3BCH. All channel FM Scramble — 1st VK3ASV; 2nd VK3YGH. 1st 40 metre Scramble — 1st VK3ASI; 2nd VK3TN; 2nd 40 metre Scramble — 1st VK5TH; 2nd VK3TN. FM Channel B contest — 1st VK3YGX; 2nd VK3ASV. Best Home Built Gear — 1st VK3ASV; 2nd VK3YFL.

For information, write to the Secretary, Geelong Amateur Radio & TV Club, PO Box 520, Geelong, Victoria 3220.

## WIA YOUTH RADIO SCHEME SOUTH AUSTRALIA

On Saturday, 16th June, 1973, the Youth Radio Club Scheme in South Australia held its annual general meeting. Twenty club leaders from metropolitan and country areas attended.

The host was Prince Alfred College, where there is a strong youth radio club with many enthusiasts among the students. A message of welcome from the headmaster was read by club leader and teacher, Mr Phil Emery.

Mr Geoff Taylor, VK5TY, president of the SA Division WIA addressed the meeting. A letter and report was received from the YRCS federal coordinator Rev Bob Guthberlet.

This year there were some new faces from Pt Augusta and Renmark, as well as from the city area. Club leaders and instructors exchanged ideas on the running of clubs, enabling them to keep up to date on the development of YRCS throughout the state.

Mr Lloyd Douglas, VK5LL, demonstrated several reusable project kits used at the Pt Augusta Youth Radio Club.

Typical kits included a "push pull" crystal set, simple multimeter, regenerative broadcast receiver, audio amplifier intercom unit. The member builds the kit using the parts, layout drawing and circuit provided, has the project tested and assessed for workmanship, and then disassembles it ready for use by the next club member. The system is particularly useful for members without a project of their own to carry on with. Also on display were a number of YRCS project kits available from the YRCS project officer in Victoria.

The committee elected is: Supervisor, Mr Allen Dunn, VK5FD; Secretary: Mr Noel Kohler, VK5DV; WIA Liaison officer, Mr John Allan, VK5UL; Country Representative, Mr Lloyd Douglas, VK5LL; Metropolitan Representative, Mr Phil Emery.

Mr Steve Johnston did not seek re-election as secretary in order that he may concentrate his YRCS interests into the Boy Scout organisation, including the Jamboree-on-the-Air.

A new club is the Sacred Heart College Youth Radio Club, under the guidance of Mr Leo Powning. Theory lessons are held on Friday nights after school, with practical work on Sunday afternoons.

The senior class at St Marys Boy Scouts Youth Radio Club have started work on a transmitter and receiver for the proposed novice bands.

At Pt Augusta Youth Radio Club some of the senior class are learning Morse code under the guidance of Mr Don Martin, ex VK9DM.

The Third Adelaide Boys Brigade Club have only a small number of boys this year but the interest is strong. Instructor Mr Mike Bloodworth, VK5LX says that there may be an elementary certificate candidate in the near future.

Elizabeth Youth Radio club members have been busy making up one transistor amplifiers using veroboard construction. These will be used to increase the volume from their crystal set projects. Club members are given the opportunity of purchasing the completed projects.

Pt Pirie Youth Radio Club are working on their new clubrooms. Water and power are yet to be completed but most of the benches for practical work are in position and the tables and chairs repaired and painted.

## NEW SOUTH WALES Maitland Radio Club


The erection of the Maitland Radio Club's new 22 metre high tower was featured in the Maitland Mercury. The local TV channel NBN 3 also screened it as part of the regional news segment. The task was carried out by the Hunter Valley County Council.

On top of the tower is a 146MHz ground plane antenna, other VHF antennas will be installed at various levels. Between the two towers now installed a multiple dipole system of HF aerials will be erected. Although self-supporting, a set of stabilising wires have been fitted, these are insulated from the tower and ground and will also be used as receiving aerials for class built projects.

# IONOSPHERIC PREDICTIONS FOR AUGUST

Reproduced below are radio propagation graphs based on information supplied by the Ionospheric Prediction Service Division of the Commonwealth Bureau of Meteorology. The graphs are based on the limits set by the MUF (Maximum Usable Frequency) and the ALF (Absorption Limiting Frequency). They have been prepared for the four most popular amateur bands over a number of interstate and international circuits. Black bands indicate periods when circuit is open.

8.73



A new 30 watt sound system built by members has been installed in the club theatre. This will provide high quality sound reproduction in the social section of the club. Work has also been done on a two metre transmitter and receiver to be used for class instruction.

Technical films are now a feature of the instruction classes. These are shown at the conclusion of the theory section class each night.

Inquiries about club activities may be obtained from the Secretary, PO Box 54, East Maitland, 2323 NSW.

## Westlakes Radio Club

The Westlakes Radio Club issues handsome certificates to members who show prowess in medium-wave and short-wave listening. These certificates are not difficult to win. They are also issued to non-members, when a fee of 60 cents is charged.

To gain the Broadcast Ten the listener must receive QSL cards from stations in the medium-wave band in the following schedule.

Four stations in New South Wales.

Three stations in any of three other states of Australia.

Two stations in New Zealand (one from each island) or one from New Zealand and one from New Guinea. One station from any other country outside Australia, New Zealand and New Guinea.

To gain the Short-Wave Ten, the listener must have received verifications cards or letters from two stations in each of the five continents, Europe, Asia, Africa, North America and South America.

Each station must be in a different country.

For purposes of the award, Great Britain, Japan and other island countries are considered part of the continent to which they are adjacent.

If your interest lies within the amateur band activities then amateur radio QSL cards for these areas will be accepted. Either short-wave or amateur station QSL cards will be accepted, but a mixture will not be acceptable.

To gain the awards, applicants should present their verifications to the secretary.

For information on all activities of the club write to Secretary, Eric Brockbank, VK2ZOP, PO Box 1, Teralba 2284, NSW.

## SO YOU WANT TO BE A RADIO AMATEUR?

To achieve this aim, why not undertake one of the Courses conducted by the Wireless Institute of Australia? Established in 1910 to further the interests of Amateur Radio, the Institute is well qualified to assist you to your goal. Correspondence Courses are available at any time. Personal classes commence in February each year.

For further information write to:

**THE COURSE SUPERVISOR, W.I.A.**  
14 ATCHISON STREET,  
CROWS NEST, N.S.W. 2065





AMPLIFICATION

COMMUNICATION

ELECTRONICS

RADIO

PHONE 51-3845

51-7008

136 VICTORIA RD., MARRICKVILLE NSW 2204

136 VICTORIA ROAD, MARRICKVILLE — 51-3845

**KAISE**

MODEL SK-100

**VOLT-OHM-MILLIAMMETER**HIGH SENSITIVITY  
100,000 Ohms per Volt DC  
10,000 Ohms per Volt AC**SPECIFICATIONS:**

- DC Volts: 0.6, 3, 12, 60, 300, 600, 1200.
- AC Volts: 6, 30, 120, 300, 1200.
- DC Current: 12uA, 300uA, 6mA, 60mA, 600mA, 12A.
- AC Current: 12A.
- Resistance: 20K ohms, 200K ohms, 2M ohms, 20M ohms.
- Decibels: Minus 20 to plus 17, 31, 43, 51, 63.
- Accuracy: DC plus minus 3pc, AC plus minus 4pc (of full scale).

- Overload Protected by dual silicon diodes.
- Double jewelled plus minus 2pc Meter.
- Plus minus 1pc temperature-stabilised film resistors.
- Polarity changeover switch.
- Scale with mirror.

Price \$34.75

Post 75c. Interstate \$1.00.

MODEL SK-20  
20K OHMS PER VOLT DC  
10K OHMS PER VOLT AC**SPECIFICATIONS:**

- DC Volts: 0.25, 2.5, 10, 50, 250, 1000.
- AC Volts: 10, 50, 250, 1000.
- DC Current: 50uA, 25mA, 250mA.
- Resistance: 7K, 700K, 7 Meg.
- Decibels: Minus 10 cps plus 22 (at AC 10V) plus 20 cps plus 36 (at AC 50V).
- Upper freq. limit 7 Kc.

OVERLOAD PROTECTION  
\$13.50MODEL SK-44  
30K OHMS PER VOLT DC  
10K OHMS PER VOLT AC**SPECIFICATIONS:**

- DC Volts: 0.6, 3, 12, 60, 300, 600, 1200, 3000.
- AC Volts: 6, 30, 120, 300, 1200.
- DC Current: 30uA, 6mA, 60mA, 600mA.
- Resistance: 10K ohms, 1 M ohms, 10 M ohms, 100 M.
- Decibels 20 cps plus 17, 31, 43, 57, 63.

OVERLOAD PROTECTION.  
SPECIFICATIONSPost 50c Interstate 75c.  
\$19.25MODEL SK-140  
20K OHMS PER VOLT DC  
10K OHMS PER VOLT AC**SPECIFICATIONS:**

- DC Volts: 2.5, 10, 50, 250, 1000.
- AC Volts: 10, 50, 250, 500, 1000.
- DC Current: 50uA, 25mA, 250mA.
- Resistance: 40K, 4 Meg.
- Decibels: Minus 20 db cps plus 62db.

Post 50c, Interstate 75c

**BENDIX BC-221**Frequency Meter, 125Hz — 20 MHz.  
Complete with Calibration Book and  
1000Hz Crystal. Good order. \$35.00.**EX-DISPOSALS  
RADIO EQUIPMENT TO  
CLEAR AT BARGAIN  
PRICES.**

FIS


- 522 TXXR 100-150 mcs \$17.50
- TR 1934 TXXR 100-125 mcs \$12.50
- TR 1935 TXXR 100-155 mcs \$17.50
- No. 62 TXXR \$35.00
- 3" Indicator / Receiver Unit  
type APN — 93API Cro-plus 33  
useful Valves. \$15.00
- Marconi Video oscillator model  
TF885A \$40.00
- AWA R-F signal generator 140-  
300 MHz \$40.00
- Command receiver QSer, 190-  
550 \$15.50
- AWA harmonic generator with  
xtals. Type 10A 50065 \$35.00
- AWA time base marker  
generator, type A51940 \$20.00
- Electro statio voltmeter, 0-5000  
V \$30.00
- AR7 receiver with S meter and  
valves but no coil boxes or  
supple \$20.00
- 6" x 6" steel carry cabinet \$2.00
- Plessey C42 TXXR with 24V  
supple \$59.00
- 1/2" x 1/4" 72 OHM CO-AX cable  
end or stock, per yd .10
- Multi strand PVC covered cable,  
7 core, per yd .15
- 14 core, per yd .35
- Twin shielder PVC, fabric  
cover, per 10 yds .90
- Single core shielded cable per 10  
yds .75
- Command transmitters \$7.50
- 12 volt solenoid relay, 4 change  
over, 10 AMP contacts \$1.50
- 5 digit counter relays, 500 OH-  
M \$1.00
- 3" flush mt. panel meter, 0-50  
MA \$2.00
- 3" S meter 0-1 MA \$2.75
- Dynamic headphone and mkc.  
50 ohms \$2.50
- Mini battery operated motors  
1 1/2-3 volts. Each .50
- Box of ten \$3.50

**P.A.  
AMPLIFIERS**

Rugged and dependable — standard  
valve circuitry. Two Hi-imp inputs suits  
either mic. or PU. Each input has a  
separate volume control, which enables  
electronic mixing — Bass / Treble tone  
control. Amplifiers available with multi-  
tapped line matchings (66, 100, 125, 250,  
600 ohms). On ordering please stipulate  
the matchings required.  
Operation 240 VAC 50Hz

4 Ratings available.

15 Watts rms	\$53.50
30 Watts rms	\$63.50
40 Watts rms	\$89.50
60 Watts rms	\$139.00

**P.A. SPEAKERS  
8 WATT**

8 in units in waterproof  
projection horns.  
15-Ohm voice coils  
Price \$18.95

**MICROPHONE  
STANDS**

Floor Model 6ft adjustable with heavy  
weight cast iron base.  
\$12.75

Goose necks 12"	\$3.95
18"	\$4.95
24"	\$6.00

**ROLA SPEAKER**

12 peg 12" 30 watts, R.M.S. fund  
resonance 80 Hz response — 55-9000 Hz  
15.0 OHMS.  
\$13.50 P & P \$1.00.

**P.A. SPEAKER  
COLUMNS**

Good frequency response, top quality  
reproduction two models available. The  
45 Watts RMS has four 8" heavy duty  
speakers. Cabinet size 37" x 11 1/2" x  
10 1/2". \$49.50. The 25 Watts RMS has four  
6" heavy duty speakers. Cabinet size 33"  
x 10" x 10" \$37.50.  
The columns are suitable for indoor or  
outdoor use — floor or wall mounting.  
Cabinets are covered with black vinyl.  
Imp 8 or 16 ohms.

**CABLE**

Twin speaker Flex. \$5.50 per 100 yds. P &  
P 70c. Low loss Mic cable. Single core  
15c per yd. Twin core 25c per yd.

**AUDIO GENERATOR**

De Luxe Model TE — 22D

Freq range, Sine 20 cps — 200KC SQ, 20  
cps — 25KC. Output Voltage Sine 7V SQ  
TV PP Output Impedance 1000 ohms  
Acc. 5 per cent 4-range attenuation.  
1, 1-10, 1 100, 1 1K. Printed circuit 240V  
AC.

\$42.45

**SIGNAL GENERATOR**

De Luxe Model TE20D

Freq Range 120 KC — 500 Msc 7 Bands.  
Accuracy 2 per cent. Output 8V.  
Provision for Xtal. Suitable for self  
calibration Marker generator. Printed  
circuit 240 VAC.

\$36.75

**MODEL TE-65  
V.T.V.M.**

DC V 0.1, 5.5, 15 50, 500, 1,500 V Rms.  
ACV 0.15, 5.5, 15, 50, 150, 500, 1,500 V Rms  
0.4, 4.4, 14, 400, 1,400, 4,000 V PP  
Resistance: RX10, 100.1K, .10K, 100K,  
1M, 10M, Decibel — 100dB minus plus 65  
dB.

240 VAC  
\$43.75**WIDE BAND  
OSCILLOSCOPE**

VERTICAL AXIS

Deflection sensitivity (at 1KHz) 0.1Vp-P  
cm.

Frequency characteristics: 1.5Hz to  
1.5MHz.

Input Impedance, 2 M ohms 25pF.  
Calibration Voltage 1V p-p cm.

HORIZONTAL AXIS

Deflection sensitivity 0.9V p-p cm  
Frequency Characteristics, 1.5Hz to  
800KHz.

Input Impedance 2 M ohms 20pF. Sweep  
Oscillator (5 range): 10Hz to 300KHz.  
Synchronisation Devices Internal  
(Positive and Negative, external).  
Power 240V AC 50 60 cps. Cathode-ray  
tube 3KFIF.  
\$135.00 plus 15% sales tax.

**E.A. PROJECTS**

21 Watt PA Amplifier June '72 Kit	\$57.00
Constructed Ready for use	\$47.00
PM 135 PA Amp Aug '72 Kit	\$47.50
Wired & Tested	\$57.50
21 Watt Guitar Amp Oct '72 Kit	\$49.00
Wired & Tested	\$59.00
We Guarantee all parts to be A1 quality and New.	
Pack & Post \$2.00.	



## 50 WATT SOLID STATE GUITAR AMPLIFIER



50 watts RMS solid-state guitar amplifier. PA125 4 inputs, 2 channel with separate volume, bass and treble controls; speed and intensity controls for vibrato. Remote foot switch with plug and lead. Black vynex carry cabinet.

Fully constructed and ready for operation off 240VAC \$125.50

## GUITAR SPEAKER CABINET

Upright floor model, black vynex covering, 34" x 18" x 12", sloping front, contains innerbond packing and two Rola 12u50 12" speakers.

\$115.00

## 15" PIONEER

15in Pioneer low frequency speaker, imp 16 ohms. Power, 30 watts RMS designed especially for use with bass guitar or electric organ. Also ideal for stereo woofer speaker.

\$33.00

## ROLA 50 Watts R.M.S. LOUDSPEAKERS

Model 12U50 Bass \$35.00  
Model 12UX50 Extended Frequency \$40.00

P & P \$1.50

## PLAYMASTER 136 STEREO AMPLIFIER



As per Dec 72 E / A  
Full kit including fairchild transistors \$62.50  
Fully constructed and tested \$75.00  
Metal work only \$7.65  
P.C. boards \$8.00

## REVERBERATION UNITS

Freq. response. 60-3000 Hz.  
Decay time 1.5 seconds.  
Dimensions 4 3/4" in x 9 1/2" in x 1 3/4" in  
\$6.95 P & P 50c

## SPECIALS

Plessey SL — 403D 1—C Units \$4.50 EA.  
Brands 5.7" 1800 FT Mylar \$3.50, 3600 ft 7" Mylar \$4.50, Cassettes BASF soft pack C60 \$1.35, Brand 5 C60 plastic pack 90c Brand 5 C90 plastic pack \$1.70 8 OHM 3" pillow phone in plastic housing works with tranny or cassette. \$2.50.  
Crystal lapel Mic \$2.00, Crystal contact Mic \$3.00, Burglar alarm. Extra loud squaker — suit car or home. Battery operated. \$1.75.

## STEREO RECORD PLAYER


240V AC — 4 speeds, ceramic cartridge. Separate motor, 7in turntable, pickup arm and rest. Post 50c.  
\$7.90

## MAGNAVOX WIDE RANGE TWIN- CONE SPEAKERS

8 — 16 OHMS  
30 — 16,000 Hz  
6WR MK5 12-W RMS \$9.90  
8WR MK5 16-W RMS \$10.75  
10WR MK5 16-W RMS \$11.50  
12WR MK5 16-W RMS \$12.50

Pack and Post 65c.

## SONATA GUITAR AMPLIFIERS



2 channels, 4 hi-imp inputs, 2 separate volume controls — separate bass and treble controls, speed and intensity controls for vibrato (tremolo) with remote foot switch with plug & lead. Attractive black vinyl covered carry cabinet.

8" heavy duty speakers  
20 watts RMS \$93.00  
35 watts RMS \$129.00

## M.S.P. 8-15 OHMS


Latest Model Speakers  
LF — 6WAC 6" \$10.50  
LF — 6WACX 6" twin \$11.50  
4MBC TWEETER \$4.50  
12PQC8 / 30 30 watts \$22.95  
8TACX 8" twin \$9.75  
12 PQ 15 OHM only \$15.95 2 MBC tweeter \$4.50.

## OVAL SPEAKERS

9" x 6" 3.5, 8 or 15 OHMS \$4.95  
7" x 5" 8 or 15 OHMS \$5.75  
7" x 4" 8 or 15 OHMS \$4.75  
6" x 2" 8 or 15 OHMS \$4.25  
5" x 3" 8 or 15 OHMS \$3.75  
4" x 2" 8 or 15 OHMS \$3.50

## STEREO RECORD CHANGERS

C129 — C141 — C142 — C142A3



Current models, 4 speeds, automatic or manual operation.

Ceramic cartridge, Sapphire stylus. Standard model with 12in turntable. \$34.00

Deluxe model with 12in turntable, Cueing device, ceramic cartridge, diamond stylus \$40.00

Deluxe model as above with an adjustable counter balance, 2 spindles, calibrated stylus pressure control added \$46.50

Deluxe model as above with 12in Diecast Heavyweight turntable, 4-pole shielded motor, suitable for Magnetic cartridge \$56.50

The latter two record changers can be supplied with magnetic cartridge and diamond stylus at \$10 extra.

## PERSPEX COVER

Smoke Tinter 17 1/4" x 13 1/2" x 4 1/2" \$9.00, P & P 60c  
Pre Cut Mounting Platform Teak and Walnut 18 1/4" x 15" x 3 1/2" \$11.50, P & P 75c.

## Top Quality padded stereo phones



Delux model with slide volume controls 18,20,000HZ 8 OHMS Special price offer. \$7.90. Standard model, 20-12,000HZ. 8 OHMS, \$4.70 P & P 40c.

Famous Zennheiser HD 414 \$25.95

## SOLID STATE FOUR TRACK CASSETTE STEREO TAPE DECK

240V 50 Hz operation, 2 V-U meters piano key push buttons. Record and erase facilities. Pause. Mic input 200 OHMS. Line input 300K OHMS. Output IMP 10K OHMS S/N ratio better than 40 dB. Crosstalk better than 50 dB T TO T 25dB CH to CH freq 50 — 10,000 Hz size 2 1/2" x 12 1/2" x 9 1/2" WT 7 lbs.  
\$132.50.  
P & P \$2.50.

## Rotating Distress Emergency Beam



Fire Brigades and Rescue squads use them. So do Car, Truck and BOAT OWNERS WHO VALUE THEIR SAFETY. At home on party nights, have a light show. Red, Blue, Amber — visibility 1/2 mile. 12v DC 1 amp operation, waterproof. Complete with heavy duty suction cap. Size 3 1/2" dia. x 5 1/2" \$5.75. Pack and post 35c.

## SONATA NS-1600D



All silicon solid-state Hi-Fi Stereo Amplifier. 10 watts RMS per channel. Each channel has separate Bass Treble controls. Inputs for magnetic or ceramic cartridge, crystal mic., radio, tape — tape out; stereo headphones. 8 — 16 ohms. Instruction booklet, circuit supplied. Timber cabinet. Dimensions: 14 1/2" x 8" x 4".

\$47.50 Plus Freight \$2.50

## GARRARD

Stereo Changer. Model SL 65B. 3 Speed Auto. Aluminium turntable. Cue & pause control. Counterbalanced bias compensated. Syn-motor, with ceramic cartridge, diamond stylus. \$88.00. P & P \$1.50.

## STEREO PLAYER

MODEL SP 25MK 111 3 Speed. 4 pole motor. Aluminium turntable. Fully balanced & CALIBRATED P.U. arm. Bias comp. cue & pause control. Click suppressor. Auto. Set down. Excluding cartridge \$55.00. P & P \$1.50. Also available.

Garrard-Zero 100 \$177.80.

Garrard SL72B \$97.00

Mounting base with perspex cover \$23.80.

Dual 1214 \$88.00.

Dual 1216 \$110.00.

Dual 1218 \$140.00.

Mounting base & cover \$29.00.

Cartridge not included mag cartridge available to suit all models. Extra \$10.00.

Send S.A.E. for specs any model.

## AIWA COMPACT CASSETTE CAR STEREO

Complete with speakers. 12 volt neg. Ground operation Starr Capstan drive. Output 5 Watts per CH. Freq response 50-10,000 Hz Tape Speed 4.8 CM / P. SEC S/N Ratio Better than 45dB, \$112.00, P & P \$2.50.

## MAGNAVOX 8 / 30 SYSTEM TEAK OR WALNUT



1.6 cft complete \$50.00 ea.  
8.30 Speaker \$16.50 ea  
3TC \$3.40 ea  
Fully built cabinet \$32.00 ea.  
Cabinet kit \$22.00 ea

## MULLARD MAGNAVOX BOOKSHELF SYSTEM TEAK OR WALNUT

6WR MK5-3TC 8 or 16 ohms 15 1/2" x 8 1/2" x 8 1/2" complete \$31.50 ea.  
Cabinet only \$13.90.

## Sonata NS — 1600



All Silicon Solid State Stereo Amplifier 240V AC powered 8 watts RMS per channel inputs for magnetic ceramic, and crystal cartridge, also recorder and radio tuner, Hi-Fi frequency response speaker matching 4-16 ohms. Size 10 1/2" in x 6 1/2" in.  
Attractive oiled teak cabinet.  
Price \$54.00  
P & P \$1.50, Interstate \$2.50.





# LISTENING TO THE WORLD

by Arthur Cushen, MBE

Listeners often receive a pleasant reward for their listening efforts in the form of cards verifying their reception reports. In recent weeks a variety of interesting countries have been represented in the mail received by some of our readers.

A relatively new listener, sending reports to the better known international broadcasters generally receives a prompt reply by airmail to his report. When he turns his attention to the lower powered stations he may become frustrated at the delays in receiving verifications, particularly from South America. However, the rewards are worth waiting for. One of our readers Chris Davis of Featherston, NZ has had considerable success from this part of the world, with eight verifications out of 22 reports; this is a good percentage for this area. Registered mail, return postage and the inclusion of mint stamps are some of the ways in which one can motivate the station to verify. Chris Davis now has 92 verifications from this area, many from low power stations. Our own verifications from South America total 315 from every country on this continent.

**BOLIVIA:** Radio Nacional, Cochabamba has verified to Chris Davis of Featherston, NZ with a letter in English concerning his report on 5975kHz at 1030GMT. The letter stated that the broadcasts at that time were in the local Indian dialect; all stations in Bolivia must devote three hours of their program each day to the minority group. The letter was signed by Jimmy Christie, Engineer, Radio Nacional, Cochabamba, Casilla No. 526, Cochabamba, Bolivia.

**AZAD KASHMIR:** A verification card has been received from Azad Kashmir on 4732kHz by David Foster, Kew, Vict. The card, brown in colour, was signed by the Station Manager. This is one of the few verifications from this station received in Australia. **SYRIA:** Damascus using 9655kHz for its general overseas service has verified for Bob Padula, Melbourne, Victoria with a multicoloured card showing a map of the world. They also sent along a badge with the insignia of the station. Damascus has been a "non-verifier" for several months and this news will be welcomed by those who have recently written to Syria.

**HONDURAS:** Radio Juticalpa on 4780kHz was heard at 1030GMT and verified for Chris Davis with a letter in English. The transmitter is 1000 watts on this frequency. As well as the letter, they enclosed a large gold and green pennant.

**CHILE:** Radio Corporacion on 6190kHz verified a report in Spanish in 14 days in response to a letter from Chris Davis. This was a coloured post-card of a tourist attraction near Santiago. The verification stated that they had two other transmitters CE 950 and CE 1515 also in operation. Our own verification of CE 1515 was in the form of a pennant. It is one of the largest we have ever received, but it was issued by the station over 20 years ago and shows an eagle sitting on top of the microphone.

**HONDURAS:** Radio Progreso was heard on 4920kHz at 0430GMT and verified for Chris Davis with a letter in Spanish which gives the power on this frequency as 1500 watts. The address is Apartado 20, F1 Progreso, Yoro, Honduras. As well as the letter, a pennant in green, black and white was also received.

## VQ09 on 9545kHz

The Solomon Islands Broadcasting Service is using a new frequency for its lunch-hour transmissions. The transmission commences at 0111GMT on 9545kHz with the usual drumbeats and ends at 0300GMT after the lunch-time program. Two Wellington listeners John Mainland and Bryan Clark report reception of this new service, but interference has been noted from Deutsche Welle at Cologne, which also uses the frequency from 0130 to 0250GMT. This means that the Solomon Islands station can only be heard free from interference from 0111 to 0130 and for the last ten minutes

of the transmission. According to a verification received from the station, the call sign is VQ09. The report from John Mainland was the first they had received on the new frequency.

## BRUNEI ON 7215kHz

Good reception is being experienced of Radio Brunei on 7215kHz from as early as 1000GMT when programs in Chinese are being broadcast. At 1400GMT, during the English program, a full identification is given; local time is 10 pm.

According to the latest schedule in the ADXN the station is operating on 4855kHz as follows:

GMT	Language
2200-0600, 1100-1430	Malay
On 7215kHz	
2258-0030, 0300-0500, 1200-1430	English
0030-0300, 0800-1100	Chinese
1100-1200	Gurka

The power on both frequencies is 10kW, according to a verification received by Geoff Cosier of Burwood, Vic.

## ENGLISH FROM BEIRUT

Radio Lebanon has three transmissions to overseas audiences, and two of these include 30 minute broadcasts in English.

In the service to North and South America from 0130-0400GMT the frequency of 11790kHz is now used, and English is broadcast from 0230-0300GMT. The service to Europe and Africa from 1830-2030GMT is on 15170kHz with English from 1830-1900GMT. The third transmission is to South America and is broadcast from 2300-0100GMT on 15355kHz. Reception on 11790kHz is very good during our afternoons, while the broadcast at 1830GMT is received at fair strength. The transmission on 15355kHz is blocked by Radio Australia after 0030GMT, but before this time reception is possible.

## MENDI ON 3275kHz

The latest station to commence operation in Papua New Guinea is Mendi using 3275kHz. The station uses the slogan "Radio Southern District" and is heard opening at 0800GMT. Our reception of the signal has been best around 1000GMT when news in Pidgin is broadcast.

The remaining stations to commence operation this year in Papua New Guinea are Alotau (3360), Port Moresby (3925), Kavieng (2428), Vanimo (3205), Lorangau (3905) and Kimbe which has not yet been assigned a frequency.

## SPLIT FREQUENCY RECEPTION

One of the most interesting aspects of long distance medium-wave reception is the use by stations of "split" frequencies which are not multiples of 10. This enables the listener to hear broadcasts over many thousands of miles. Around dawn the Europeans can be received and as they use a 9kHz separation, they come up on the dial between the Australian and New Zealand stations.

In the evenings in New Zealand we are also enjoying reception on split frequencies from stations in Central and South America. The best received signals include Radio Nacional Lima (844kHz), Radio Colosal, Neiva, Colombia (1025), Radio Nacional Caracas, Venezuela (1055), Radio Paradise, St Kitts (1265), while WXLE on Canton Island in the Pacific is heard on 1385kHz. Many other signals are heard around dusk in New Zealand on

split frequencies but identification is difficult due to television receiver interference on some of the channels.

## THE PEACE SHIP

After being fitted out at New York and testing on 1540kHz off the coast of the United States (when an appeal was made for financial support) Abe Nathan's Peace Ship has arrived in the Israel area. The ship had a hard voyage across the Atlantic and, after putting into Marseille for repairs, it took up its anchorage 4 miles off the coast of Famagust in Cyprus.

The station is now in regular operation on 1540kHz, broadcasting in French, English and Italian from 1930 to 2115GMT. The English program of popular music conducted by former Radio Caroline disc jockey, Tony Allen, is reported from listeners in Europe who give the mailing address as Voice of Peace, PO Box 1010, Nicosia, Cyprus. The station eventually plans to broadcast in Hebrew and Arabic and try to do its part in resolving the Middle East crisis.

## COUNTRIES CHANGE NAMES

In the next few months several countries will make a name change and two in New Guinea will be of greatest interest to us. Papua and New Guinea is to be changed to the Pidgin name for the country, New Gune. The neighbour, the former Dutch New Guinea to the west, was changed to West Irian and now has been named Irian Jaya.

The Philippines is also scheduled to make a name change and will be known as Mahasika. Ceylon is getting to be known as Sri Lanka, though the radio is still identified as Radio Ceylon, and few signs of a change are noted in external services. Bangladesh is accepted as the former East Pakistan, while the former Belgian Congo, and later Congo (Kinshasa), is now known as Zaire.

## THE VOICE OF HOPE

Adventist World Radio, which uses the slogan "Voice of Hope" broadcasts to Europe over the facilities of Radio Trans Europe. Their block programmed segments have been on the air every day since October 1, 1971.

From the studios in Lisbon, Portugal, their signal is carried by VHF signal to the RTE relay station at Sesimbra, 35 kilometres south of the city. Another VHF link conveys the signal to the transmitter site at Sines, 85 kilometres south of Lisbon.

At Sines the powerful 250,000 watt Marconi transmitter thrusts the Voice of Hope to preselected areas of the European part of the world. The signal also reaches parts of North Africa, the Middle East and Russian Asia.

All responses to their programs are processed at the language center in the country where the program was produced. Nearly a dozen such centers are involved, in addition to the Lisbon AWR studio. Adventist programs also blanket the rest of the world from a variety of radio outlets including FM, medium and short-wave stations.

Recently the station added an additional program in English which is broadcast at 0945GMT on Sunday. This new time follows the English program at 0930 which contains DX News and other station information. The DX Session is also heard on Sunday at 0500GMT on 9640kHz, while the transmission at 0930 is on 9670kHz.

Recently the station offered an EP recording to its listeners and already 3,000 of these have been posted out. A further pressing of the 6-language music disc is available to listeners who report on the reception of the Voice of Hope and send their requests to The Voice of Hope, Box 5409, Paris 9, France.

## MEDIUM-WAVE NEWS

**NEW ZEALAND:** The seventh private commercial station has been licenced to operate from Wellington by the Broadcasting Authority. It is expected that this will be the last private station to be licenced, due to a change in the Government policy.

The new station will broadcast from 1730-1200GMT daily, and from 1830-1100GMT on Sunday. Two competing radio companies combined (Radio Wellington and the Hutt Wellington Broadcasting Company) and after finding a new transmitter site to which the NZBC did not object the licence was granted. The station is expected to commence operation on November 1st, on 1080kHz using 5kW.

**HAWAII:** The new Honolulu station KISA on 1540kHz has been heard opening at 1600GMT with all programs in Tagalog with English announcements for station identification only. Frank Wilson of Dunedin NZ has verified KISA: his report was the first received by the station from anyone, so he can lay claim to be the first in the world to verify KISA.

Continued on Page 125

Notes from readers should be sent to Arthur Cushen, 212 Earn Street Invercargill, New Zealand. All times are GMT. Add 8 hours for WEST, 10 hours for EAST, and 12 hours for NZ.



# POCKET CALCULATORS from \$59.95

plus 15%  
sales tax

ONE YEAR WARRANTY (Incl. parts & labour) BATTERIES LAST UP TO 150 HOURS



1200 SERIES  
POCKET CALCULATOR

**MODEL 1440 DESK CALCULATOR**, addition, subtraction, multiplication, division, squaring, square root, constant data memory, independent data memory, exchange operands key, ability to enter negative numbers, etc. 14 digit LED display. Price: Kit \$209.95 assembled \$249.95 + 15% Sales Tax. External printer and programmer available soon.

**MODEL 7400 ADVANCED SCIENTIFIC CALCULATOR** 200 decade calculating range, 2 memories plus up to 7 stack registers, addition, subtraction, multiplication, division, 14 digits of mantissa (10 digits displayed plus 2 digits exponent) sine, arcsine, cosine, arccosine, tangent, arctangent, degree to radians, radians to degree, polar form to rectangular form, rectangular form to polar form. etc. 14 digit Sperry display. Price: Kits from \$329.95. Assembled from \$379.95 + 15% Sales Tax.

External printer and programmer available soon.

Students are eligible to purchase this calculator Tax free, ask for our exemption form.

**MODEL 1240 DESK CALCULATOR** four functions plus one memory register with 4 separate controls, can be added to, subtracted from, recalled to display or cleared without clearing the calculator. 12 digit Sperry display. Price: Kit \$119.95 assembled \$139.95 + 14% Sales Tax.

## Nematic and Cholesteric Liquid Crystals

We are Australian Sole Distributor for the largest US Manufacturer of LIQUID CRYSTAL PRODUCTS. We are offering a very large range of chemicals, conductive coated glass, Thermo film for temperature measurements which indicates temperatures by brilliant colour changes, Piezo-Optical Kits, laminated, polarizing, conductive coated glass, etched and finished to your specifications, storage type LIQUID CRYSTALS for both electronically and thermal (IR) addressed display applications, negative and positive dielectric LIQUID CRYSTALS.

A technical catalogue on LIQUID CRYSTAL PRODUCTS will be available shortly.

555 TIMERS	\$1.50 + A
309K 1 A VOLTAGE REGULATOR	\$2.50 + B
LM 308 OPERATIONAL AMPLIFIER	\$2.00 + B
LM 380 2W AUDIO AMPLIFIER	\$2.20 + B
7490 DECADE COUNTER	\$1.20 + A
74192 UP-DOWN DECADE COUNTER	\$3.50 + A
7475 LATCH	\$1.30 + A
7447 7-SEGMENT DECODER	\$1.98 + A
74121 MONOSTABLE MULTIVIBRATOR	\$0.91 + A
7441 BCD DECODER	\$1.85 + A
7400 SERIES GATES	\$0.60 + A
SCHOTTKY IC's FROM	\$1.00 + A
TUNNEL DIODES	\$1.00 + B
LARGE RANGE OF LED'S FROM	\$0.48 + A
6-DIGIT DIGITAL CLOCK CHIPS	\$18.20 + A
CALCULATOR CHIPS FROM	\$16.50 + A
PHOTO DARLINGTON AMPLIFIER	\$1.00 + B

INFRARED FILTER AND LENS	\$0.85 + B
LIGHT ACTIVATED SCR's	\$1.55 + A
25A, 600V TRIAC	\$4.80 + A
MICRO REED SWITCHES	\$0.30 + A
10 MHz CRYSTAL 0.0015%	
with circuit (5 volt)	\$6.50 + A
MOLEX IC SOCKETS per 100	\$1.20 + A
MAN-1 DISPLAY (LED)	\$4.55 + A
MAN-3A DISPLAY (LED)	\$3.60 + A
MINITRON DISPLAY	\$3.20 + A
FLUORESCENT DISPLAY	\$2.95 + A
NIXIE DISPLAY	\$2.95 + A
SPERRY DISPLAY	\$3.40 + A
QUARTZ CONTROLLED TIME STANDARD	
WITH 27 OUTPUT FREQUENCIES	\$26.50 + A
WIRED DECADE COUNTERS WITH LATCH,	
BCD OUTPUT, MAN-1 DISPLAY etc.	\$13.50 + A
35 W RMS POWER AMPLIFIER MODULE	\$10.50 + B
FLAT TO 100KHz, short circuit proof	
LARGE RANGE OF FIBER OPTICS,	
FIBER OPTICS DISPLAY KITS	
COLOURED FIBER OPTICS	
LARGE RANGE OF DIFFRACTION GRATINGS	
POLARIZING MATERIAL	
DIGITAL IC TESTER	
DIGITAL CLOCK KITS	
CONDUCTIVE FOAMS FOR MICROWAVE ABSORPTION	
CONDUCTIVE RUBBER MATTS FOR WORKBENCHES	
IDEAL FOR MOS LSI's	
DIGITAL STOPWATCH FROM 100ns to DAYS	
TECHNICAL CATALOGUE WITH MORE ITEMS AVAILABLE	
FREE OF CHARGE. PLEASE PRINT NAME, ADDRESS AND	
INCLUDE POSTCODE	

A — 15% Sales Tax, B — 27 1/2% Sales Tax



**W.H.K. ELECTRONIC & SCIENTIFIC INSTRUMENTATION**

POSTAL ADDRESS: PO BOX 147, ST ALBANS, VICTORIA, AUSTRALIA 3021



## NEW RH (Radio House) RANGE OF MULTIMETERS

### MODEL RH-60 \$29.00 Packing & Postage \$1.00



50,000 Ohms per Volt DC.  
10,000 Ohms per Volt AC.  
**Specifications:**  
DC Volts: 0.25, 2.5, 10, 50, 250,  
500, 1000.  
AC Volts: 10, 50, 250, 500,  
1000.  
DC Current: 25uA, 5mA,  
50mA, 500mA  
Resistance: 10K, 100K, 1M,  
10M.  
Decibels: -10 +62dB.  
Accuracy: DC  $\pm 3$  p.c., AC  
 $\pm 4$  p.c. (of full scale).  
Batteries: Two 1.5V dry  
cells. Overload protected.

### MODEL RH-100 \$39.75. Postage \$1.00

100,000 Ohms per Volt DC 10,000 Ohms per Volt AC

• Overload-protected by dual silicon diodes • Double-jewelled  $\pm 2$  per cent meter •  $\pm 1$  per cent temperature-stabilised film resistors • Polarity changeover switch • Mirror scale • Instructions for operation with circuit diagram.



#### SPECIFICATIONS:

DC Volts: 0.6, 3, 12, 60, 300,  
600, 1200 (100,000 / V).  
AC Volts: 6, 30, 120, 300, 1200  
(10,000 / V).  
DC Current: 12A, 300A, 6mA,  
60mA, 600mA, 12 amps. AC  
Current 12 amps.  
Resistance: 20K, 200K, 2M,  
20M.  
Decibels: -20 to +17, 31, 43,  
51, 63.  
Accuracy: DC  $\pm 3$  per cent.  
AC  $\pm 4$  per cent (of full  
scale).  
Batteries: Two 1.5V dry  
cells, size AA, "Eveready"  
915.

### "HANDYMAN" RH150 \$11.50

CHECKED PACKED  
& POSTED \$12.00



Pocket-size  $3\frac{1}{4}$ " x  $4\frac{1}{2}$ " x  $1\frac{1}{4}$ ".  
Instruction sheet and circuit.

#### SPECIFICATIONS:


DC Volts: 2.5, 10, 50, 250, 1000.  
10,000 ohms per volt  
AC Volts: 10, 50, 250, 500, 1000.  
DC Current: .1, 25, 250mA.  
Resistance: 20K and 2M.  
Decibels: -20dB, +62dB, 0.7KHz.  
Capacitance: .0001, .01, .0025, .25uF

### MODEL RH-20 \$15.00 Packing & Postage 75c



20,000 Ohms per Volt DC.  
10,000 Ohms per Volt AC.  
**Specifications:**  
DC Volts: 0.25, 2.5, 10, 50, 250, 1000.  
AC Volts: 10, 50, 250, 500, 1000.  
DC Current, 50uA, 25mA, 250mA.  
Resistance: 7K, 700K, 7M.  
Decibels: -10, +22 (at AC / 10V) + 20,  
+36 (at AC / 50V). Upper frequency  
limit 7KHz.  
Batteries: Two 1.5V dry cells.  
Complete with test leads

### MODEL RH-80 \$20.00 Packing & Postage 75c



20,000 Ohms per volt DC.  
10,000 Ohms per volt AC.  
**Specifications:**  
DC Volts: 0.5, 2.5, 10, 50, 250, 500, 1000.  
AC Volts: 10, 50, 250, 500, 1000.  
DC Current: 50uA, 5mA, 50mA,  
500mA.  
Resistance: 5K, 50K, 500K, 5M.  
Decibels: -10dB + 62dB.  
Accuracy: DC 3pc.  
AC 4 per cent (of full scale).  
Batteries: Two 1.5V dry cells,  
size AA, "Eveready", 915.

• Overload protected by dual silicon diodes • Double-jewelled  $\pm 2$  per cent meter •  $\pm 1$  per cent temperature-stabilised film resistors • Mirror scale.

## TAPE RECORDERS AT DISCOUNT PRICES

Book type Solid State tape recorder, operated by 2 torch batteries. Mike Records, plays back, erases automatically. Size  $10\frac{1}{2}$ " x  $6\frac{3}{4}$ " x  $1\frac{1}{4}$ ". Complete with mike and tape \$19.75. Post and packing 75c.

When closed looks like a book




SPARE  
REELS  
OF TAPE  
3" REELS  
225 feet 50c.  
3" REELS  
450 feet 80c.



Tape Recorder TC-3000 battery operated model with mike and remote switch and tape \$32.75. With A.C. adaptor for 240V operation. \$45.00 complete. Packed and posted.

$3\frac{1}{4}$ " REELS  
OF TAPE  
200 feet 50c  
300 feet 75c.  
400 feet \$1.00




## RADIO HOUSE PTY. LTD.

306-308 PITT STREET 61-3832 26-2817

760 GEORGE STREET SYDNEY. 211-0171





# ANSWERS TO CORRESPONDENTS

**TOLERANCE:** In most of your projects, you state that the resistors used have "10pc tolerance." Unfortunately, I have trouble obtaining resistors with 10pc tolerance and so use 5pc types. How does this change affect the performance of your projects? Who sells 10pc types? The suppliers I deal with sell only 5pc types. Also, what happened to the "Answer Man." (I.Y., West Cairns, Qld.)

② The whole subject of tolerances is based on the need to specify a component which is sufficiently accurate for the job, but not more expensive than it needs to be. With the exception of some precision projects (such as the Digital VOM in the January issue) 10pc tolerance components — or even 20pc in some cases — are quite adequate.

The lower the tolerance of a resistor, the closer it will be to its marked value. For example, a nominal 1k resistor with a tolerance of 20pc will be 1000 ohms plus or minus 20pc of 1000 ohms. In other words, it may have a value anywhere from 800 to 1200 ohms. The same resistor in a 10pc tolerance will have a value somewhere between 900 and 1100 ohms. A 5pc type 950 to 1050, and a 1pc 990 to 1010 ohms. Most circuits require only 10pc, but there is nothing to stop you using a lower tolerance type should you desire. It can only make things better, not worse. On the other hand, don't expect any shattering improvement in performance; it will be far too subtle to be noticed.

The "Answer Man" column was deleted to make way for other sections of the magazine — such as the Home Study Course, Elementary Electronics, etc.

**DECODER:** I have just finished building the 4-channel decoder described in the November 1972 issue and it has turned out to be a pure delight. I am most happy with it, so much so that I went straight out and bought a new pair of rear speakers. May I ask you how the rear speakers should be phased relative to the front pair? I have carefully watched all connections for polarity as shown on your circuit, but is this enough? Congratulations on an excellent magazine. (L.J., Christchurch, NZ.)

② There is no way to predict the correct connections, to ensure proper phase, in such a situation. We suggest that the front speakers be phased relative to each other, using time honoured methods, and that the rear pair be similarly phased relative to each other. From here on it is largely a matter of subjective judgement as to whether the phase of the rear group is correct with respect to the front group. Trial and error will be necessary, paying particular attention to the bass response as observed in typical listening positions.

**MISTAKE?:** I built the 4 channel decoder described in the November 1972 issue. It is a splendid unit. However, I am wondering if you have made an error in regard to one of the components. At the left rear output, you show a 0.01uF capacitor connected to the collector of TR2, while the right channel shows a 0.1uF in the same position. Should they both be 0.1uF? (L.J., Christchurch, NZ.)

② There is no error, L.J. The capacitors must be of the values shown to obtain the correct phase relationship between the channels.

**CDI:** Can you tell me the difference between a negative and positive chassis CD ignition system as regards coil windings and component placement? I have a 6V positive chassis coil and wish to build a CDI based on that shown in your Nov 71 issue. What changes would I need to make? Is the BT101 500R the same as the BT101 500 as advertised in the same issue? Also, you mention that "if all is well the converter should emit a whistle ... if not swap the base connections and it should start." Can you explain this? (G.N., Greensborough, Vic.)

② Your question is a little too general to answer properly. G.N. There is usually no difference in the coil, but there is in other components. We cannot undertake special research or modifications to existing projects (we do have a magazine to produce!) The BT101 500R is not the same as the BT101 500 — the anode and cathode connections are swapped. We cannot explain the statement much more — it is self-explanatory. If you hear a whistle, the converter is working. If not, one of the windings is probably out of phase and swapping the base connections cures this, by providing the correct feedback polarity.

**STATION LIST:** Your list of broadcasting stations published in the January issue each year is very useful. However as an amateur of long standing, I would like to be able to paste the list on cardboard and hang it on the wall of the shack. At present I can't do this, however, because you print the explanatory notes on the back. Could you arrange things a little more helpfully in future, please? I have been getting your magazine for over 30 years now — keep up the good work. (W.M., Leigh Creek Coalfield, SA.)

② Thanks for the compliment, W.M., and we will see whether we can do as you ask. It is not always possible to layout the magazine to allow for all contingencies, as much as we would like to, but when we know of reader preferences, we can at least try!

**BLINKER:** I need a blinker for a vehicle. The output power would have to be approximately 50 to 60 watts at 12V with a repetition rate of 1 pulse per second. (D.L., Chester Hill, NSW.)

② You have two approaches. The first is to use a rotating distress beacon of the type used by the police and ambulance and available from at least one of our advertisers quite cheaply. The other is to use a standard automotive traffic indicator flasher unit and a suitably rated lamp in an appropriate housing. We have published two articles on electronic flasher circuits, but neither could be called high power. The first was in March 1969 (File No 3 MS 16) and the second in August 1971 (File No 3 MS 26). Copies of both articles are available at the usual fee from our Information Service.

**TA20C AMPLIFIER:** I have built the Playmaster 134 guitar amplifier but have used the TA20C hybrid IC instead of the TA20B. I found that when a chord was played, the signal faded from full volume to no volume after about 3 seconds and then after another 3 seconds it came back to full volume. I am not sure whether it was a quirk of the circuit or a faulty component but I finally cured it by placing a 22uF electrolytic in series with the 47uF electrolytic which is connected via a 1k resistor to pin 7 of the IC. Could you please tell me whether this was a good thing to do and why it helped. (M.M., Belrose, NSW.)

② We are not sure whether you have a faulty IC or not, but either way it seems likely that you were overloading the unit at low frequencies which caused it to cut off for a short period. By adding the 22uF electrolytic you have reduced the low frequency response of the amplifier and thus the likelihood of overload.

**ORGANS:** I have been reading EA for some time, but I haven't as yet sighted a project or circuit for an electronic organ. Could you please tell me where I might be able to obtain such a circuit? (R.B., Freemans Reach, NSW.)

② We described an electronic organ in the early sixties, but parts for this are now rather hard to get. The main reason we are wary about doing another one is that many readers start building, then realise the magnitude of the task and give the game away. An electronic organ is a very big project for the average home constructor. As well as this, many specialised parts have to be obtained. At the moment an organ project doesn't look promising.

## "ELECTRONICS AUSTRALIA" INFORMATION SERVICES

As a service to readers "Electronics Australia" is able to offer: (1) Project reprints, metal work dyelines, photographs, printed wiring patterns and other filed material to do with constructional projects and (2). A strictly limited degree of assistance by mail or through the columns of the magazine. Details are set out below:

**PROJECT REPRINTS:** These cost 50c per issue-reprint. Thus, a project spread over three issues will cost \$1.50. Reprints are available for all projects, but no material can be supplied additional to that already published. Reprints can be supplied more speedily if they are positively identified and not accompanied by technical queries. Material not on file can normally be supplied in photostat form at 30c per page.

**SUBSCRIPTIONS, BINDERS, HANDBOOKS etc:** These are handled by separate department. For fastest service, send separate orders to the departments concerned.

**PHOTOGRAPHS, METAL WORK DRAWINGS:** Original photographs are available for most projects. Price: \$1 for 6in x 8in glossy print. Metal work dyelines are available for most projects. Price: \$1. These show dimensions and positions of holes and cut-outs, but give no wiring details.

**PRINTED WIRING PATTERNS:** We can supply transparencies, actual size, positive or negative, as specified. Price: 50c. We do NOT deal in manufactured boards. These are available from advertisers.

**BACK NUMBERS:** As available. On issues up to six months, face value. Seven months to 12 months, face value plus 5c. Thirteen months or older, face value plus 10c. Postage and packing, 10c per issue extra. Please indicate if a PROJECT REPRINT may be substituted if the complete issue is not available.

**REPLIES BY POST:** These are provided to assist readers encountering problems in the construction of our projects published within the last two years. Note, particularly, that we cannot provide lengthy answers, or undertake special, research or modifications to basic designs. Charge: 50c. Inclusion of an additional fee does not entitle correspondents to special consideration.

**OTHER QUERIES:** Technical queries outside the scope of "Replies by Post" may be submitted without fee and may be answered in the magazine at the discretion of the Editor. Technical queries will not be answered by interview or telephone. **COMMERCIAL EQUIPMENT:** "Electronics Australia" does not maintain a directory of commercial equipment, or circuit files of commercial or ex-disposals equipment etc. We are therefore not in a position to comment on any aspect of such equipment.

**COMPONENTS:** "Electronics Australia" does not deal in electronic components. Prices, specifications, etc should be sought from appropriate advertisers or agents.

**REMITTANCES:** These must be negotiable in Australia, and should be made payable to "Electronics Australia". Where the exact charge may be in doubt, we recommend submitting an open cheque, endorsed with a suitable limitation.

**POSTAGE & PACKING:** All charges shown include postage and packing, unless otherwise specified.

**ADDRESS:** All requests for data and information should be directed to the Assistant Editor, "Electronics Australia", Box 157, Beaconsfield 2015.

(8 / 73)



# MYCALL

27.240 MHZ  
POCKET RECEIVER



★ Ideal for group instruction where any number of receivers can be used in conjunction with a walkie talkie.

★ **USED BY**

SKI INSTRUCTORS  
SPORTS COACHES  
SURVEYORS  
STOCK CONTROLLERS

FOR MORE INFORMATION  
CONTACT

**SHALLEY**  
ELECTRONICS

127 YORK STREET  
243767 — 247021

## *Revolution in the snow!*

Cross-country skiing is the only way to fly. Read how, in *Walkabout*, the magazine of Australia. Plus stories on kiteman Bill Moyes, a tiger hunt — and lots more!

**walkabout**

August

In colour. 60 cents.





## ANSWERS

**COMPLIMENTS AND QUESTIONS:** I would like to thank you for a very well-planned magazine. It has something for everyone — the beginner, dabbler and expert. Other Australian magazines have too many "product tests" and not enough projects. Could you tell me what "state-of-the-art" means? Also, have you published a simple short-wave receiver? Is there any way of testing a capacitor for value? How can one find out what the inside of an IC looks like? Is it possible to use just a part of an IC in a project? Also when sending for project reprints, is it permissible to pay in stamps, as postal orders cost so much these days? (M.R. Craigie, WA.)

Thanks for the compliments, M.R. We are glad you like the contents and format of the magazine. "State-of-the-art" means the present knowledge and technology in a particular field — in our case, electronics or a branch of it. The 1970 All-Wave Two (File No 4/TR2/5) published in April 1970 is about as simple a short-wave set as one could get. One transistor and one IC are the only active components! (Reprints are available.) A simple capacitance bridge may be used to check the values of capacitors. Our last one was described in the April 1968 issue (File No 7/B/9).

We are not sure what you mean by "the inside of an IC." If you mean circuit-wise, this information is usually available from the manufacturer or distributor. If you mean physically, then the only way is to carefully break one open (preferably a dud) and look! (You will probably need a microscope.) It is possible to use part of an IC, depending on the circuit. Notice, for example the Digital VOM (January 1973.) On the circuit there are a number of parts with 1/4 before them — meaning that only 1/4 of the IC is used in that part. The odds are the rest will be used elsewhere in the circuit — otherwise they are wasted. Stamps are quite permissible — as is any form of negotiable payment in Australian currency.

**CDI:** I have a few questions regarding CDI systems: You have stated that the CDI doubles the output voltage from the coil — on a sports coil which, say, delivers 40,000V already, would it be desirable to use CDI, which would then produce about 80,000V? Is there any chance of arcing in the distributor cap with CDI? Is there any need to change the standard points gap? What is bifilar winding? If this system were used in a V8 engine, would there be any need to decrease the gap from the 0.05in indicated in your Aug. 70 article? How much would the ignition timing need to be retarded for a V8 engine? How could this be worked out exactly? (C.M., Campbell, ACT.)

A sports coil should not be used with CDI. There would be a very high risk of crossfiring, arcing over, breakdown and other troubles. Because CDI places a much greater voltage stress on the electrical (ignition) system, the latter must be in perfect order. The points gap should be set as stated by the manufacturer, but with CDI this becomes less critical. Bifilar winding is where two wires are wound side by side as if they are one wire. We see no reason to change the plug settings, but this (and your other questions) are more a matter for a tuning shop.

## NOTES AND ERRATA

**PLAYMASTER 127 CONTROL UNIT** (November, 1969, File No 1/SC/8) some units are unstable when switched to the "tape" position. This may be cured by removing the tape input leads from the DIN socket and terminating them on one of the "radio" sockets. The leads from the radio socket may then go to the vacated pins on the DIN socket.

**RECORD REVIEW:** "The World of Albert Ketelbey" reviewed in the May issue, is a Decca release, number PFS-4170.

**130 RECEIVER** (April, 1972, File No 2/SW/62): The .002uF capacitor in the parts list should read .022uF. **FERGUSON TRANSFORMER:** The transformer announced in the New Products section of the March 1973 issue (p.105) should have the type number MT552. **TWO PLAYMASTER 138 PROJECTS:** Due to an oversight, there are two projects with the "Playmaster 138" designation: the Program Source tuner of December 1972 (File No 2/TU/33), and the Guitar Amplifier of May 1973 (File No 1/GA/20). Readers are warned not to confuse the two projects concerned, especially when ordering kits of components or metalwork.

**EXPERIMENTER'S AMPLIFIER:** Have you ever published an amplifier suitable for experimenters? One or two watts would be satisfactory. Would the amplifier from the Solid State Fremodyne be suitable? Would an impedance matching stage be necessary with a radio which uses a crystal or magnetic ear-piece? Have you published an amplifier which could be run off a 12V 2 amp transformer? If so, what is its power rating. Have you published any R C units suitable for a boat or plane with a range of up to 1km. (I.B., Whyalla Stuart, SA.)

The "Audio Mate" described in the March/July issues of 1972 (File No. 1 MA 49) should be close to what you require. It also includes a power supply suitable for running your experimental circuits. The Fremodyne power amplifier would be somewhat less suitable. There should be no need for impedance matching. We may have published a 12V 2A amplifier, but to find one would mean a long search through our indexes and files. It is, in any case, a very vague description. The last R C equipment we described was in December 1965 and January 1966. We feel these should no longer be recommended, as they are now rather dated.

**HIGH QUALITY AMPLIFIER REVIEWS:** I appreciate your product reviews as a Hi-Fi enthusiast but wonder why you do not review some of the top grade equipment available. A report on some of this equipment would be appreciated by many readers to provide standards of comparison and obtainable limits related to a number of aspects on which a judgement can be made. Secondly, can you supply any information on a multi stage, octave equaliser, audio frequency contourer? (Indecipherable signature, RANC, HMAS Creswell, Jervis Bay, NSW 2540.)


Our product reviews must generally be limited to those items which are submitted to us. If manufacturers or dealers elect not to submit their products, there is little we can do about it. Concerning your second query, we regret that we have no information. It may be worthwhile approaching the manufacturers of commercial units, or perhaps referring to copies of overseas journals in your local library.

**PRE-AMPLIFIER:** I am presently engaged in a project using a National LM380 IC amplifier and require a circuit for a preamplifier to boost the output of a 4in loudspeaker used as a microphone, to the level of a crystal cartridge. I would also be grateful if you could supply a speed control circuit for a turntable. (M.T., Mitcham, Vic.)

We would suggest an ordinary microphone preamplifier with a gain of around 100. A suitable circuit would be the preamplifier published in March 1972, which had adjustable bass response. (File No 1 PRE 27). Copies of the article are available from our Information Service at the usual fee. Alternatively, it might be possible to avoid using a preamplifier by fitting the speaker with a conventional speaker transformer to provide a stepup ratio. Unfortunately, we cannot supply information on turntable speed control circuits.

**HEADPHONE JACK:** I have successfully built the low cost stereo amplifier featured in January 1972 and now wish to add a headphone jack. Could you please advise me of the necessary circuitry? (D.B., East Preston, Vic.)

A headphone socket may be added very simply with the addition of two 330 ohm resistors to the existing circuit as shown in the diagram. No dummy loads are required in place of the loudspeakers during headphone listening.



**ERRATA:** Having just read your Notes and Errata column in the May issue, I wonder if readers are supplied with these amendments when purchasing project reprints? (J.F., Wickham, WA)

Yes, J.F., we go to some trouble to file all such notes with the master copies used for our reprint service. In this way the notes are copied automatically when a reprint is made.

Continued on Page 127

## "INNERBOND"

(Regd.)

## BONDED ACETATE FIBRES

FOR PACKING IN  
SPEAKER ENCLOSURES

A new resilient Bonded Wadding made from ultra fine Cellulose Acetate Fibres that gives high efficiency for sound absorption.

"INNERBOND" is light, clean, dust-free and easy to handle. Because all the fibres are bonded "INNERBOND" will hang as a "curtain" and will not fracture or break down due to vibration. "INNERBOND" is odourless, highly resistant to attack by bacteria or fungus and is vermin repellent. "INNERBOND" at 16oz sq. yd. has a normal thickness of 1" and at this density is recommended as a packing in speaker enclosures for sound absorption.

If unobtainable

For 1 sq. yd. as above send \$2.00  
For 2 sq. yds. as above send \$3.75  
For 4 sq. yds. as above send \$6.50

Postage paid in Australia and Territories to the manufacturers.

## WONDER WOOL

PTY LTD

87 JAMES STREET, LEICHHARDT,  
NSW 2040

Box 548 — GPO, Sydney 2001.  
Phone: 56 2780.



## UNITED TRADE SALES PTY LTD

280 LONSDALE STREET  
MELBOURNE 663 3815

- Crystal filters 10.7MHz 10KHz band width, \$5 each P/P 30c.
- Computer boards min 10 transistors plus 30 diodes, resistors and capacitors all have long leads. \$1.25 each P/P 40c. or 6 for \$6. P/P 80c.
- Silicon diodes 100 PIV 145 amp \$3.00 each P/P 40c. Terminals for above 50c each.
- Cassette tape heads transistor mono \$1.50 each P/P 15c.
- Piano key switches 6 keys 4 sections with 6 changeovers \$1.00 each P/P 40c.
- Battery holders — metal, holds 2 x UMI batteries 15c each p/p 15c.
- Car radio push button tuner complete \$4.00 each P/P 50c.
- Cannon 15 pin chassis mount socket and lock on plug \$3.00 pair P/P 30c.
- TV legs 13" long \$1.00 set of four P/P 40c.
- Resistors carbon 1/2 watt and 1 watt. Pack of 100 mixed values \$2.00 per pack P/P 20c.
- Silver Wire 12v relays 1" x 1 1/2" complete with socket, 75c P/P 20c. As above but with latching \$1 P/P 20c.
- Uher 12V DC cassette tape recorder motors with transistorised motor control module \$4 pair P/P 40c.
- Speakers new MSP 9" x 6" and 8" x 4" \$5 each P/P 40c.
- Computer fans 7" diameter, 120V AC. Use two to run on 240V AC. \$6.50 each P/P \$1.00.
- 15" reels 1/2" computer tape, \$3.50 ea P/P 75c.
- Electrolytic Capacitors 2,500 uF 25 VDC working \$3.50 ea. P/P 40c.

Wanted to buy — Test Equipment Transmitters & Receivers



<b>SOUND PROJECTORS</b> Cinevox Prefect and Harmour and Heath 16mm in good working order. 240v operated, complete with speaker and amplifier. <b>from \$115.00</b>	<b>NIBBLING TOOL</b> Cuts sheet metal like a punch and die, trims, notches and cuts to any size or shape over 7 1/2-inch. <b>ONLY \$6.50</b> Post 74c.	<div style="border: 2px solid black; padding: 5px; text-align: center;"> <b>VALVES</b>  <b>BRAND NEW</b>  <b>IN CARTONS</b> </div> <p>Special discount for quality</p> <table border="0"> <tr> <td>807</td><td>\$1.50</td> <td>CV850</td><td>\$1.50</td> </tr> <tr> <td>65N7GT</td><td>95c</td> <td>1H6G</td><td>50c</td> </tr> <tr> <td>5U4G</td><td>75c</td> <td>832</td><td>\$3.00</td> </tr> <tr> <td>EF50</td><td>75c</td> <td>6AK5</td><td>\$1.50</td> </tr> <tr> <td>5Y3</td><td>\$1.99</td> <td>6X4</td><td>\$1.00</td> </tr> <tr> <td>6C4</td><td>50c</td> <td>VR65</td><td>50c</td> </tr> <tr> <td>2 x 2</td><td>75c</td> <td>VT4C</td><td>75c</td> </tr> <tr> <td>6AG5</td><td>80c</td> <td>80</td><td>\$1.25</td> </tr> </table> <p>Please add postage on all articles</p>	807	\$1.50	CV850	\$1.50	65N7GT	95c	1H6G	50c	5U4G	75c	832	\$3.00	EF50	75c	6AK5	\$1.50	5Y3	\$1.99	6X4	\$1.00	6C4	50c	VR65	50c	2 x 2	75c	VT4C	75c	6AG5	80c	80	\$1.25	<b>MINE DETECTORS</b> Ex A.M.F. Complete in wooden case. Ideal for plumbers, councils for locating buried pipes, etc. Freight payable at nearest attended railway station <b>\$39.00</b>
807	\$1.50	CV850	\$1.50																																
65N7GT	95c	1H6G	50c																																
5U4G	75c	832	\$3.00																																
EF50	75c	6AK5	\$1.50																																
5Y3	\$1.99	6X4	\$1.00																																
6C4	50c	VR65	50c																																
2 x 2	75c	VT4C	75c																																
6AG5	80c	80	\$1.25																																
<b>CIRCULAR SLIDE RULE</b> 3 1/4 inch diameter. Will do the same work as the conventional slide rule. Instruction book included. <b>from \$1.60 each</b> Post 12c.	<b>NIFE CELLS</b> 1.2 Volt, fully charged, 4in x 3in x 1in 4 AM. <b>\$1 each.</b> Post N.S.W. 25c. Interstate 35c. 3.6V 10AH. set of three batteries in wooden holder, \$7.50 per set or \$2.50 per battery 1.2 volt 10AH. Post N.S.W. \$1.10; Interstate \$2.72.	<b>PYREX PARABOLIC REFLECTOR 36"</b> <b>\$37.50</b> Shap Sales Only.	<b>BATTERY CHARGERS</b> <b>BRAND NEW WITH METER</b> plugs into 240V power and gives both 6V and 12V DC output. 4 amps with hi, medium and low charges. Dimensions, 9" x 5" x 5" \$35 value only <b>\$27.50</b> Post NSW \$1.00 Interstate \$1.50																																
<b>P.M.G. TYPE TELEPHONES</b> Standard desk type with magneto bell calling device. Range 30 miles. Uses standard batteries at each phone. Any number can be connected together on single line. <b>\$25.00</b> (2 TELEPHONE SETS) 30c. cartage to rail. Freight payable at nearest attended railway station. Please note we are now able to include 1/4 mile of twin telephone cable FREE with each set of phones.	 <b>P.M.G. TYPE KEY SWITCHES.</b> 45c each. Post 24c.	<b>RADAR TRANSCEIVER</b> <b>X BAND WITH KLYSTRON ETC.</b> <b>\$45.00</b>	<b>SCOTCH BRAND RECORDING TAPES USA.</b> EX ABC 1/4" Polyester 2400ft. on 10 1/2" reels <b>\$3.95</b> Post NSW 45c. Interstate 75c.																																
<b>WHIP AERIALS</b> 3 Piece. Tapers from 1" to 1/8". No Base \$4.95. Shop Sales Only. <b>66VTVM</b> University Graham Tested \$45 Post \$1.00	<b>TELESCOPES ZOOM FOCUSING</b> 25 x 30 \$19.95 — 40 x 40 \$28.95 <b>POST NSW 95c INTERSTATE \$1.45</b>	<b>TRANSMITTERS ARC 49</b> 100-165 M/CS <b>\$25.00</b>	<b>SOLENOIDS</b> Plunger Type 12V 300MA. Suit electric camera control, miniature trains, radio, etc. <b>\$1.25. Post 24c.</b> 200 MA 24 volt, 1/2 in push movement. <b>\$1.25. Post 24c.</b>																																
<b>MINIATURE ELECTRIC MOTORS</b> 1 1/2 to 3 volts DC. Ideal for model boats, cars, planes, etc. Strong torque. Only <b>45c. each or 10 for \$4</b> (Post 12c.)	 <b>TELESCOPES</b> 60 magnification with a 60mm coated objective lens. With tripod. <b>\$29.50</b> As illustrated. Postage \$1.20; Interstate \$1.45.	<b>TELESCOPES</b> 40 x 40 with Tripod. <b>\$7.95</b> Post N.S.W. 95c; Interstate \$1.45	<b>ZOOM FOCUSING MICROSCOPE</b> Battery and mirror illuminated 900x magnification. Complete with dissecting kit slides etc. <b>\$22.50</b> Post NSW \$1.00 Int, \$1.25																																
<b>TRANSCEIVER</b> (2-way radio) R.C.A. America RT 68, 24 volt, operated 10 watt output 38-54MHz F.M. crystal locked. Transmitter and receiver using frequency synthesiser in 100KHz; step 10 channel per MHz with power supply, \$45. 60c cartage to rail. Freight payable at nearest attended railway station.	<b>BC221</b> Frequency Meters. <b>\$35.00</b>	<b>CHASSIS PUNCH SET</b> Five sizes: 1/4-inch, 3/8-inch, 7/8-inch, 1-inch and 1 1/2-inches. With taper reamer. <b>\$14.50</b> Post, \$1.15	<b>FIELD STRENGTH METERS</b> 144 M/CS. <b>\$12.50</b>																																
<b>TRANSCEIVER</b> (2-way radio) 62 set, 12V, operation. Ideal Hams, etc. 1.6 to 10MHz. Crystal locked or VFO controlled. 5 watt output. Complete with antenna, headphones and mike. \$40. 30c. cartage to rail. Freight payable at nearest attended railway station.	<b>WALKIE TALKIES</b> 2-way radio, 7 transistor, PMG approved, set of 2 only \$47.50 Post NSW \$1.00 9 transistor \$57.50 Interstate \$1.20	<b>SELSYN MOTORS MAGSLIP</b> Mk. II..... <b>\$5.25 ea.</b> No. 19 TWO-WAY RADIOS. Power supply, accessories, etc., <b>\$35.</b>	<b>TEN CHANNELS VHF TRANSCEIVER</b> Types TR 1934 100-125 MHz and TR1935 125-150 MHz. 28 volt DC operated AM single crystal locks both TX and RX on same channel complete with generator. <b>\$33.00</b>																																
<b>SMITH'S BRASS (English) SHIPS CLOCKS</b> 8-day, no bell, \$37.50 each. Post NSW \$1.15. Interstate \$1.70.	<b>SMALL COMPUTER PANELS</b> 3in x 2in containing 2 valves, qty. of resistors, etc. <b>ONLY 75c.</b> Post 24c.	<b>BINOCULARS</b> PRISMATIC. Coated Lenses. Brand new. Complete with case. 7 x 35 Wide Angle..... <b>\$34.50</b> 8 x 40 Wide Angle..... <b>\$39.50</b> 7 x 50..... <b>\$28.45</b> 10 x 50..... <b>\$29.60</b> 12 x 50..... <b>\$30.60</b> 20 x 50..... <b>\$34.45</b>	<b>RECORDING TAPES</b> TOP QUALITY. BRAND NEW 3" x 150' ..... 75c ..... 12c 3 1/4" x 600' ..... 1.75 ..... 13c 5" x 900' ..... 2.20 ..... 13c 5" x 1800' ..... 3.99 ..... 13c 7" x 1200' ..... 3.25 ..... 24c 7" x 2400' ..... 5.80 ..... 74c 7" x 3600' ..... 6.99 ..... 74c																																
<b>PRISMATIC COMPASSES</b> Genuine ex-army Mk 3, liquid damped, as new \$27.50. Post NSW 95c. Interstate \$1.15.	<b>ELECTRONIC FREQUENCY COUNTER</b> Austroinc type DFC-4 240V 50 cycle 0-100KHZ <b>\$150</b>	<b>3000 TYPE RELAYS</b> P.M.G. 200 Ohms — 1,500 Ohm Coils. \$1.25 each. Post 24c.	<b>CASSETTE TAPES</b> C60 99c C90 \$1.75 C120 \$1.95 Post 13c. Crystal Earphone ..... 75c Cassette head cleaners ..... <b>\$1.50</b> Small Lapel Microphones, ea. <b>\$1.25</b> Post 24c.																																
<b>COLLINS TRANSCEIVERS</b> Auto-tuned 100-150MHz. 10 channels. <b>\$65.00</b>	<b>IMPELLER PUMPS</b> New gunmetal body, Stainless Steel Shaft. Neoprene Impeller. Up to 15ft. Lift, suitable for almost any type of liquid. Self priming. Ideal boat bilge pump, sillage drains, etc. Approx size 8" x 5". 3/8" ..... <b>\$19.95</b> 1/2" ..... <b>\$22.75</b> 3/4" ..... <b>\$27.50</b> Post NSW \$1.20. Int. \$1.90.	<b>TOGGLE SWITCHES</b> Brand new, 3 amp, 240 volt. S.P., S.T. 39c each or 10 for \$3. Add postage. Cintel Oscillator and Electronic Counter, type 388. <b>\$250.</b>	<b>AIRCRAFT MAGNETOS DELCO</b> Magnetos, new cond, 12 cpls, \$15 ea. Post NSW \$1.20, Interstate \$1.95. <b>BYER 77 Mk. 1</b> Rack Mounting Tape Recorder ex A.B.C. 7 1/2-15 ips. Full track tested <b>\$150.</b> <b>BC348 RECEIVER</b> <b>\$80.00</b> Marconi Video Oscillator type TF885A 0-12 MHz. <b>\$75.</b>																																
<b>AR7 RECEIVERS</b> WITH ONE COIL BOX \$45.00 Complete with Power Supply and 5 Coil Boxes \$115.00. Freight payable at nearest attended Rly. Stn.	<b>A.W.A. B.F.O. TYPE R7077</b> 1-800 CYCLES <b>\$30.00</b> 1-13 K/CS.	<b>SPECIAL lucky dip valve offer, 15 new valves in cartons for only \$2. We haven't got time to sort them, so you reap the benefit.</b> Post 75c.	<b>A.W.A. SIG GENERATOR</b> UHF 140-300 MHz <b>\$65.00</b> Pye 4 Channel Crystal Locked Oscillator, 1.5-30 MHz New. <b>\$25</b>																																
<b>UNI-SELECTORS</b> 25 bank 25 position \$4 each. Post N.S.W. 45c. Interstate 65c.	<b>CONDENSER LENS</b> 2 1/2in DIAM. 2in FL. \$1.50 each. Or \$2.50 per pair. Post 24c.	<b>CONDENSER LENS</b> 1 1/2in diam. 1 1/2FL. 50c each. Postage 24c.	<b>TRANSPONDER APX6</b> with Lighthouse Tubes. Can be converted to 1200 MHz. <b>\$17.</b>																																
<b>CAR TACHOMETERS</b> NEW IMPORTED Suit 6 cylinders only \$20 each. Post N.S.W. \$1.05, Interstate \$1.75.	<b>522 Transceivers</b> 100-150 M/CS <b>\$35.00</b>	<div style="text-align: center;"> <h1>Deitch Bros.</h1> <h2>70 OXFORD STREET, SYDNEY 2010</h2> </div>	<b>ADLER FREQUENCY METER</b> 100KHz-20MHz <b>\$95</b>																																
<b>4 DIGIT RELAY COUNTERS</b> 50-volt DC, suit slot car. Lap counters, etc. <b>\$1.25 each. Post 18c.</b>	<b>Cossor Double Beam Oscilloscope</b> 1035. Tested. <b>\$150</b>	<p style="text-align: center;">SORRY, NO C.O.D.</p>																																	



## Listening from p.118

### BRUSSELS USES 9655kHz

Station ORU, Brussels, Belgium has been noted on a new frequency for their two transmissions in English; this differs from that announced by the station. According to the May 6 schedule the English broadcasts were to be carried on 9550 and 15235kHz, but we have been receiving the new frequency of 9655kHz which replaces 9550kHz for the period 2300-0100GMT at very good strength.

English programs are heard daily from 2300-2315GMT and again from 0040-0100GMT. On Friday at 0040GMT a mail-bag session is presented and requests are made for reception reports to PO Box 26, Brussels, Belgium.

CZECHOSLOVAKIA: One of our listeners at Tinonee, NSW, Ron Knott reports on reception of Radio Prague in their transmission to Australia and New Zealand. At the present time only three frequencies are being used; these are 11855, 15310 and 21700kHz. The English program for the Pacific is broadcast from 0700 to 0800GMT.

## Total communications from p.18

of the United States, in absolute terms, during the last half of the 1970s — something that would have been unimaginable just ten years ago.

All of the international implications of Japan's emergent leadership in telecommunications are not clear, by any means. But this much is certain: with a multi-billion home market for advanced telecommunications products, and the heavy outlays for a well-orchestrated R&D program it will make possible, the Japanese industry will have formidable international competitive power. Moreover, as telecommunications becomes increasingly a global activity, Japan can be expected to play an important role in extending the information revolution to other parts of the world, not only through the sale of products and the transfer of the necessary technology, but also in the development of vital new international communications organisational structures that will be needed to maximise the benefits of total communications to humanity as a whole.

"Communications," says NEC's Dr Koji Kobayashi, "must become world communications. It can no longer be organised on national lines. By the turn of the century

a total global communications system can be a reality. We have the basic technology in microwave and satellite systems. Laser communications will increase our communications capabilities even further. What are needed now are new approaches to organising efficient global communications systems."

## VHF converter from p.33

Whatever aerial system is used, it should be cut to suit the frequency of interest, or when a band of frequencies is to be considered, then the aerial should be cut to suit the middle of the band.

As a bare minimum, a simple folded dipole may be made up from 300 ohm TV ribbon, with both ends shorted and one lead cut in the centre to connect in another length of ribbon, which acts as a feeder. The dipole length is calculated by dividing the desired frequency in MHz into 14,070, which gives the answer in cm. When constructed, the dipole section may be tied or otherwise fixed to a piece of wooden dowel for support.

Strictly a 300 ohm-to-75 ohm balun should be used to match the balanced feeder to the converter input. However this could probably be omitted if desired, and the feeder connected directly to the converter aerial input and earth.

A little practice will be required to tune this converter. The tuning will appear to be rather sharp and the degree of this will depend upon the actual bandwidth being covered. If you only have to tune say from 52 to 54MHz, then tuning will be much easier than if you are tuning from 118 to 136MHz — 2MHz as compared with 18MHz. Another point to remember is that the system is limited by the ability of the main receiver as far as modulation resolution is concerned. This applies particularly to frequency modulation. More than likely, the TV sound channels will sound distorted, due to the fact that TV sound uses a wide deviation and the selectivity characteristics of the receiver will probably be quite narrow. This is an important point to remember when evaluating the overall system.

# LANTHUR ELECTRONICS

69 BUCHANAN AVENUE, NORTH BALWYN, VICTORIA, 3104. PH. 85 4061.

### BUILD YOUR OWN

Battery charger. Basic kit consists of transformer, bridge rectifier, ballast resistor, pair clips and circuit with instructions. Charges 12 volt batteries at 2 amps. \$7.50 Plus postage, Vic. \$0.40, Other \$0.70. 4 amp. model charges both 6 and 12 volt batteries. \$14.80. Plus postage, Vic. \$0.70 (Certified), Other \$0.85.

### BUILD YOUR OWN

Battery saver. Basic kit consists of transformer, bridge rectifier, filter capacitor and circuit. DC voltages available from 6 to 15. One amp. size \$4.50 Two amp. size \$8.50 Plus postage. Vic. \$0.40, Other \$0.70.

### FERRITE RODS

6" long x three eighths inch diameter. \$0.45 ea.

### TOGGLE SWITCHES

Sub. miniature S.P.D.T. 250 vac. 2 amp. \$1.50 ea.

### SILICON DIODES

Stud mount type. 25 amp. rating. Suitable for automotive or battery charger use. 50 P.I.V. \$1.15, 100 P.I.V. \$1.30. Specify whether forward or reverse type required. Heat sink adaptors to suit \$0.35. Prices include postage.

### BROADCAST BAND TUNER

Ready to use. Suitable for Hi-Fi amplifiers, tape recorders etc. Uses solid state module, 8" aerial rod and fitted with straight line dial 6 1/4" x 1 1/4". Chassis size 6" x 4". Band width 8kHz. Output approx. 1/2 volt. Requires 9 volt supply at 5ma. \$23.95. Plus cert. post. Vic \$0.60, Other \$0.85.

### STRAIGHT LINE DIAL

As used in above tuner. Glass, back plate, drum and hardware. \$5.95. Includes postage.

### ELECTRONIC SIREN MODULE

Four models producing either Siren, Yip, Warbler or Whip sound when connected to speaker. Ideal for burglar alarms. One unit will operate up to 3 speakers from 12 volt dc supply. \$16.95. Includes postage.

### REFLEX HORN SPEAKERS

For use with above. \$9.95.

Includes postage.

# HAM RADIO SUPPLIERS

MAIL ORDER SPECIALISTS

323 Elizabeth Street Melbourne  
(2 doors from Little Lonsdale Street)



**200-H. \$12.50**  
90° quadrant meter. Pocket size.  
AC/V: 10V, 50V, 100V, 500V, 1000V (10,000Ω/V)  
DC/V: 5V, 25V, 50V, 250V, 500V, 2500V (20,000Ω/V)  
DC/A: 50μA, 2.5mA, 250mA  
OHM: 60kΩ, 6MΩ  
Capacitance: 100pF to .01μF, .001μF to .1μF  
dB: -20dB to +22dB  
Audio Output: 10V, 50V, 120V, 1000V AC  
Approx. size: 4 1/2" x 3 1/4" x 1 1/2"

### AS-100D/P.

**\$34.50**  
High 100,000 Ω/Volt sensitivity on D.C.  
Mirror scale. Protected movement.  
AC/V: 6V, 30V, 120V, 300V, 600V, 1200V (10,000Ω/V)  
DC/V: 3V, 12V, 60V, 120V, 300V, 600V, 1200V (100,000Ω/V)  
DC/A: 12μA, 6mA, 60mA, 300mA, 12A  
OHM: 2kΩ, 200kΩ, 20MΩ, 200MΩ  
dB: -20 to +63dB  
Audio Output: 6V, 30V, 120V, 300V, 600V, 1200V AC  
Battery: Internal  
Approx. size: 7 1/2" x 5 1/2" x 2 3/4"



### MODEL OL-64D/P MULTIMETER

20,000 ohms per volt. DC volts: 0.025, 1, 10, 50, 250, 500, 1000 (at 20K Ω p.v.). 5000 (at 10K Ω p.v.). AC volts: 0-10, 50, 250, 1000 (at 8K Ω p.v.). DC current: 50μA, 1mA, 50mA, 500mA, 10 amps. Resistance: 0-4K, 400K, 4M, 40 megohms. DB scale -20 to plus 36 dB. Capacitance: 250pF to 0.02μF. Inductance: 0-5000 H. Size: 5 1/2" x 4 1/4" x 1 3/4" in.  
**Price \$19.75**  
Postage 30c.

### MODEL C1000 \$6.95

is the ideal low cost pocket meter.  
AC volts: 10V, 50V, 250V, 1000V (1000Ω/V)  
DC volts: 10V, 50V, 250V, 1000V (1000Ω/V)  
DC current: 1mA, 100mA  
OHM: 150kΩ  
Decibels: -10dB to +22dB  
Dimensions: 4 1/4" x 3 1/4" x 1 1/4" 4 1/4" x 3 1/4" x 1 1/4"



### CT-500/P. \$16.75

Popular, medium-size, mirror scale. Overloaded-Protected.  
AC/V: 10V, 50V, 250V, 500V, 1000V (10,000Ω/V)  
DC/V: 2.5V, 10V, 50V, 250V, 500V, 5000V (20,000Ω/V)  
DC/A: 50μA, 5mA, 50mA, 500mA  
OHM: 12kΩ, 120kΩ, 1.2MΩ, 12MΩ  
dB: -20dB to +62dB  
Approx. size: 5 1/2" x 3 3/4" x 1 3/4"



### A-10/P \$55.00

Giant 6 1/2" Meter. Inbuilt signal injector. Overload Protected.  
AC/V: 2.5V, 10V, 50V, 250V, 500V, 1000V, 5000V (10,000Ω/V)  
DC/V: 0.5V, 2.5V, 10V, 50V, 250V, 500V, 1000V at 30,000Ω/V  
5000V (10,000Ω/V)  
DC/A: 50μA, 1mA, 50mA, 250mA, 1A, 10A  
AC/A: 1A, 10A  
OHM: 10kΩ, 100kΩ, 1MΩ, 100MΩ  
dB: -20 to +62dB  
Signal injector. Blocking oscillator circuit with a 2SA102 transistor  
Approx. size: 6 1/2" x 7 1/2" x 3 3/4"

### 1 WATT TRANSCEIVER, 13 TRANSISTOR 3 CHANNEL



and Call System. Specifications: Circuit: 13 Transistors, 1 Diode, 1 Thermistor. Range: Up to 10 miles (depending on terrain, etc.). Frequency: 27.240 MHz (PMG approved) Freq. Stability: Plus or minus 0.005%. Transmitter: Crystal controlled, 1 watt. Receiver: Superheterodyne. Crystal controlled. Antenna: 13 Section Telescopic. Power Source: 8 UM3 1.5 volt pen batts. Size 8 1/4in. x 3 1/4in. x 1 1/4in. Weight: 25 ozs. Other features:

Leather carrying case, battery level meter, squelch control, earphone jack, A.C. adaptor, jack, etc. Price \$79.50 A PAIR. Single units available \$40 each. Be early!



# MARKETPLACE

## FOR SALE

Multitester parts moving coils with needles, meter scales, 3 terminal rectifiers, send for price list. WATSON WILL & Co, Box 130 Valley, Brisbane 4006.

**Huge Clearance Sale!!!** Yes, we are selling off all these lines at mad prices so hurry and stock up now. This month's specials:— Polyester Capacitors .47 200v-20 for 50c, Ceramic Disc .001 50v, .0027 500v-20 for 30c. Semiconductors: BC108-10 for \$2.90, EM402-10 for \$1.85, 2N3055-1.60 ea. or 2 for \$3, 2N1305-80c, 1N662, 1N3666-15c ea, SE1001-10 for \$2. Zener Diodes (ITT) ZG Series (400mw) 1, 2, 7, 4.7, 6.2, 10, 15, 18, 27 volts-40c ea. or 10 for \$3.80; ZM Series (1.1w) 3.9, 4.7, 5.6, 6.8, 12, 15, 18, 27, 39, 56 volts-75c ea. or 10 for \$7; ZL series (10w) 3.9, 6.8, 7, 8, 8.2, 18, 27, 39, 180 volts-\$1.40 ea. Tantulum Capacitors, Top Quality, miniature type: 5, 7, 30, 40uf (3v), 4, 6uf (6v), 4, 5uf (10v), 1.5uf (15v) — all only 20c ea. or 10 for \$1.80. Polyester Capacitors Top Brand (10v, Tol.) 160v: .001, .012, .015, .018, .033, .039, .056, .068, .082-10 for 40c; .12, .15, .18, .22-10 for 60c; .27, .39, .47, .56, .68, .82-10 for 90c (Note: These prices for this month only). Electrolytics: 10uf 50v, 47uf 10v-10 for 50c; 100uf 12v-10 for \$1; 470uf 25v-10 for \$1.90. Potentiometers: Single Pots 1k w-10 for \$3.50, 500 ohms D (Miniature)-10 for \$2.50, Switch Pot 50k c-10 for \$3. Stereo Pots 5k c-10 for \$5. Trimpots, miniature P.C. type (10mm) 500, 1k, 2k, 5k, 10k, 25k, 50k, 100k, 250k, 500k, 1M, 2M-10 for \$1.60. Ceramic Disc Capacitors: 1.8, 2.2, 10, 22pf 500v, .001uf 500v, 18pf 100v, .015 25v-20 for 50c, 68pf 3kv-20 for 60c. Resistors: Precision 10 ohm, 1%, 1/4w-10c ea.; Mixed bag of top quality 5%, 10%, 1/4w & 1/2w, ideal for V.H.F. or servicing, 100 for \$1 (Great value). Speakers: 6" Round 15 ohm V.C. — \$4.50 ea. (P.P. 50c). Rotary Switch (2 Pol. 3 Pos.)-50c. Bank of 4 push button switches, Push on — off — 50c. Tag Strips 10 lug-10 for 60c, 4 lug-10 for 20c. Trimmers (12-120pf)-10 for \$1. Copper Clad Board 6" x 6" — 10 for \$3. Hurry, stocks won't last. Post Pack 20c or extra for heavy parcels. MICRONICS, PO Box 175, Randwick, NSW, 2031.

**Bargain 100 YF 250V Pigtail 26c .022, .047, YF 400V Poly 10c resistors Philips 1/2W, 4C, 1W, 6C most values magnetic cartridge, \$7.50; SHURE M91E cart \$40, 2 1/4" speaker, 15 ohm, 25 ohm, 40 ohm, \$1.99, add 20c p. post, extra for heavy parcels. Quantity disc. BRYSTAN SERVICE P. L., 12 Gordon Ave, Geelong West, 3218. Phone 91524.**

**Sansui AU555A amplifier \$180.00 JVC nivico SRP473E turntable ADC 550 XE cartridge \$140.00 wharfedale dovetailed III speakers \$220.00 national RQ2125 cassette recorder \$75.00. All above only six months old, phone 70 5562 I. B. UNWIN, 34 Church Rd., Yagoona, NSW 2199.**

**Parts new SCR's T.C44 30V 1A 80CT, 4 for \$200.00. TAG cap's 1 pr 35V TANT, 30c 8 for \$2.00, 2 pr 600V NON Polarise TANT cap's 80c 4 for \$2.00 Fibreglass PCB 5" x 6" 80c Used SCR's C106 50V 4A 50c. Post Paid. C. Baker, Box Q113, QVB, SYDNEY.**

**Public Address Amplifier AWA model PA 1005 12.5 watts with ceramic microphone and 4 speakers. Excellent condition \$50. PO Box 360 Brookvale, NSW 2100.**

**BRENELL MK4 T. D and LINK Stereo \$500.00 ono 734531. R.E. POTBURY, 2 Lorraine St, Homebush, NSW.**

**Crystals for CB 27.240 and 26.785 MHz, 1/2 pin miniature \$6 pair Post free Shalley, 127 York Street, Sydney.**

**Power Supply 12.6V DC 3A, regulates to less than 0.2 V from 210-270 V (no taps) 45-60Hz input, full overload and short-circuit protection. Manufacturer's surplus, brand new in cartons. \$29.50 plus freight. PO BOX 360, BROOKVALE, 2100 NSW.**

**Byer Tape Recorders ex broadcast use mark II mod 77 \$390 — mark I mod 77 \$165 — mark II mod 66 with built-in radio tuner \$300 — F.A.S.C. O 4GY, Mary St, Gympie 4570. Phone 822346 a/h 821183 (Std 071), S.L. FITTELL, 78 Channon St, Gympie, Qld 4570.**

**Zener Diodes 1/2W, sil & germ trans untested, all 15 for \$1, stereo tape heads \$3 pr SURTRAN, Box 317, GPO SYDNEY.**

**SONY AV 3600 videocorder and SONY monitor TV receiver as brand new. Refails over \$700. Bargain at offers over \$350 phone SYDNEY 858 1874. N. C. PAYOE, 4 11 Riverview Street, West Ryde, NSW 2114.**

**Back Issues Electronics Australia Stocked, 50c each, prompt service, Post Free. T WEIR, 56 O'Connor St, Haberfield, NSW 2045. Phone Sydney 798 7569. Wanted to buy copies also.**

## STOCK SALE

a genuine 20% off all prices

★ Free price list available ★

HILLTOP ELECTRONICS

21 Hilltop St., Geelong West 3218

## C.D.I. SYSTEMS TRANSFORMERS & CONVERTERS

6 & 12 volt negative and positive polarities transformer only \$6 including tax p & p 50c extra. Converter less transformers only \$10 including tax p & p 50c extra.

F. MIHAI — 48 Chapel Rd., Moorabbin, Vic. 3189. Tel. 95.4839.

## WAYNE COMMUNICATIONS PTY. LTD.

757 GLENFERRIE RD., HAWTHORN, 3122. PH. 81 2818.

INTEGRATED CIRCUITS	
SN7490	\$1.80 ea.
SN7441AN	\$2.50 ea.
SN7475N	\$1.80 ea.
SN7400N	75c ea.
SN7410N	75c ea.
SN7430N	75c ea.
SN7440N	75c ea.
SN7472N	\$1.75 ea.
SN7473N	\$2.00 ea.
SN7447N	\$2.60 ea.
LM709 OP AMP	\$1.20 ea.
LM305 Pos Reg	\$3.80 ea.
LM304 Neg Reg	\$4.90 ea.
TIL 209 L.E.D.	80c ea.
Postage on I.C's 10c ea.	
TRANSISTORS	
2N3055	\$1.60 ea.
BC109	60c ea.
BC108	50c ea.
BC107	50c ea.
2N3568	75c ea.
2N3866	\$1.50 ea.

**DISPLAY ADVERTS in MARKETPLACE** are sold in multiples of one inch to a maximum of five inches. Rate \$10.00 per inch per insertion, subject to continuity discounts.

**CLASSIFIED RATES \$1.00 per line per insertion payable in advance.** Minimum two lines. A convenient form is provided in each issue.

**CLOSING DATE** is four weeks prior to the on-sale date. Issues are on-sale the first Monday of each month.

**ADDRESS** all classified orders, copy, enquiries, etc. to: The Advertising Manager, **ELECTRONICS Australia**, Box 162 Beaconsfield, 2015.

## WANTED

**Coscor Mod 1035 cro Mains Tx Wanted.** part no MC413037 or any helpful suggestions, George Richings, 156 Ferrars St, South Melbourne, VIC 3205.

## READER SERVICE

**Cassette Library, Reel-Reel Tapes, Discounts, magazine, Tapespondence, AUST Tape Recording Society, BOX 130 PO. HORNSBY, NSW 2077.**

**Atira** the club that makes friends with your tape recorder (reel or cassette). SAE Box 970, GPO, Adelaide, SA 5001.

## HI FI ANNUAL

Still available from our office or box 157, Beaconsfield, 2015.

\$2.30.

## ELECTRONICS Australia

*Guarantee yourself a complete set of issues for your library with no copies missing.*

**POST THIS COUPON TO:**

**Subscription Department, ELECTRONICS Australia, Box 139 Beaconsfield, 2015**

Name .....

Address .....

Enclosed is \$..... for ..... years. Start with .....

### Subscription Rates

Australia  
New Guinea,  
New Zealand

\$7.50 per year

Elsewhere

\$10.00 per year

## SERVICE

**BILL TURNBULL** offers you service on Hi Fidelity equipment tape Recorders, Communication Receivers and Electronic Test Equipment.

**All work guaranteed  
BILL TURNBULL**

11 ELLALONG ROAD,  
CREMORNE, N.S.W. 90 4825



## POSITIONS VACANT

Part time student interested in miniature solid state electronics. Contact MR. WILSON, PO BOX 78, BURWOOD, NEW, 2134. PHONE 74 2733.

### TWO-WAY RADIO TECHNICIANS MARINE RADIO & RADAR TECHNICIANS

We have positions for two experienced technicians in each of the above departments. Good working conditions in a well equipped workshop a few minutes from the centre of Cairns.

Wages will be by negotiation and according to experience and qualifications. Applications giving full details of experience and employers should be forwarded to—

Manager,

**NORTHERN COMMUNICATIONS,**  
PO Box 1277, CAIRNS QLD 4870.

### AMV4 ALBURY/WODONGA

### Experienced TECHNICIAN Experienced CO-ORDINATOR

For AMV studios going colour March 1975. Australia's chosen growth centre. Apply with all particulars to:

VACANCY P.O. Box 444, Lavington, N.S.W. 2641, or phone Albury 25 1444 Reverse charge Kidd AMV.

## ANSWERS from P.123

**LAWN POWER:** I have found that if I stick the probes of my multimeter in the lawn and set it for 0.25V I get a reading of 1/2 volt. I tried moving the probes slightly and the meter reversed. I then tried running a small oscillator circuit from it — it ran for five minutes before running out. Could you explain this? I asked two people. One said, "It's all the shocking people around", and the other said, "It's electric worms". (P.J., Hawthorn, Vic.)

It is not really possible for us to give an explanation of your observation without being on the spot. It is possible that there are heavy earth currents in your vicinity or there may be an electrolysis action in the soil. We doubt that either of the other suggestions offered are valid explanations, though.

**PIC. TUBE REJUVENATOR:** In the May issue of Electronics Australia, a reader, T.S., of Waikerie, SA, was enquiring about a circuit for a picture tube rejuvenator. The answer is to be found on p109 June 1969 issue of "EA". (P.F., Crawley, WA.)

Thanks to our correspondent from Crawley WA, there is your answer, T.S.



### ELECTRONIC ORGANS

Do not start to build yourself an organ without first finding out about the superb **SCHOBER (USA)** assemble-it yourself kits. Inquiries to Schober Organs (Aust), 124 Livingstone Ave., Pymble, NSW, 2073. (Mail only please.)

### TRANSISTOR RADIO KIT

2 silicon transistors easy to build — all parts supplied including P.C. board and full instructions.



\$5.25  
PP 55c

ALSO 2 WATT AMPLIFIER KIT TO MATCH \$6.50



### VHF CONVERTER TUNER

110-136 MHz  
coupled to broad-  
cast receiver  
\$14.95  
PP55c

### NEW MODEL



**7 TRANSISTOR RADIO KIT**  
Silicon transistors, complete with instruction book, carrying case and earphones.  
Special price \$9.75  
Wired \$11.75  
Post and pack .75

### CASSETTE TAPE DECKS

6 volt and 240V Motors From \$23.00

## INTEGRATED CIRCUITS

7400	Nand Gate	88c
7401	2Ip Nand Gate	90c
7402	Nor Gate	88c
7403	Nand Gate	88c
7404	Hex Inverter	88c
7408	And Gate	88c
7410	Nand Gate	88c
7412	3Ip Nand	1.35
7413	Schmidt Trip	1.40
7420	Nand Gate	88c
7430	Nand Gate	88c
7440	4Ip Gate	88c
7441	BCD	2.33
7442	BCD	2.20
7460	Expander	90c
7473	Flip Flop	1.70
7475	Latch	1.90
7476	JK Flip Flop	1.85
7490	Counter	1.85
7493	Counter	2.75
74121	Monostable	1.50
U A709 OP. AMP		1.00
U A739 DUAL		4.30
L M300 VOLT REG.		6.75
L M301A VOLT REG.		1.90
L M308 VOLT REG.		10.75
L M309 VOLT REG.		4.50
L M373 R F		5.90
L M741 OP. AMP		1.50
PA246 SW AUDIO		4.95
TAA 300 1W AUDIO		3.65
TA 5B 5B AUDIO		6.50
TA 10B 10W AUDIO		7.50

LEDS	88c
4 LEDS	\$2.40
7 LEDS	\$6.00

ALL BARGAIN PACKS STILL AVAILABLE

### ALPHA 6 BAND BC MARINE S.W. AIRCRAFT VHF. FM. 15 TR PORTABLE



Battery or 240V AC, tuning meter, 5" spk.

540-1600 KHz	
1.8-4MHz	\$109.50
4-12MHz	
22-108 FM	
108-135 MHz	P.&P.
145-174 MHz	\$2.00

### EXPO HIGH SPEED DRILLS — 12 VOLT DC

Miniature multi purpose precision tools are invaluable to:

- o Electronic engineers
- o Model makers
- o Lapidarists
- o Engineers
- o Dental mechanics
- o Chiropractors



RELIANT  
STANDARD  
\$12.70

TITAN  
SUPER  
\$17.50  
P.P.  
\$1.00

## WILLIS TRADING CO.

PERTH G.P.O. BOX No. X2217, W.A. 6001

445 MURRAY ST.,  
PERTH, W.A.  
21 7609

## E-A Guide to Component Suppliers

As a service to readers, Electronics Australia publishes below a list of firms who stock components suitable for our construction projects. Some may specialise in particular types of component, or in kits, while others may be comprehensive stockists. For further details about any specific firm, readers should refer to their advertisements.

### NEW SOUTH WALES

A.C.E. Radio Pty Ltd, 136 Victoria Rd, Marrickville, 2048. Phone 51 7008.

John Carr Pty Ltd, 405 Sussex St, Sydney (PO Box K39, Haymarket 2000). Phone 211 5077.

Edge Electrix, 25A Burwood Rd, Burwood 2134. Phone 747 2931.

Dick Smith Electronics Pty Ltd, 162 Pacific Hwy, Gore Hill, 2065. Phone 439 5311.

Kitsets Australia (Sydney) Pty Ltd, 400 Kent St, Sydney and 1st Floor, 21 Oaks Ave, Dee Why (PO Box 176, Dee Why 2099). Phone 29 1005, 982 7500.

MS Components, 95-97 Regent St, Redfern, 2016. Phone 69 5922.

National Radio Supplies, 332 Parramatta Rd, Stanmore, 2048. Phone 56 7398.

Pre-Pak Electronics Pty Ltd, 718 Parramatta Rd, Croydon, 2132. Phone 797 6144.

Radio Despatch Service, 869 George St, Sydney 2000. Phone 211 0816.

Radio House Pty Ltd, 306-308 Pitt St and 760 George St, Sydney 2000. Phone 61 3832, 211 0171.

RCS Radio Pty Ltd, 651 Forest Rd, Bexley 2207. Phone 587 3491.

Wardrobe and Carroll Fabrications Pty Ltd, Box 330, Caringbah, 2229. Phone 525 5222.

### VICTORIA

E.D. & E. Sales Pty Ltd, 118 Lonsdale St, Melbourne, 3000. Phone 662 3506.

Imported Components, PO Box 1683P, Melbourne 3001.

Kitsets Australia (Vic) Pty Ltd, 271 Bridge Rd, Richmond. Phone 42 4651.

J. H. Magrath, 208 Little Lonsdale St, Melbourne, 3000. Phone 663 3731.

Radio Parts Pty Ltd, 562 Spencer St, Melbourne 3000. Phone 329 7888.

### SOUTH AUSTRALIA

Gerard & Goodman Pty Ltd, 192 Rundle St, Adelaide, 5000. Phone 23 2222.

Kitsets Australia (SA), 50 Grenfell St, Adelaide, 5000. Phone 87 5505.

### QUEENSLAND

Kitsets Australia (Qld) Pty Ltd, 293 St Paul's Terrace, Fortitude Valley 4006. Phone 52 8391.



# Reader Information Service

Here is a convenient and easy way for you to get additional information about products or services advertised in this issue. Just fill out the coupon stating the information you require, cut out the coupon and post to:

Reader Information Service, ELECTRONICS AUSTRALIA,  
Box 157, Beaconsfield 2015.

Note: Please list only one advertiser and one product on each coupon.

Post to: **ELECTRONICS AUSTRALIA,**  
**Box 157, Beaconsfield 2015**

Advertiser ..... Page

Product .....

Your Name .....

Address .....

Postcode .....

Position & Company ..... 5/ 73

Post to: **ELECTRONICS AUSTRALIA,**  
**Box 157, Beaconsfield 2015**

Advertiser ..... Page

Product .....

Your Name .....

Address .....

Postcode .....

Position & Company ..... 5/ 73

## CLASSIFIED ADVERTISERS

To the Advertising Manager, ELECTRONICS Australia, Box 162, Beaconsfield 2015

- Please insert the following advertisement in the ..... issue
- Tick the classification required

☐ FOR SALE ☐ WANTED ☐ READER SERVICE ☐ POSITIONS

Please write in block letters with ink or ball-point pen. Number of insertions .....

Signed: .....

Residential Address .....

State .....

- I enclose P. Note Cheque for \$ ..... being full payment for ..... lines at \$1.00 per line. (minimum 2 lines)

## Index to Advertisers

A. & R. Soanar Group	103
ACE Radio	116,117
A.C.I. Ltd.	42
Akai Australia Pty Ltd	23
Amalgamated Wireless Valve Co. Pty Ltd	7
Amplion (A'sia) Pty Ltd	93
Atram Pty Ltd	50
Audifec Australia	92
Australian General Electric Pty Ltd	32
Australian Musical Industries Pty Ltd	1BC
Australian Transistor Co	49
Bleakley Gray Corporation	19,88
British Merchandising	67
British Tobacco	OBC
BSR Australia Pty Ltd	98
John Carr Pty Ltd	80
Maurice Chapman Pty Ltd	11
Classic Radio Service	38
Commonwealth of Australia Recruiting	44
Computer Handbooks	110
Convoy International Pty Ltd	91, 108, 126
Deitch Bros.	124
Direct Disposals Trading Co.	31
J. A. Davey	52
ED & E (Sales) Pty Ltd	58
Edge Electrix	78
Electronic Exports	53,106
Encel Electronics Pty Ltd	100
Ferguson Transformers Pty Ltd	108
Richard Foot (Aust.) Pty Ltd	102
General Accessories Ltd	60,86,87
General Electronic Services	37
Haco Distributing Agencies Pty Ltd	71,73,75
Ham Radio Suppliers	125
Hi Fi Annual	99
Instrol Hi Fi Centre	6
International Correspondence Schools	81,122
International Dynamics (Agencies) Pty Ltd	40,94
IRH Components Pty Ltd	56
Jacoby Kempthorne Pty Ltd	IFC,82
Jervis Australia	36,96
Kitsets Australia Pty Ltd	64,65
Lanthur Electronics	125
Leroxy Industries Pty Ltd	4 5 68
Marconi School of Wireless	33
McGills Newsagency Pty Ltd	110
National Radio Supplies	84
N.S. Electronics	66
Natsound	97
Nationwide Electronics	109
Parameters	114
Philips Industries Ltd (Elcoma)	2
C. Pinczewski	92
Plessey Ducon Pty Ltd	12,52,78
Plessey Rola Pty Ltd	54
Radio Despatch Service	109
Radio House Pty Ltd	120
RCS Radio Pty Ltd	32
R. M. C. Recruiting	14
E. S. Rubin	104
Sato Parts Co Ltd	60
Scientific Electronics Pty Ltd	105
Peter Shalley Electronics Pty Ltd	122
Dick Smith Electronics Pty Ltd	15
Stotts Tech Correspondence College	107
T & M	61
Technical Book & Magazine Co Pty Ltd	111
Tecnico Electronics	114
Tiger Electrics Pty Ltd	95
Transformer Winders Ltd	126
United Trade Sales Pty Ltd	123
University Graham Inst Pty Ltd	76
W. H. K. Electronics	119
Walkabout	90
Wardrobe & Carroll	49
Wayne Communication Electronics	85
Weston Electronics Pty Ltd	57
Willis Trading Co	127
Wireless Institute of Australia (NSW)	115
Wonder Wool Pty Ltd	123
Zephyr Products Pty Ltd	63



# TEAC

If you'd like to know more  
write to us for the TEAC Catalogue,  
price list and franchised dealer list.

Sole Australian Distributors:  
Australian Musical Industries Pty. Ltd.,  
155 Gladstone Street, South Melbourne, Vic. 3205.  
Phone: 69 5888, Telex: AA 33037.  
619 Pacific Highway, St. Leonards, N.S.W. 2065.  
Phone: 439 6966.

The sound of perfection




Ocean Distributors: New Zealand: Direct Imports (N.Z) Ltd., 590W Southampton St., Hastings. Phone: 89-184. Fiji: D. Jeevan & Sons, 87 Cumming St., (G.P.O. Box 148), Suva. Phone: 22710. New Guinea, Paul Mow & Co., Box 449, Lae. Phone: 2953.





Why thoughtful  
people are smoking  
Hallmark



Hallmark aren't like conventional cigarettes. It's the filter system that makes them different. There are two filters; one for smoothness, the other for mildness. So the smoke is more refined. But the good tobacco flavour still comes through. Give some thought to Hallmark. They're worth thinking about.

Hallmark Dual Filter  
Worth thinking about